

FILE NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1215	99-00169-05-WR	LAKE	153	5
SUMMARY OF QUANTITIES				
CONTRACT NO. 83847		ILLINOIS	SUNSET AVENUE	

SUMMARY OF QUANTITIES					
CODE NO	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE	
				IDOT	
				ROAD 1000-2A	SIGNALS Y031-1F
* 78000300	THERMOPLASTIC PAVEMENT MARKING - LINE 5"	FOOT	1,082	1,082	
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	1,784	1,784	
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	1,322	1,322	
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	191	191	
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	2,667	2,667	
* 78001120	PAINT PAVEMENT MARKING - LINE 5"	FOOT	9,770	9,770	
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	266	266	
* 78300100	PAVEMENT MARKING REMOVAL	SQ FT	4,930	4,930	
* 78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	84	84	
* 81000600	CONDUIT IN TRENCH, 2" DIA., GALVANIZED STEEL	FOOT	5,110		5,110
* 81000700	CONDUIT IN TRENCH, 2 1/2" DIA., GALVANIZED STEEL	FOOT	153		153
* 81001000	CONDUIT IN TRENCH, 4" DIA., GALVANIZED STEEL	FOOT	175		175
* 81018500	CONDUIT PUSHED, 2" DIA., GALVANIZED STEEL	FOOT	168		168
* 81018900	CONDUIT PUSHED, 4" DIA., GALVANIZED STEEL	FOOT	207		207
* 81400100	HANDHOLE	EACH	13		13
* 81400300	DOUBLE HANDHOLE	EACH	1		1
* 85000200	MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	EACH	2		2
* 85700200	FULL-ACTUATED CONTROLLER AND TYPE IV CABINET	EACH	1		1
* 86400100	TRANSCIVER - FIBER OPTIC	EACH	2		2
* 87301215	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 2C	FOOT	1,292		1,292
* 87301225	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C	FOOT	2,862		2,862
* 87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	849		849
* 87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C	FOOT	1,629		1,629
* 87301805	ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 6 2C	FOOT	90		90
* 87502500	TRAFFIC SIGNAL POST, GALVANIZED STEEL, 16 FT.	EACH	4		4

SUMMARY OF QUANTITIES					
CODE NO	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE	
				IDOT	
				ROAD 1000-2A	SIGNALS Y031-1F
* 87600100	PEDESTRIAN PUSH-BUTTON POST, TYPE I	EACH	1		1
* 87704080	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE, 30 FT. (SPECIAL)	EACH	2		2
* 87704090	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE, 32 FT. (SPECIAL)	EACH	1		1
* 87704120	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE, 38 FT. (SPECIAL)	EACH	1		1
* 87800100	CONCRETE FOUNDATION, TYPE A	FOOT	16		16
* 87800150	CONCRETE FOUNDATION, TYPE C	FOOT	4		4
* 87800400	CONCRETE FOUNDATION, TYPE E 30-INCH DIAMETER	FOOT	60		60
* 87900200	DRILL EXISTING HANDHOLE	EACH	1		1
* 88030020	SIGNAL HEAD, LED, 1-FACE, 3-SECTION, MAST ARM MOUNTED	EACH	4		4
* 88030100	SIGNAL HEAD, LED, 1-FACE, 5-SECTION, BRACKET MOUNTED	EACH	4		4
* 88030110	SIGNAL HEAD, LED, 1-FACE, 5-SECTION, MAST ARM MOUNTED	EACH	4		4
* 88102717	PEDESTRIAN SIGNAL HEAD, LED, 1-FACE, BRACKET MOUNTED, WITH COUNTDOWN TIMER	EACH	8		8
* 88200110	TRAFFIC SIGNAL BACKPLATE, LOUVERED	EACH	8		8
* 88600600	DETECTOR LOOP REPLACEMENT	FT	72		72
* 88700200	LIGHT DETECTOR	EACH	2		2
* 88700300	LIGHT DETECTOR AMPLIFIER	EACH	1		1
* 88800100	PEDESTRIAN PUSH BUTTON	EACH	8		8
* 89000100	TEMPORARY TRAFFIC SIGNAL INSTALLATION	EACH	1		1
* 89502300	REMOVE ELECTRIC CABLE FROM CONDUIT	FOOT	258		258
* 89502375	REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	EACH	10		10
* 89502380	REMOVE EXISTING HANDHOLE	EACH	4		4
* 89502385	REMOVE EXISTING CONCRETE FOUNDATION	EACH	9	1	8

* DENOTES SPECIALTY ITEMS

DATE	
BY	
DESIGNED	
CHECKED	
NOTED	
ALIGNED	
CREATED	
FT. OF WAY CHECKED	
PLAN	
NOTE BOOK	
No.	

DATE	
BY	
DESIGNED	
CHECKED	
NOTED	
ALIGNED	
CREATED	
FT. OF WAY CHECKED	
PROFILE	
NOTE BOOK	
No.	

REVISIONS	
NAME	DATE



SUNSET AVENUE
SUMMARY OF QUANTITIES