

FILE NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1215	99-00169-05-WR	LAKE	153	22
SCHEDULES				
CONTRACT NO. 83847		ALUMINUM	SUNSET AVENUE	


28 SCHEDULE OF PROPOSED DRAINAGE STRUCTURES (2 OF 2)

STA	OFFSET	LT/RT	CB TA 4 DIA T8G 60200805	CB TA 4 DIA T24F&G 60201340	RDCB 4 DIA T24F&G 60214714	MAN TA 4 DIA T1F OL 60218300	MAN TA 4 DIA T1F CL 60218400	MAN TA 5 DIA T1F OL 60221000	MAN TA 5 DIA T1F CL 60221100	MH TA 6D TIF CL RP XX004592	RD MAN 5 DIA T1F OL 60225300	INLETS TA T1F CL 60235300	INLETS TA T8G 60236200	INLETS TA T11F&G 60236800	INLETS TA T24F&G 60237470	PRC FLAR END SEC 30 54213675	GRATING-C FL END S 30 54247150	MANHOLE ADJUSTING RING 60257700	JUNCTION CHAMBER 60247800	CIP RC END SEC 54215400	
30+62.76	41.85	RT												1							
31+03.79	41.88	RT				1								1							
31+24.90	54.37	LT																			
31+27.15	42.96	RT	1			1															
32+00.44	54.37	LT							1												
32+00.44	30.00	LT		1																	
32+00.44	44.58	RT							1												
33+75.00	30.00	LT													1						
33+74.87	30.00	RT													1						
33+74.87	42.58	RT					1														
36+04.49	30.00	LT													1						
36+04.37	30.00	RT					1								1						
36+04.37	42.58	RT					1														
36+22.14	54.50	RT												1							
36+72.18	54.50	RT												1							
36+88.52	48.34	RT	1																		
36+93.37	42.58	RT							1												
37+85.79	30.00	LT	1																		
37+85.63	42.58	RT					1														
38+81.88	30.00	LT		1																	
38+98.80	49.22	RT	1																		
38+98.64	42.58	RT					1														
40+50.12	30.00	LT													1						
40+50.12	30.00	RT													1						
40+50.12	52.58	RT					1														
41+97.13	30.00	LT													1						
41+97.13	30.00	RT													1						
41+97.13	42.58	RT					1														
42+76.40	54.50	RT												1							
43+16.92	54.50	RT												1							
43+40.88	54.40	RT	1																		
43+53.85	30.00	LT													1						
43+58.90	42.58	RT					1														
44+73.83	30.00	LT													1						
44+73.83	30.00	RT													1						
44+73.83	42.58	RT					1														
46+52.96	30.00	LT													1						
46+56.66	42.58	RT					1														
46+95.95	70.00	RT													1						
47+25.78	70.00	RT													1						
47+49.38	49.47	RT	1																		
47+67.84	42.58	RT					1														
47+67.84	30.00	LT													1						
47+67.84	30.00	RT													1						
48+79.52	30.00	LT				1															
48+79.52	42.58	RT																1			
48+79.52	30.00	RT		1																	
49+52.14	44.50	LT	1																		
50+32.73	30.00	LT													1						
50+32.73	30.00	RT													1						
50+32.73	42.58	RT																			
51+65.68	30.00	LT													1						
51+65.68	30.00	RT													1						
51+65.68	42.58	RT				1															
52+98.44	30.00	LT													1						
52+98.62	21.31	LT							1												
53+07.04	42.58	RT							1												
53+10.82	30.00	RT													1						
TOTALS			8	13	4	3	22	3	9	1	5	2	4	6	34	2	2	5	1	1	

DATE: \_\_\_\_\_ BY: \_\_\_\_\_  
 REVISIONS PLOTTED  
 ALIGNMENT CHECKED  
 RT. OF WAY CHECKED  
 PLAN  
 NOTE BOOK No. \_\_\_\_\_

DATE: \_\_\_\_\_ BY: \_\_\_\_\_  
 REVISIONS PLOTTED  
 GRADES CHECKED  
 STRUCTURE NOTATIONS CHECKED  
 PROFILE  
 NOTE BOOK No. \_\_\_\_\_

REVISIONS	
NAME	DATE

  
**Lake County**  
 Division of Transportation  
**SUNSET AVENUE**  
**QUANTITY SCHEDULES**