

35 SCHEDULE OF PAVEMENT MARKING REMOVAL

STAGE 2					
FROM	TO	WIDTH (IN)	DESCRIPTION	PAVEMENT MARKING REMOVAL (SF) 78300100	WORK ZONE PAVEMENT MARKING REMOVAL (SF) 70301000
0+76.00	9+63.49	4	DOUBLE YELLOW	591.7	
19+00.00	25+97.04	4	DOUBLE YELLOW	464.7	
24+52.00	25+97.04	6	WHITE LINE	72.5	
24+52.00	25+97.04	6	WHITE LINE	72.5	
24+75.00		-	ONLY/ARROW	36.4	
24+75.00		-	ONLY/ARROW	36.4	
26+75.00	29+30.00	5	WHITE EDGE LINE	122.2	
27+00.00	29+00.00	12	WHITE DIAGONAL	128.5	
27+13.00	30+60.00	4	DOUBLE YELLOW	231.3	
27+40.00		-	ONLY/ARROW	36.4	
28+85.00		-	ONLY/ARROW	36.4	
29+40.00	30+40.00	6	WHITE LINE	50.0	
29+50.00	30+50.00	12	YELLOW DIAGONAL	45.7	
29+70.00		-	ONLY/ARROW	36.4	
31+18.00	33+00.00	5	WHITE EDGE LINE	75.8	
31+18.00	36+30.00	4	DOUBLE YELLOW	341.3	
31+90.00		-	ONLY/ARROW	36.4	
34+83.00	36+01.00	5	WHITE EDGE LINE	49.2	
35+00.00		-	ONLY/ARROW	36.4	
35+57.00	36+30.00	6	WHITE LINE	36.5	
35+80.00		-	ONLY/ARROW	36.4	
36+78.00	44+39.00	4	YELLOW LINE	508.7	
36+78.00	44+39.00	4	YELLOW SKIP DASH	127.2	
36+98.00	38+02.00	5	WHITE EDGE LINE	43.3	
37+30.00		-	ONLY/ARROW	36.4	
38+10.00		-	ARROWS (2)	31.2	
40+80.00		-	ARROWS (2)	31.2	
43+05.00		-	ARROWS (2)	31.2	
44+39.00	46+60.00	4	DOUBLE YELLOW	147.3	
45+56.00	48+60.00	6	WHITE LINE	52.0	
45+80.00		-	ONLY/ARROW	36.4	
47+50.00	55+00.00	4	DOUBLE YELLOW	500.0	
48+50.00		-	ONLY/ARROW	36.4	
52+50.00	55+00.00	4	WHITE SKIP DASH	20.8	
53+69.00	55+00.00	6	WHITE LINE	65.5	
54+00.00		-	ONLY/ARROW	36.4	
98+00.00	99+00.00	4	DOUBLE YELLOW	66.7	
100+65.00	101+65.00	6	WHITE LINE	50.0	
STAGE 2 SUBTOTAL				4394	0

STAGE 2A					
FROM	TO	WIDTH (IN)	DESCRIPTION	PAVEMENT MARKING REMOVAL (SF) 78300100	WORK ZONE PAVEMENT MARKING REMOVAL (SF) 70301000
98+00.00	99+00.00	4	YELLOW LINE		33.3
98+00.00	99+73.00	5	WHITE EDGE LINE		72.1
100+05.00	102+63.00	5	WHITE EDGE LINE		121.3
100+63.00	102+63.00	4	DOUBLE YELLOW		133.3
102+63.00	103+23.00	4	YELLOW LINE		20.0
STAGE 2A SUBTOTAL				0	380

STAGE 3					
FROM	TO	WIDTH (IN)	DESCRIPTION	PAVEMENT MARKING REMOVAL (SF) 78300100	WORK ZONE PAVEMENT MARKING REMOVAL (SF) 70301000
2+23.00	5+00.00	4	YELLOW LINE		92.3
3+10.00	5+00.00	4	YELLOW LINE		63.3
52+53.00	55+25.00	5	WHITE EDGE LINE		126.7
53+59.00	55+00.00	4	DOUBLE YELLOW		94.0
53+59.00	55+00.00	4	YELLOW LINE		47.0
56+00.00	61+12.00	5	WHITE EDGE LINE		224.1
56+50.00	59+10.00	6	WHITE LINE	130.0	
56+50.00	61+50.00	4	DOUBLE YELLOW	333.3	
57+15.00		-	ONLY/ARROW	36.4	
58+80.00		-	ONLY/ARROW	36.4	
96+50.00	99+47.00	4	DOUBLE YELLOW		198.0
96+50.00	99+47.00	5	WHITE EDGE LINE		123.8
99+63.00		24	STOP BAR		86.0
100+05.00	103+48.00	5	WHITE EDGE LINE		153.6
100+10.00	100+91.00	5	WHITE EDGE LINE		50.7
100+60.00	103+30.00	4	DOUBLE YELLOW		180.0
STAGE 3 SUBTOTAL				536	1440

STAGE 3A					
FROM	TO	WIDTH (IN)	DESCRIPTION	PAVEMENT MARKING REMOVAL (SF) 78300100	WORK ZONE PAVEMENT MARKING REMOVAL (SF) 70301000
96+49.00	98+32.00	4	YELLOW LINE		61.0
97+36.00	98+32.00	4	YELLOW LINE		32.0
98+32.00	99+63.00	4	DOUBLE YELLOW		87.3
98+32.00	99+95.00	5	WHITE EDGE LINE		79.2
100+30.00	102+63.00	5	WHITE EDGE LINE		116.5
100+62.00	103+49.00	4	DOUBLE YELLOW		191.3
STAGE 3A SUBTOTAL				0	567

STAGE 4					
FROM	TO	WIDTH (IN)	DESCRIPTION	PAVEMENT MARKING REMOVAL (SF) 78300100	WORK ZONE PAVEMENT MARKING REMOVAL (SF) 70301000
0+76.00	3+10.00	4	YELLOW LINE		156.0
2+15.00	5+50.00	5	WHITE EDGE LINE		151.8
3+10.00	5+50.00	4	DOUBLE YELLOW		160.0
5+50.00	26+00.00	4	DOUBLE YELLOW		1366.7
27+10.00	29+10.00	6	WHITE LINE		100.0
27+10.00	46+80.00	4	DOUBLE YELLOW		1300.0
27+10.00	46+80.00	5	WHITE EDGE LINE		812.5
27+10.00		24	STOP BAR		66.0
45+80.00	46+80.00	6	WHITE LINE		50.0
47+50.00	48+50.00	6	WHITE LINE		50.0
47+50.00	54+80.00	4	DOUBLE YELLOW		486.7
47+50.00	54+80.00	5	WHITE EDGE LINE		304.2
53+70.00	54+80.00	6	WHITE LINE		55.0
54+80.00		24	STOP BAR		48.0
55+85.00	61+50.00	5	WHITE EDGE LINE		235.4
56+46.00	58+00.00	6	WHITE LINE		77.0
56+46.00	58+00.00	4	DOUBLE YELLOW		102.7
58+00.00	61+50.00	4	YELLOW LINE		116.7
58+00.00	63+75.00	4	YELLOW LINE		191.7
96+50.00	99+63.00	5	WHITE EDGE LINE		130.4
97+45.00	99+63.00	4	DOUBLE YELLOW		145.3
99+48.00		24	STOP BAR		64.0
100+30.00	103+46.00	4	DOUBLE YELLOW		210.7
101+79.00	103+46.00	5	WHITE EDGE LINE		94.2
STAGE 4 SUBTOTAL				0	6475

STAGE 5					
FROM	TO	WIDTH (IN)	DESCRIPTION	PAVEMENT MARKING REMOVAL (SF) 78300100	WORK ZONE PAVEMENT MARKING REMOVAL (SF) 70301000
0+76.00	25+92.00	4	YELLOW LINE		838.7
0+76.00	25+92.00	4	YELLOW LINE		838.7
24+50.00	25+92.00	6	WHITE LINE		71.0
25+92.00		24	STOP BAR		50.0
27+40.00	29+30.00	4	DOUBLE YELLOW		126.7
27+40.00	30+20.00	4	YELLOW LINE		93.3
27+40.00	30+20.00	4	YELLOW LINE		93.3
29+30.00	35+50.00	4	YELLOW LINE		206.7
29+30.00	35+50.00	4	YELLOW LINE		206.7
STAGE 5 SUBTOTAL				0	2525


TOTAL		PAVEMENT MARKING REMOVAL (SF) 78300100	WORK ZONE PAVEMENT MARKING REMOVAL (SF) 70301000
TOTAL		4930	11387

36 SCHEDULE OF SHORT TERM PAVEMENT MARKINGS					
FROM	TO	LT/RT	DESCRIPTION	SHORT TERM PAVEMENT MARKINGS (FT) 70300100	PAVEMENT MARKING TAPE, TYPE III 4" (FT) 70300520
0+76.23	25+93.84	RT	4" WHITE LINE	228.9	228.9
5+36.02	25+97.45	LT	4" WHITE LINE	187.4	187.4
27+20.65	46+60.65	LT	4" WHITE LINE	176.4	176.4
27+32.01	46+67.92	RT	4" WHITE LINE	176.0	176.0
47+65.82	54+96.98	LT	4" WHITE LINE	66.5	66.5
47+65.82	54+96.33	RT	4" WHITE LINE	66.4	66.4
56+48.23	64+00.00	LT	4" WHITE LINE	68.3	68.3
SUBTOTAL				969.9	969.9
31+40.19	43+23.19	LT	4" YELLOW LINE	107.5	107.5
31+40.32	43+23.18	RT	4" YELLOW LINE	107.5	107.5
50+30.89	52+26.92	LT	4" YELLOW LINE	17.8	17.8
50+30.94	52+26.94	RT	4" YELLOW LINE	17.8	17.8
60+36.52	63+76.00	LT	4" YELLOW LINE	30.9	30.9
60+36.56	63+76.00	RT	4" YELLOW LINE	30.9	30.9
SUBTOTAL				312.4	312.4
31+40.19	43+23.19	LT	4" YELLOW LINE	107.5	107.5
31+40.32	43+23.18	RT	4" YELLOW LINE	107.5	107.5
50+30.89	52+26.92	LT	4" YELLOW LINE	17.8	17.8
50+30.94	52+26.94	RT	4" YELLOW LINE	17.8	17.8
60+36.52	63+76.00	LT	4" YELLOW LINE	30.9	30.9
60+36.56	63+76.00	RT	4" YELLOW LINE	30.9	30.9
SUBTOTAL				312.4	312.4
0+71.01	9+91.68	RT	4" DOUBLE YELLOW	167.4	167.4
5+36.01	9+91.40	LT	4" DOUBLE YELLOW	82.8	82.8
20+70.80	25+93.72	LT	4" DOUBLE YELLOW	95.1	95.1
20+70.78	23+95.59	RT	4" DOUBLE YELLOW	59.1	59.1
27+13.83	31+40.32	RT	4" DOUBLE YELLOW	77.5	77.5
29+29.49	31+45.59	LT	4" DOUBLE YELLOW	39.3	39.3
43+17.20	45+31.90	RT	4" DOUBLE YELLOW	39.0	39.0
43+23.19	46+67.97	LT	4" DOUBLE YELLOW	62.7	62.7
47+65.84	50+30.94	RT	4" DOUBLE YELLOW	48.2	48.2
52+26.92	54+96.97	LT	4" DOUBLE YELLOW	49.1	49.1
51+46.40	61+50.03	RT	4" DOUBLE YELLOW	182.5	182.5
56+46.40	60+36.51	LT/RT	4" DOUBLE YELLOW	70.9	70.9
97+43.00	99+39.00	LT	4" DOUBLE YELLOW	35.6	35.6
100+61.00	103+51.00	LT	4" DOUBLE YELLOW	52.7	52.7
101+83.00	103+53.00	RT	4" DOUBLE YELLOW	30.9	30.9
SUBTOTAL				1092.9	1092.9
3+10.00	5+36.02	LT	4" WHITE LINE	226.0	226.0
3+10.00	5+36.02	RT	4" WHITE LINE	226.0	226.0
23+96.06	25+93.97	LT	4" WHITE LINE	197.9	197.9
27+13.46	29+10.32	LT	4" WHITE LINE	196.9	196.9
45+53.06	46+68.01	RT	4" WHITE LINE	115.0	115.0
47+65.78	48+80.84	LT	4" WHITE LINE	115.1	115.1
53+62.06	54+97.05	RT	4" WHITE LINE	135.0	135.0
56+48.32	59+10.34	LT	4" WHITE LINE	262.0	262.0
97+41.80	99+38.51	RT	4" WHITE LINE	196.7	196.7
100+61.45	101+82.95	LT	4" WHITE LINE	121.5	121.5
SUBTOTAL				1792.0	1792.0
5+25.83			ARROW + "ONLY"	109.0	109.0
5+25.83			ARROW + "ONLY"	109.0	109.0
5+25.83			ARROW + "ONLY"	109.0	109.0
24+05.66			ARROW + "ONLY"	109.0	109.0
29+00.00			ARROW + "ONLY"	109.0	109.0
32+31.44			ARROW + "ONLY"	90.0	90.0
34+31.44			ARROW + "ONLY"	90.0	90.0
37+31.44			ARROW + "ONLY"	90.0	90.0
40+32.44			ARROW + "ONLY"	90.0	90.0
42+31.00			ARROW + "ONLY"	90.0	90.0
45+63.03			ARROW + "ONLY"	109.0	109.0
48+71.00			ARROW + "ONLY"	109.0	109.0
50+49.28			ARROW + "ONLY"	90.0	90.0
52+09.00			ARROW + "ONLY"	90.0	90.0
53+72.05			ARROW + "ONLY"	109.0	109.0
57+42.21			ARROW + "ONLY"	109.0	109.0
59+00.00			ARROW + "ONLY"	109.0	109.0
97+52.00			ARROW + "ONLY"	109.0	109.0
101+73.00			ARROW + "ONLY"	109.0	109.0
SUBTOTAL				1938.0	1938.0
TOTAL				6418	6418

DATE: _____ BY: _____
 SURVEYED: _____
 PLOTTED: _____
 CHECKED: _____
 ALIGNED: _____
 NO. OF SHEETS: _____
 PLAN: _____

DATE: _____ BY: _____
 SURVEYED: _____
 PLOTTED: _____
 CHECKED: _____
 ALIGNED: _____
 NO. OF SHEETS: _____
 PROFILE: _____

REVISIONS	
NAME	DATE


 Lake County
 Division of Transportation
SUNSET AVENUE
QUANTITY SCHEDULES