F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1394	97-00226-00-FP	COOK	80	4
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

CONTRACT NO.: 83898

SUMMARY OF QUANTITIES

CODE NO.	DESCRIPTION	UNIT	TOTALS	DIVISION STREET ROADWAY 1000-2A QUANTITY	AUGUSTA STREET ROADWAY 1000-2A QUANTITY
20101000	TEMPORARY FENCE	FOOT	400	300	100
• 20101100	TREE TRUNK PROTECTION	EACH	20	10	10
• 20101200	TREE ROOT PRUNING	EACH	20	10	10
• 20101350	TREE PRUNING (OVER 10 INCH DIAMETER)	EACH	20	10	10
• 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	100	50	50
• 25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	100	50	50
• 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	100	50	50
• 25200200	SUPPLEMENTAL WATERING	UNIT	50	35	15
20200100	EARTH EXCAVATION	CU YD	400	300	100
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	1,300	900	400
20700420	POROUS GRANULAR EMBANKMENT, SUBGRADE	CU YD	1,300	900	400
20800150	TRENCH BACKFILL	CU YD	150	100	50
• 21101610	TOPSOIL FURNISH AND PLACE, 3"	SQ YD	1,300	1,000	300
25200110	SODDING, SALT TOLERANT	SQ YD	1,300	1,000	300
28000510	INLET FILTERS	EACH	103	80	23
31101200	SUB-BASE GRANULAR MATERIAL, TYPE B 4"	SQ YD	1,283	1,036	247
35800100	PREPARATION OF BASE	SQ YD	35,000	26,928	8,072
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	40	40	0
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	2,800	2,154	646
40600300	AGGREGATE (PRIME COAT)	TON	70	54	16
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	1,481	1,131	350
40600895	CONSTRUCTING TEST STRIP	EACH	2	2	0
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	1,350	1,100	250
40603085	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70	TON	4,850	3,700	1,150
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	3,350	2,500	850
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD	160	100	60
42400800	DETECTABLE WARNINGS	SQ FT	160	136	24
44000198	HOT-MIX ASPHALT SURFACE REMOVAL (VARIABLE DEPTH)	SQ YD	35,028	26,928	8,100
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	160	100	60
44001700	COMBINATION CC&G REMOVAL AND REPLACEMENT	FOOT	6,700	5,200	1,500
44201713	CLASS D PATCHES, TYPE I, 6 INCH	SQ YD	376	300	76
44201717	CLASS D PATCHES, TYPE II, 6 INCH	SQ YD	190	150	40
44201721	CLASS D PATCHES, TYPE III, 6 INCH	SQ YD	250	200	50
44201723	CLASS D PATCHES, TYPE IV, 6 INCH	SQ YD	1,200	850	350
56500600	DOMESTIC WATER SERVICE BOXES TO BE ADJUSTED	EACH	25	20	5
60200105	CATCH BASINS, TYPE A, 4'- DIAMETER, TJF, OL	EACH	1	1	0
60218400	MANHOLES, TYPE A, 4'- DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1	1	0
60234200	INLETS, TYPE A, TYPE 1 FRAME, OPEN LID	EACH	1	1	0

• SPECIALTY ITEMS

STRAND ASSOCIATES, INC. ENGINEERS

REVISIONS NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

FAU 1394
DIVISION STREET/AUGUSTA STREET

SUMMARY OF QUANTITIES

SCALE: VERT. HORIZ.
DATE 1/18/2007
DRAWN BY JBH
CHECKED BY JDM

FILENAME: s:\006\281-8900\280\280\internal\augusta\summary of quantities-augusta.dgn DATE: 1/18/2007 TIME: 8:14:59 AM