

FAU RTE 1369	SECTION 07-00053-00-RS	COUNTY DUPAGE	TOTAL SHEETS 12	SHEET NO. 3
SCHICK RD.		PROJECT NO. M-8003(760)		
F.H.W.A. REG. ILLINOIS		CONTRACT NO. 83901		

L23 07C

NO.	ITEM	UNIT	QUANTITY	NON-PARTICIPATING ITEM
			1000-2A	
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ.YD.	700	
25000400	NITROGEN FERTILIZER NUTRIENT	LB	9	
25000500	PHOSPHOROUS FERTILIZER NUTRIENT	LB	9	
25000600	POTASSIUM FERTILIZER NUTRIENT	LB	9	
25200110	SODDING, SALT TOLERANT	SQ.YD.	700	
25200200	SUPPLEMENTAL WATERING	UNIT	10	
40600635	LEVELING BINDER (Machine Method), N70	TON	1050	
40603340	HOT-MIX ASPHALT Surface Course, MIX "D", N70	TON	2450	
40800010	BIT. MATERIALS (PRIME COAT)	GAL.	2500	
40800030	AGGREGATE (PRIME COAT)	TON	75	
42001300	PROTECTIVE COAT	SQ.YD.	1060	
42300200	P.C.C. DRIVEWAY PAVEMENT 6"	SQ.YD.	50	
42400800	DETECTABLE WARNINGS	SQ.FT.	1250	
44000157	HOT-MIX ASPHALT SURFACE REMOVAL - 2"	SQ.YD.	25017	
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ.YD.	50	
44001700	COMBINATION CONCRETE C & G REMOVE & REPLACE	FT.	4800	
44200934	CLASS B PATCH - TYPE II, 8"	SQ.YD.	500	
44200942	CLASS B PATCH - TYPE III, 8"	SQ.YD.	1000	
44200944	CLASS B PATCH - TYPE IV, 8"	SQ.YD.	1000	
44300100	AREA REFLECTIVE CRACK CONTROL TREATMENT	SQ.YD.	25017	
55019500	STORM SEWER TYPE 1 RCP, CLASS IV 12"	FT.	8	
60107700	PIPE UNDERDRAINS, 6"	FT.	0	50
60237600	INLETS, TYPE A, TYPE B-24 FRAME & GRATE	EACH	1	
60238500	INLETS, TYPE A, WITH SALVAGED FRAME & GRATE	EACH	6	
60242400	INLETS, SPECIAL	EACH	0	1
60260100	INLETS TO BE ADJUSTED	EACH	28	
60266500	VALVE VAULTS TO BE REMOVED	EACH	2	
60300305	FRAME & LID TO BE ADJUSTED	EACH	42	
60500060	REMOVING INLETS	EACH	7	
67100100	MOBILIZATION	L. SUM	1	
70102620	TRAFFIC CONTROL & PROTECTION, STANDARD 701501	L. SUM	1	
70102640	TRAFFIC CONTROL & PROTECTION, STANDARD 701801	L. SUM	1	
70300100	SHORT TERM PAVEMENT MARKING	FT.	7000	
* 78000100	THERMOPLASTIC PAVEMENT MARKING, LETTER & SYMBOLS	SQ.FT.	319	
* 78000200	THERMOPLASTIC PAVEMENT MARKING, LINE - 4"	FT.	11750	
* 78000400	THERMOPLASTIC PAVEMENT MARKING, LINE - 6"	FT.	1250	
* 78000600	THERMOPLASTIC PAVEMENT MARKING, LINE - 12"	FT.	250	
* 78000650	THERMOPLASTIC PAVEMENT MARKING, LINE - 24"	FT.	110	
* 88600100	DETECTOR LOOP - TYPE 1	FT.	1050	
XX001306	SIDEWALK REMOVE & REPLACE	SQ.FT.	3500	
XX006866	VALVE VAULTS, 4'-DIAM., WITH SALVAGED FRAME & GRATE	EACH	2	

* SPECIALITY ITEM

HOT-MIX ASPHALT MIXTURE REQUIREMENTS		
ITEM	AC TYPE	VOIDS
HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	PG 64-22	4% @ 70 Gyr.
LEVELING BINDER (MACHINE METHOD), N70	PG 64-22/58-22	4% @ 70 Gyr.

* THE UNIT WEIGHT USED TO CALCULATE ALL HOT-MIX SURFACE MIXTURE QUANTITIES IS 112 LBS./SQ.YD./IN.
 * WHEN RAP EXCEEDS 20%, THE NEW ASPHALT BINDER IN THE MIX SHALL BE PG 58-22

