



SCHEDULE OF LIGHTING EQUIPMENT

QTY	LABEL	ITEM	LOCATION
TOUHY AVENUE			
1	TB4	STREET LUMINAIRE, POLE, FOUNDATION	STA. 30+92 O/S 32.0'R
1	TC4	STREET LUMINAIRE, POLE, FOUNDATION	STA. 30+93 O/S 32.0'L
1	TD9	STREET LUMINAIRE, POLE, FOUNDATION	STA. 31+80 O/S 32.0'R
1	TA9	STREET LUMINAIRE, POLE, FOUNDATION	STA. 31+79 O/S 32.0'L
1	TD10	PEDEST. LUMINAIRE, POLE, FOUNDATION	STA. 32+33 O/S 33.0'R
1	TA10	PEDEST. LUMINAIRE, POLE, FOUNDATION	STA. 32+59 O/S 32.5'L
1	TB8	STREET LUMINAIRE, POLE, FOUNDATION	STA. 33+39 O/S 32.0'R
1	TC8	STREET LUMINAIRE, POLE, FOUNDATION	STA. 33+38 O/S 32.0'L
1	T	LIGHTING CONTROLLER CABINET	STA. 33+74 O/S 68.0'L
1	TB9	PEDEST. LUMINAIRE, POLE, FOUNDATION	STA. 34+09 O/S 33.0'R
1	TC9	PEDEST. LUMINAIRE, POLE, FOUNDATION	STA. 34+08 O/S 32.5'L
1	TD11	STREET LUMINAIRE, POLE, FOUNDATION	STA. 34+79 O/S 32.0'R
1	TA11	STREET LUMINAIRE, POLE, FOUNDATION	STA. 34+78 O/S 32.0'L
1	TD12	PEDEST. LUMINAIRE, POLE, FOUNDATION	STA. 35+50 O/S 33.0'R
1	TA12	PEDEST. LUMINAIRE, POLE, FOUNDATION	STA. 35+48 O/S 32.5'L
CRAWFORD AVENUE			
1	TB7	STREET LUMINAIRE, POLE, FOUNDATION	STA. 10+10 O/S 31.0'R
1	TD8	STREET LUMINAIRE, POLE, FOUNDATION	STA. 10+11 O/S 31.0'L
1	TB6	PEDEST. LUMINAIRE, POLE, FOUNDATION	STA. 11+06 O/S 32.0'R
1	TD7	PEDEST. LUMINAIRE, POLE, FOUNDATION	STA. 11+16 O/S 33.0'L
1	TB5	STREET LUMINAIRE, POLE, FOUNDATION	STA. 12+81 O/S 31.5'R
1	TD6	STREET LUMINAIRE, POLE, FOUNDATION	STA. 12+80 O/S 31.5'L
1	TC5	STREET LUMINAIRE, POLE, FOUNDATION	STA. 13+15 O/S 31.0'R
1	TA6	STREET LUMINAIRE, POLE, FOUNDATION	STA. 13+16 O/S 31.0'L
1	TC6	PEDEST. LUMINAIRE, POLE, FOUNDATION	STA. 13+37 O/S 32.5'R
1	TA7	PEDEST. LUMINAIRE, POLE, FOUNDATION	STA. 13+38 O/S 32.5'L
1	TC7	STREET LUMINAIRE, POLE, FOUNDATION	STA. 14+06 O/S 31.5'R
1	TA8	STREET LUMINAIRE, POLE, FOUNDATION	STA. 14+04 O/S 31.5'L

SITE PLAN - LIGHTING

SCALE: 1"=20'-0"
 NOTES:
 1. REFER TO SHEET 23 FOR LIGHTING NOTES.

LEGEND

- STREET LIGHTING POLE WITH 250W MH LUMINAIRE, REFER TO POLE DETAIL ON DRAWING 23.
- PEDESTRIAN LIGHTING POLE WITH 50 W MH LUMINAIRE, REFER TO ORNAMENTAL LIGHTING DETAIL ON DRAWING 24.
- #6 AWG CONDUCTOR AND #6 AWG GROUND IN CONDUIT, A MINIMUM OF 48" BELOW GRADE. REFER TO DRAWING 21 FOR NUMBER OF CONDUCTORS UNLESS NOTED OTHERWISE.
- IDOT PAY ITEM #81700120 (EACH CONDUCTOR) #81018500 (PUSHED) #81000600 (TRENCH)
- LIGHTING CONTROLLER, REFER TO DETAIL 1/25.

KJWW ENGINEERING CONSULTANTS
 Experience you can build on.
 1771 W. DELHI ROAD, SUITE 300
 HAWKINSVILLE, IL 60893
 630.517.2520 FAX: 630.517.2531
 www.kjww.com PROJECT #06-015043
 © 2007 KJWW, P.C.

PLANS PREPARED BY:
GEWALT HAMILTON ASSOCIATES, INC.
 Consulting Engineers & Surveyors
 852 Forest Ridge Drive
 Vernon Hills, IL 60061
 (847) 478-9759
 (847) 478-9751 Fax

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SITE PLAN - LIGHTING
 BUSINESS DISTRICT IMPROVEMENTS
 TOUHY AVE. AND CRAWFORD AVE.
 SECTION # 06 - 00048 - 00 -RS
 SCALE: N.T.S.
 DATE: 11-2-06
 DRAWN BY: JFF
 DESIGNED BY: SWS
 CHECKED BY: SDB

E:\06\06-00048-00-RS\Lighting - 11-2-06\11-2-06-00048-00-RS.dwg Scale: 1"=20' Thursday, February 13, 2007 9:40am By: jff