

SECTION	COUNTY	TOTAL SHEET NO.
05-00012-00-PP	HENRY	75 17
TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT

# SCHEDULE OF QUANTITIES

<u>42001300</u>	<u>PROTECTIVE COAT</u>	<u>S. Y.</u>
	STA. 10+16.37 TO 23+75	7,922
	<u>TOTAL</u>	<u>7,922</u>

<u>42300300</u>	<u>PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 7 INCH</u>	<u>S. Y.</u>
	RT. STA. 11+20.00	6
	RT. STA. 11+98.76	16
	LT. STA. 12+10.16	15
	RT. STA. 12+10.16	14
	RT. STA. 12+84.06	24
	RT. STA. 15+33.74	19
	LT. STA. 15+54.33	21
	RT. STA. 15+18.95	23
	RT. STA. 17+02.14	27
	RT. STA. 17+45.43	27
	RT. STA. 20+71.24	15
	<u>TOTAL</u>	<u>207</u>

<u>42400200</u>	<u>PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH</u>	<u>S. F.</u>
	LT. STA. 10+22 TO 13+95	2,421
	RT. STA. 10+22 TO 13+95	1,545
	▪ LT. STA. 14+29 TO 18+15	4,177
	▪ RT. STA. 14+29 TO 18+15	3,803
	▪ LT. STA. 18+48 TO 20+70	2,352
	▪ RT. STA. 18+48 TO 20+34	1,903
	▪ RT. STA. 20+55 TO 20+65.45	27
	▪ LT. STA. 20+70 TO 21+22.5	113
	▪ RT. STA. 21+17.46 TO 21+36	64
	▪ LT. STA. 21+22.5 TO 21+81	900
	RT. STA. 21+70 TO 22+62.3	546
	LT. STA. 22+14 TO 23+75	869
	<u>TOTAL</u>	<u>18,720</u>

<u>42400800</u>	<u>DETECTABLE WARNINGS</u>	<u>S. F.</u>
	LT. STA. 9+52	8.0
	LT. STA. 10+27	8.0
	RT. STA. 10+27	8.0
	LT. STA. 10+43	8.0
	RT. STA. 10+43	8.0
	<u>TOTAL</u>	<u>40.0</u>

<u>44000100</u>	<u>PAVEMENT REMOVAL</u>	<u>S. Y.</u>
	STA. 9+15 TO 9+65	108
	STA. 10+16.37 TO 24+20	10,010
	STA. 24+22 TO 24+81	62
	<u>TOTAL</u>	<u>10,180</u>

<u>44000200</u>	<u>DRIVEWAY PAVEMENT REMOVAL</u>	<u>S. Y.</u>
	RT. STA. 11+20.00	9
	RT. STA. 11+98.76	11
	LT. STA. 12+10.16	10
	RT. STA. 12+10.16	6
	RT. STA. 12+84.06	16
	RT. STA. 15+33.74	17
	LT. STA. 15+54.33	13
	RT. STA. 15+18.95	14
	RT. STA. 17+02.14	22
	RT. STA. 17+45.43	22
	RT. STA. 20+71.24	7
	<u>TOTAL</u>	<u>147</u>

<u>44000600</u>	<u>SIDEWALK REMOVAL</u>	<u>S. F.</u>
	LT. STA. 9+52	36
	RT. STA. 9+99.22 TO 14+12.19	1,386
	LT. STA. 9+99.22 TO 14+12.19	1,967
	▪ RT. STA. 14+12.19 TO 18+32.06	2,758
	▪ LT. STA. 14+12.19 TO 18+32.06	3,430
	▪ RT. STA. 18+32.06 TO 21+75.31	2,784
	▪ RT. STA. 18+32.06 TO 21+98.07	2,789
	RT. STA. 21+75.31 TO 24+20	565
	LT. STA. 21+98.07 TO 24+20	359
	<u>TOTAL</u>	<u>16,074</u>

<u>44201747</u>	<u>CLASS D PATCHES, TYPE IV, 8 INCH</u>	<u>S. Y.</u>
	STA. 9+15.5 TO 9+70.5	101
	STA. 24+22 TO 24+81	62
	<u>TOTAL</u>	<u>163</u>

<u>44213200</u>	<u>SAW CUTS</u>	<u>FT.</u>
	LT. STA. 9+15.5 TO 9+70.5	101
	LT./RT. STA. 10+16.37	112
	CENTER STREET LT.	55
	CENTER STREET RT.	42
	EXCHANGE STREET LT.	48
	EXCHANGE STREET RT.	42
	DEPOT STREET RT.	25
	LOCUST STREET LT.	53
	LT./RT. STA. 24+20	39
	RT. STA. 24+22 TO 24+81	111
	<u>TOTAL</u>	<u>628</u>

<u>48100100</u>	<u>AGGREGATE SHOULDERS, TYPE A</u>	<u>TON</u>
	RT. STA. 23+75 TO 24+14	2
	<u>TOTAL</u>	<u>2</u>

• ITEP ELIGIBLE ITEMS