

SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
05-00012-00-FP	HENRY	75	20
STA.		TO STA.	
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT

# SCHEDULE OF QUANTITIES

78001110	PAINT PAVEMENT MARKING, LINE 4"	FT.
	SOLID WHITE	
	RT. STA. 10+65.7 TO 10+85.7 (PARALLEL PARKING)	20.3
	LT. STA. 10+65.7 TO 11+75.7 (PARALLEL PARKING)	64.3
	RT. STA. 11+39 TO 11+79 (PARALLEL PARKING)	31.3
	LT. STA. 12+30.9 TO 13+58.9 (PARALLEL PARKING)	75.3
	RT. STA. 12+36.8 TO 12+56.8 (PARALLEL PARKING)	20.3
	RT. STA. 13+19 TO 13+59 (PARALLEL PARKING)	31.3
	LT. STA. 14+52.2 TO 14+92.5 (ANGLE PARKING)	98.5
	RT. STA. 14+81.7 TO 15+19.9 (ANGLE PARKING)	98.5
	LT. STA. 15+11.6 (ACCESSIBILITY PARKING)	122.8
	LT. STA. 15+72.3 (ACCESSIBILITY PARKING)	122.8
	LT. STA. 15+91.4 TO 16+72.6 (ANGLE PARKING)	320.2
	RT. STA. 16+22.6 TO 16+73.4 (ANGLE PARKING)	123.2
	LT. STA. 17+63.3 (ACCESSIBILITY PARKING)	122.8
	LT. STA. 18+75.2 (ACCESSIBILITY PARKING)	122.8
	LT. STA. 18+94.3 TO 19+70.6 (ANGLE PARKING)	172.4
	RT. STA. 19+12.4 TO 20+46.4 (ANGLE PARKING)	270.9
	LT. STA. 19+89.8 (ACCESSIBILITY PARKING)	122.8
	LT. STA. 19+93.3 TO 20+95.2 (ANGLE PARKING)	197.0
	RT. STA. 22+22.8 TO 22+48.2 (ANGLE PARKING)	73.9
	LT. STA. 22+69.9 (ACCESSIBILITY PARKING)	122.8
	LT. STA. 22+88.2 TO 23+51.9 (ANGLE PARKING)	147.8
	<b>TOTAL</b>	<b>2,482.0</b>
78001180	PAINT PAVEMENT MARKING, LINE 24"	FT.
	SOLID WHITE	
	STA. 10+42.7 (CROSSWALK)	36.0
	<b>TOTAL</b>	<b>36.0</b>
LR430050	CONCRETE PAVER SIDEWALK	S. Y.
	CENTER STREET	
	• LT. STA. 13+83	2.0
	• RT. STA. 13+83	2.0
	• LT. STA. 13+93	2.0
	• RT. STA. 13+93	2.0
	• LT. STA. 14+32	2.0
	• RT. STA. 14+32	2.0
	• LT. STA. 14+42	2.0
	• RT. STA. 14+42	2.0
	EXCHANGE STREET	2.0
	• LT. STA. 18+03	2.0
	• RT. STA. 18+03	2.0
	• LT. STA. 18+13	2.0
	• RT. STA. 18+13	2.0
	• LT. STA. 18+52	2.0
	• RT. STA. 18+52	2.0
	• LT. STA. 18+62	2.0
	• RT. STA. 18+62	2.0
	MIDBLOCK	
	• LT. STA. 19+87	1.6
	DEPOT STREET	
	• RT. STA. 21+29	2.0
	• RT. STA. 21+31	2.0
	• RT. STA. 21+78	2.0
	LOCUST STREET	
	• LT. STA. 21+61	2.0
	• LT. STA. 21+79	2.0
	• LT. STA. 22+17	2.0
	NORTH OF LOCUST AND DEPOT STREETS	
	LT. STA. 22+54	1.6
	RT. STA. 22+54	1.6
	• ITEP ELIGIBLE ITEMS	<b>TOTAL 52.8</b>

X0322033	STORM SEWER (WATER MAIN REQUIREMENTS) 12 INCH	FT.
	PROSPECT STREET	
	LT. & RT. STA. 13+64	42
	LT. & RT. STA. 16+13.5	56
	LT. & RT. STA. 17+69.5 TO 17+75	57
	LT. & RT. STA. 19+50	56
	LT. & RT. STA. 21+07.5 TO 21+32.5	62
	LT. & RT. STA. 23+49 TO 24+00	72
	<b>TOTAL</b>	<b>345</b>
X0322034	STORM SEWER (WATER MAIN REQUIREMENTS) 15 INCH	FT.
	PROSPECT STREET	
	RT. STA. 13+65 TO 14+00	35
	<b>TOTAL</b>	<b>35</b>
X0322035	STORM SEWER (WATER MAIN REQUIREMENTS) 18 INCH	FT.
	PROSPECT STREET	
	29' RT. STA. 18+38.5 TO 18+59.5	21
	<b>TOTAL</b>	<b>21</b>
X0323185	DUCTILE IRON WATER MAIN TEE, 6"X6"	EACH
	18' LT. STA. 10+13.18	1
	18' LT. STA. 10+33	1
	46' LT. STA. 21+77	1
	<b>TOTAL</b>	<b>3</b>
X0323821	DUCTILE IRON WATER MAIN REDUCER, 10"X8"	EACH
	11' LT. STA. 9+64	1
	9' LT. STA. 9+64	1
	<b>TOTAL</b>	<b>2</b>
X0324444	DUCTILE IRON WATER MAIN FITTINGS 10"X10" CROSS	EACH
	9' LT. STA. 9+64	1
	9' LT. STA. 13+89	1
	9' LT. STA. 18+49	1
	<b>TOTAL</b>	<b>3</b>
X0324448	DUCTILE IRON WATER MAIN FITTINGS 10" 45 DEGREE BEND	EACH
	10' LT. STA. 9+45	1
	3' RT. STA. 9+33	1
	9' LT. STA. 9+65 (VERTICAL)	1
	9' LT. STA. 9+67 (VERTICAL)	1
	9' LT. STA. 10+30 (VERTICAL)	1
	9' LT. STA. 10+32 (VERTICAL)	1
	<b>TOTAL</b>	<b>6</b>