

SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
05-00012-00-FP	HENRY	75	21
TO STA.			
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT	

SCHEDULE OF QUANTITIES

<u>X0324928</u>	<u>VALVE GATE, 6" MJRW & BOX</u>	<u>FT.</u>
	18' LT. STA. 10+28	1
	55' LT. STA. 21+77	1
	10' LT. STA. 23+93	1
	<u>TOTAL</u>	<u>3</u>

<u>X0325143</u>	<u>FILLING EXISTING VAULT</u>	<u>EACH</u>
	• LT. STA. 19+20	1
	<u>TOTAL</u>	<u>1</u>

<u>X0325340</u>	<u>FIRE HYDRANT WITH AUXILIARY VALVE AND VALVE BOX</u>	<u>EACH</u>
	35' LT. STA. 10+33	1
	50' RT. STA. 13+95	1
	46' RT. STA. 18+54	1
	46' LT. STA. 21+70	1
	<u>TOTAL</u>	<u>4</u>

<u>XX000739</u>	<u>CURB STOP & BOX 1 INCH</u>	<u>EACH</u>
	LT. STA. 11+44	1
	RT. STA. 11+78	1
	RT. STA. 20+20	1
	LT. STA. 13+10	1
	RT. STA. 13+16	1
	LT. STA. 14+34	1
	LT. STA. 14+38	1
	RT. STA. 14+96	1
	LT. STA. 15+19	1
	RT. STA. 15+62	1
	LT. STA. 16+02	1
	RT. STA. 16+10	1
	LT. STA. 16+28	1
	LT. STA. 16+33	1
	LT. STA. 16+77	1
	LT. STA. 16+83	1
	LT. STA. 17+29	1
	LT. STA. 17+33	1
	LT. STA. 17+81	1
	RT. STA. 18+79	1
	LT. STA. 18+84	1
	RT. STA. 19+10	1
	LT. STA. 19+27	1
	RT. STA. 19+43	1
	RT. STA. 19+72	1
	LT. STA. 19+84	1
	RT. STA. 20+04	1
	LT. STA. 20+10	1
	LT. STA. 20+28	1
	RT. STA. 20+35	1
	LT. STA. 20+55	1
	RT. STA. 20+71	1
	LT. STA. 20+84	1
	LT. STA. 21+38	1
	RT. STA. 21+94	1
	LT. STA. 22+35	1
	LT. STA. 22+66	1
	<u>TOTAL</u>	<u>37</u>

<u>XX001484</u>	<u>ROOF DRAIN GUTTER OUTLET</u>	<u>EA.</u>
	• RT. STA. 17+70.5	1
	• 50.75' LT. STA. 18+60	1
	• LT. STA. 19+14	1
	<u>TOTAL</u>	<u>3</u>

<u>XX003528</u>	<u>DUCTILE IRON WATER MAIN FITTING-8" PLUG</u>	<u>EACH</u>
	12' LT. STA. 9+64	1
	8' LT. STA. 9+64	1
	<u>TOTAL</u>	<u>2</u>

<u>XX003795</u>	<u>VALVE GATE, 8" MJRW & BOX</u>	<u>EACH</u>
	12' LT. STA. 9+64	1
	8' LT. STA. 9+64	1
	<u>TOTAL</u>	<u>2</u>

<u>XX003799</u>	<u>COPPER SERVICE, TYPE K 1"</u>	<u>FT.</u>
	LT. STA. 11+44	20
	RT. STA. 11+78	40
	RT. STA. 12+20	40
	LT. STA. 13+10	20
	RT. STA. 13+16	40
	LT. STA. 14+34	30
	LT. STA. 14+38	30
	RT. STA. 14+96	50
	RT. STA. 15+62	50
	LT. STA. 15+19	30
	LT. STA. 16+02	30
	RT. STA. 16+10	50
	LT. STA. 16+28	30
	LT. STA. 16+33	30
	LT. STA. 16+77	30
	LT. STA. 16+83	30
	LT. STA. 17+29	30
	LT. STA. 17+33	30
	LT. STA. 17+81	30
	RT. STA. 18+79	50
	LT. STA. 18+84	30
	RT. STA. 19+10	50
	LT. STA. 19+27	30
	RT. STA. 19+43	50
	RT. STA. 19+72	50
	LT. STA. 19+84	30
	RT. STA. 20+04	50
	LT. STA. 20+10	30
	LT. STA. 20+28	30
	RT. STA. 20+35	50
	LT. STA. 20+55	30
	RT. STA. 20+71	50
	LT. STA. 20+84	30
	LT. STA. 21+38	30
	RT. STA. 21+94	40
	LT. STA. 22+35	25
	LT. STA. 22+66	30
	<u>TOTAL</u>	<u>1,325</u>

• ITEP ELIGIBLE ITEMS