

SCHEDULE OF QUANTITIES

SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
05-00012-00-FF	HENRY	75	22
STA. TO STA.		FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT	

XX004065	LINE STOPS 8"	EACH
	48' LT. STA. 18+44	1
	47' RT. STA. 18+44	1
	TOTAL	2

XX004941	PCC SIDEWALK, TEXTURED, COLORED, 5"	S. F.
	* LT. STA. 13+53	20
	* LT. STA. 14+66	20
	* RT. STA. 14+71	20
	* LT. STA. 15+36	20
	* RT. STA. 15+48	20
	* LT. STA. 16+06	20
	* RT. STA. 16+20	20
	* RT. STA. 16+84	20
	* LT. STA. 16+85	20
	* LT. STA. 17+64	20
	* RT. STA. 17+64	20
	* LT. STA. 18+82	20
	* RT. STA. 19+18	20
	* LT. STA. 19+44	20
	* RT. STA. 19+78	20
	* LT. STA. 19+96	20
	* RT. STA. 20+28	12
	* LT. STA. 20+46	20
	* LT. STA. 21+26	17
	TOTAL	369

XX004998	PVC WATER MAIN 6"	FT.
	18' LT. STA. 10+13 TO 10+33	20
	LT. STA. 10+33	25
	STA. 13+90 TO 13+95	5
	STA. 18+49 TO 18+54	5
	STA. 21+72 TO 21+77	5
	TOTAL	60

XX004999	PVC WATER MAIN 8"	FT.
	LT. STA. 18+49	47
	RT. STA. 18+49	66
	LT. STA. 18+45	4
	RT. STA. 18+45	4
	TOTAL	121

XX005000	PVC WATER MAIN 10"	FT.
	RT. STA. 9+33 TO LT. STA. 24+00	1529
	9' LT. TO 61' LT. STA. 13+89	52
	RT. STA. 13+89	62
	TOTAL	1,643

XX005001	DUCTILE IRON WATER MAIN FITTING - 10" PLUG	EACH
	3' RT. STA. 9+33	1
	16' LT. STA. 23+98	1
	TOTAL	2

XX005003	DUCTILE IRON WATER MAIN FITTING-10"x6" TEE	EACH
	10' LT. STA. 9+57	1
	9' LT. STA. 10+33	1
	50' RT. STA. 13+89	1
	46' RT. STA. 18+49	1
	9' LT. STA. 21+77	1
	9' LT. STA. 23+93	1
	TOTAL	6

XX005005	DUCTILE IRON WATER MAIN FITTING-10"x8" TEE	EACH
	52' LT. STA. 18+49	1
	53' RT. STA. 18+49	1
	TOTAL	2

XX005008	DUCTILE IRON WATER MAIN FITTINGS 10" 90 DEGREE BEND	EACH
	9' LT. STA. 23+98	1
	TOTAL	1

XX005010	DUCTILE IRON WATER MAIN FITTING-4"x6" REDUCER	EACH
	34' LT. STA. 9+57	1
	13' LT. STA. 23+93	1
	TOTAL	2

XX005013	DUCTILE IRON WATER MAIN FITTING-6" PLUG	EACH
	55' LT. STA. 21+77	1
	TOTAL	1

XX005102	DUCTILE IRON WATER MAIN FITTINGS 4" 90 DEGREE BEND	EACH
	13' LT. STA. 9+57	1
	13' LT. STA. 23+93	1
	TOTAL	2

XX006429	SIDEWALK, SPECIAL	S. F.
	* RT. STA. 20+34 TO 21+20.46	482
	TOTAL	482

Z0030240	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 2	EACH
	LT./RT. STA. 9+80	1
	LT./RT. STA. 10+20	1
	TOTAL	2

* ITEP ELIGIBLE ITEMS