

# SCHEDULE OF QUANTITIES

SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
05-00012-00-FR	HENRY	75	23
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT	

Z0076600	TRAINEES	HOUR
ENTIRE PROJECT		500
<u>TOTAL</u>		<u>500</u>
BUILDING GRATE TO BE ADJUSTED		EACH
▪ RT. STA. 18+82		1
▪ RT. STA. 18+95		1
▪ RT. STA. 19+20		1
<u>TOTAL</u>		<u>3</u>
PCC PAVEMENT, TEXTURED, COLORED, 8"		S. Y.
CENTER STREET		
▪ SOUTH LEG		23
▪ WEST LEG		22
▪ EAST LEG		22
▪ NORTH LEG		33
EXCHANGE STREET		
▪ SOUTH LEG		33
▪ WEST LEG		22
▪ EAST LEG		22
▪ NORTH LEG		33
DEPOT STREET		
▪ SOUTH LEG		38
▪ EAST LEG		26
LOCUST STREET		
▪ WEST LEG		22
▪ NORTH LEG		26
<u>TOTAL</u>		<u>322</u>
PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH, ELEVATED		S. F.
▪ LT. STA. 1620.24 TO 16+54.24		56
▪ LT. STA. 17+17.69 TO 17+30.19		50
▪ RT. STA. 18+67.2 TO 19+11.4		274
▪ RT. STA. 19+97 TO 20+13.5		88
▪ LT. STA. 20+51.6 TO 20+62.6		45
▪ LT. STA. 20+70 TO 21+22.5		410
<u>TOTAL</u>		<u>923</u>
PVC WATER MAIN 10", IN CASING		FT.
9' LT. STA. 9+69 TO 9' LT. STA. 10+29		60
<u>TOTAL</u>		<u>60</u>
STEEL CASING PIPE, 18" AUGERED & JACKED		FT.
10' LT. STA. 9+69 TO 9' LT. STA. 10+29		60
<u>TOTAL</u>		<u>60</u>

• ITEP ELIGIBLE ITEMS

TAP, TAPPING SLEEVE & CORP, 1"	EACH
LT. STA. 11+44	1
RT. STA. 11+78	1
RT. STA. 12+20	1
LT. STA. 13+10	1
RT. STA. 13+16	1
LT. STA. 14+34	1
LT. STA. 14+38	1
RT. STA. 14+96	1
RT. STA. 15+62	1
LT. STA. 15+19	1
LT. STA. 16+02	1
RT. STA. 16+10	1
LT. STA. 16+28	1
LT. STA. 16+33	1
LT. STA. 16+77	1
LT. STA. 16+83	1
LT. STA. 17+29	1
LT. STA. 17+33	1
LT. STA. 17+81	1
RT. STA. 18+79	1
LT. STA. 18+84	1
RT. STA. 19+10	1
LT. STA. 19+27	1
RT. STA. 19+43	1
RT. STA. 19+72	1
LT. STA. 19+84	1
RT. STA. 20+04	1
LT. STA. 20+10	1
LT. STA. 20+28	1
RT. STA. 20+35	1
LT. STA. 20+55	1
RT. STA. 20+71	1
LT. STA. 20+84	1
LT. STA. 21+38	1
RT. STA. 21+94	1
LT. STA. 22+35	1
LT. STA. 22+66	1
<u>TOTAL</u>	<u>37</u>

TAP & CORPORATION VALVE, 1 1/2"	EACH
RT. STA. 9+35	1
61' LT. STA. 13+89	1
52' RT. STA. 13+89	1
57' RT. STA. 18+49	1
56' LT. STA. 18+49	1
55' LT. STA. 21+77	1
16' LT. STA. 23+98	1
<u>TOTAL</u>	<u>7</u>

TAPPING TEE, VALVE & BOX, 8"	EACH
52' RT. STA. 18+45	1
52' LT. STA. 18+45	1
<u>TOTAL</u>	<u>2</u>