

SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
05-00012-00-FF	HENRY	75	24
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT

SCHEDULE OF QUANTITIES

VALVE GATE, 10" MJRW & BOX	EACH
9' LT. STA. 9+61	1
9' LT. STA. 13+85	1
9' LT. STA. 13+95	1
47' LT. STA. 13+89	1
47' RT. STA. 13+89	1
9' LT. STA. 18+35	1
9' LT. STA. 18+70	1
57' RT. STA. 18+49	1
56' LT. STA. 18+49	1
16' LT. STA. 23+98	1
TOTAL	10
DUCTILE IRON SOLID SLEEVE, 4"	EACH
13' LT. STA. 9+57	1
13' LT. STA. 23+93	1
TOTAL	2
DUCTILE IRON SOLID SLEEVE, 6"	EACH
18' LT. STA. 10+13	1
TOTAL	1
DUCTILE IRON WATER MAIN FITTING-10" CAP	EACH
61' LT. STA. 13+89	1
52' RT. STA. 13+89	1
TOTAL	2
WATER MAIN DOUBLE LINE STOP 4"	EACH
LT. STA. 9+50 TO LT. STA. 9+67	1
LT. STA. 23+85 TO LT. STA. 24+00	1
TOTAL	2
WATER MAIN DOUBLE LINE STOP 6"	EACH
15' RT. & 25' RT. STA. 10+13	1
TOTAL	1
WATER MAIN DOUBLE LINE STOP 8"	EACH
47' RT. STA. 18+45	1
47' LT. STA. 18+45	1
TOTAL	2

CRUSHED STONE TRENCH FOUNDATION	C. Y.
PROSPECT STREET - WATER MAIN STA. 9+50-23+98	20
TOTAL	20
CUT AND CAP EXISTING 4" WATER MAIN	EACH
13' RT. STA. 9+63	1
LT. STA. 13+75	1
RT. STA. 18+55	1
LT. STA. 22+32	1
LT. STA. 23+90	1
TOTAL	5
CUT AND CAP EXISTING 8" WATER MAIN	EACH
RT. STA. 18+45	1
LT. STA. 18+45	1
TOTAL	2

EARTHWORK SCHEDULE				
LOCATION	EARTH EXCAVATION	EARTH EXCAVATION ADJUSTED FOR SHRINKAGE *	EMBANKMENT	EARTHWORK
				BALANCE
	C. Y.	C. Y.	C. Y.	C. Y.
STA. 10+16.37 TO 14+12.97	693	520	87	+ 433
STA. 14+12.97 TO 18+32.06	783	587	51	+ 537
STA. 18+32.06 TO 21+75.31	624	468	97	+ 371
STA. 21+75.31 TO 21+98.07	79	59	0	+ 59
STA. 21+98.07 TO 24+20	581	436	29	+ 406
TOTAL	2,760	2,070	264	1,805

* ADJUSTED FOR SHRINKAGE FACTOR OF 25%

• ITEP ELIGIBLE ITEMS