

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

ROUTE NO.	SECTION	COUNTY	SHEET	PAGE
	#	Tazewell	43	2
FED. ROAD DIST. NO. 7	ILLINOIS	FED. AID PROJECT		


* 03-00123-03-BT CONTRACT # 89302

GENERAL NOTES:

- ALL CONSTRUCTION MATERIALS, EARTHWORK, BIKE TRAIL SUB-BASE, AND BIKE TRAIL SURFACE CONSTRUCTION SHALL CONFORM TO THE APPLICABLE ARTICLES OF THE "STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION" OF THE ILLINOIS DEPARTMENT OF TRANSPORTATION, LATEST EDITION - HEREINAFTER REFERRED AS "STANDARD SPECIFICATIONS".
- ABANDONED UNDERGROUND UTILITIES THAT CONFLICT WITH CONSTRUCTION SHALL BE REMOVED AND DISPOSED OF OUTSIDE THE LIMITS OF THE RIGHT OF WAY ACCORDING TO ARTICLE 202.03 OF THE STANDARD SPECIFICATIONS AND AS DIRECTED BY THE ENGINEER. THIS WORK WILL NOT BE PAID FOR SEPARATELY BUT SHALL BE CONSIDERED INCIDENTAL TO EARTH EXCAVATION, AND NO ADDITIONAL COMPENSATION WILL BE ALLOWED.
- THE CONTRACTOR SHALL BE RESPONSIBLE FOR PROTECTING UTILITY PROPERTY FROM CONSTRUCTION OPERATIONS AS OUTLINED IN ARTICLE 107.26 OF THE STANDARD SPECIFICATIONS. THE ILL. I.E. NUMBER IS 800-892-0123. A MINIMUM OF 48 HOURS ADVANCE NOTICE IS REQUIRED. UTILITIES SHOWN ON PLANS ARE APPROXIMATE ELEVATIONS AND LOCATIONS ONLY. ACTUAL ELEVATIONS AND LOCATIONS ARE TO BE VERIFIED IN THE FIELD BY THE CONTRACTOR.
- ALL ELEVATIONS SHOWN ARE IN REFERENCE TO THE BENCHMARKS AND MUST BE FIELD VERIFIED BY THE GENERAL CONTRACTOR AT GROUNDBREAK.
- ALL DISTURBED EARTH AREAS SHALL BE SEEDED WITH A CLASS 2 LAWN MIXTURE AS SPECIFIED IN SECTION 250 OF THE "STANDARD SPECIFICATIONS."
- THE LOCATIONS OF EXISTING WATER MAINS, GAS MAINS, SEWERS, ELECTRIC POWER LINES, TELEPHONE LINES AND OTHER UTILITIES AS SHOWN ON THE PLANS ARE BASED ON CAREFUL FIELD INVESTIGATION AND THE BEST INFORMATION AVAILABLE, BUT THEY ARE NOT GUARANTEED. IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO ASCERTAIN THEIR EXACT LOCATION FROM THE UTILITY COMPANIES AND BY FIELD INSPECTION.
- ALL EMBANKMENT MATERIAL ON FILL AREAS SHALL BE APPROVED BY THE ENGINEER.
- A SHRINKAGE FACTOR OF 30% WAS USED TO CALCULATE QUANTITIES OF WASTE/SHORTAGE MATERIAL.
- SLOPES WITH FILL GREATER THAN 10' HIGH SHALL BE BENCHED ACCORDING TO IDOT DIST. 4 CADD STANDARD 205001-D4. THIS WORK WILL NOT BE PAID FOR SEPARATELY BUT SHALL BE CONSIDERED INCIDENTAL TO THE EARTH EXCAVATION PAY ITEMS, AND NO ADDITIONAL COMPENSATION WILL BE ALLOWED.
- THE CONTRACTOR SHALL NOT STORE MATERIALS OR PARK EQUIPMENT ON RAILROAD CLEAR ZONE.
- THE CONTRACTOR SHALL STOCKPILE ALL TOPSOIL WHERE AVAILABLE FOR USE THROUGHOUT THE PROJECT.
- THE PERIMETER EROSION BARRIER SHALL BE PLACED ALONG THE CONSTRUCTION BOUNDARIES AT THE STATIONS SHOWN IN THE SCHEDULE OF QUANTITIES.
- THE ENTIRE SUBGRADE SHALL BE COMPACTED TO NOT LESS THAN 95 PERCENT OF THE STANDARD LABORATORY DENSITY.
- SEGMENTS OF THE BIKE TRAIL THAT CALL FOR 5" OF BITUMINOUS MATERIAL SHALL BE CONSTRUCTED WITH A 3" LIFT FOLLOWED BY A 2" LIFT FOR THE FINAL SURFACE.
- THIS PROJECT IS FOR SECTION A. SECTION A IS FROM STATION 10+00 TO STATION 25+68.80. ALL OTHER INFORMATION IN THE PLANS AND SPECIFICATIONS ARE FOR INFORMATIONAL PURPOSES ONLY.

HOT MIX ASPHALT	
LOCATIONS:	PROJECT LIMITS
MIXTURE USE(S):	BIKE TRAIL 2"
AC/PG	PG58-22
RAP % MAX	30
DESIGN AIR VOIDS	3.0% @ N30
MIXTURE COMPOSITION	IL 9.5 L
FRICTION AGGREGATE	Mixture C

GENERAL NOTES
BIKE TRAIL OVER FARM CREEK
SECTION 03-00123-03-BT
TAZEWELL COUNTY

DESIGNED	RMB	 RANDOLPH & ASSOCIATES, INC. 111 N. PIONEER PARKWAY, P.O. BOX 11, GLENVIEW, ILL. 60025-2124 TEL: 847-972-9800 FAX: 847-972-9895 T1: 800-871-9221 HTTP://WWW.RANDOLPHINC.COM CONSULTING ENGINEERS & LAND SURVEYORS	FILE NUMBER	56.46
CHECKED	CWB		DATE	August 2003
DRAWN	RMB			
CHECKED	CWB			