

ROUTE NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
C.H. 14 F.A.S. 209	00-00091-00-BR	MERCER	111	14
FED. ROAD DIST. NO.	ILLINOIS PROJECT			

CONTRACT NO. 89312

MAINLINE SCHEDULE

LOCATION	SUB GRAN MAT B (TON)	HMA BSE CSE 4" (SQ YD)	HMA BC WID 6" (SQ YD)	BIT MATLS PR CT (GAL)	AGG PR CT (TON)	AGGREGATE SHLDS A (TON)	HMA SC "C" N50 (TON)	HMA BC IL-19.0 N50 (TON)	HMA PVT FD 6 1/2" (SQ YD)	AGG SURF CSE A (TON)	TEMP ACCESS-ROAD (EACH)
87+25 TO 111+67				2794	11.3	1083.3					
LT 87+25 TO LT 90+60			74.5								
LT 90+60 TO LT 96+00			119.1								
RT 87+25 TO RT 91+13			106.0								
RT 91+13 TO RT 93+67		2335									
87+25 TO 95+15 (MOT)								327			
87+25 TO 94+00							203	467			
94+00 TO 100+00	975								1600		
100+00 TO 111+37.51	1848								3033		
111+37.51 TO 111+97.51							23				
111+97.51 TO 115+00	491								807		
111+67 TO 136+50				2634	13.3	1107.8					
115+00 TO 127+50	2030								3200		
127+50 TO 136+50							271	623			
131+25 TO 136+50 (MOT)								624			
RT 127+77 TO RT 132+44		904.1									
RT 132+44 TO RT 136+50			116.9								
LT 124+50 TO LT 133+00			192.0								
LT 133+00 TO LT 136+50			78.1								
162ND AVENUE											1
	65								103		
									79		
TOTALS	5409	1407.3	686.6	* 5428	* 24.6	2191.1	497	2041	8743	* 79	1

* NOT A TOTAL QUANTITY

TRAFFIC STAGING SCHEDULE

LOCATION	BIT MATLS PR CT (GAL)	AGG PR CT (TON)	TEMPORARY RAMP (SQ YD)	** TEMP PVT MK LINE 4 (FOOT)	SHORT-TERM PAVT MKING (FOOT)	WORK ZONE PAVT MK REM (SQ FT)
87+25 TO 100+00	40	1.6		3500	7875	1550
93+20 TO 94+00			213.3			
115+00 TO 128+00	40	1.6		1400		
127+50 TO 128+30			212.7			
128+00 TO 136+50	39	1.6		3400		
124+50 TO 136+50					10800	2100
TOTALS	* 119	* 4.8	426	* 8300	23400	3650

*NOT A TOTAL QUANTITY ** WHITE EDGE LINE

TREE REMOVAL SCHEDULE

LOCATION	TREE REMOV 6 TO 15 (UNIT)	TREE REMOV ACRES (ACRE)
LT 87+25 TO 89+50 BETWEEN EXISTING ROW AND PROPOSED EDGE OF PAVEMENT		0.05
76.5' LT 108+34	7	
75.7' LT 108+39	6	
STA 110+63 TO 111+68 BETWEEN EXISTING EDGE OF PAVEMENT AND CONSTRUCTION LIMITS		0.12
STA 111+68 TO 115+74 BETWEEN EXISTING EDGE OF PAVEMENT AND CONSTRUCTION LIMITS		0.52
STA 112+75 TO 114+05 IN PROPOSED WETRLAND UP TO PROPOSED ROW LIMIT		0.05
TOTALS	13	0.75

TREE REMOVAL ACRES WIDTHS VARY AS SHOWN ON PLANS. CLEAR TREES UP TO CONSTRUCTION LIMITS.

CULVERT REMOVAL SCHEDULE

LOCATION	TYPE	SIZE	REM EXIST CULVERTS (FOOT)
LT STA 96+72	CMP	15"	22
LT STA 103+35	PVC	15"	31
LT STA 105+00	CMP	15"	45
LT STA 105+63	RCP	12"	33
LT STA 124+50 TO LT STA 125+00	RCP	15"	50
LT STA 125+00	RCP	18"	30
LT STA 127+18	CMP	12"	45
RT STA 133+29.8	CMP	15"	30
TOTAL			286

ENTRANCE AND MAILBOX TURNOUT SCHEDULE

LOCATION	TYPE	WIDTH	AGG SURF CSE A (TONS)	TEMP ACCESS - PRIV ENT (EACH)
RT STA 88+26.4	FE	16'	16	1
RT STA 89+73.8	FE	16'	19	1
LT STA 103+35.0	PE	10'	47	1
LT STA 104+85.0	PE	11'	128	1
LT STA 109+50.0	FE	16'	42	1
RT STA 109+50.0	FE	16'	63	1
RT STA 133+29.8	FE	16'	14	1
RT STA 135+12.5	PE	9'	8	1
RT STA 135+98.8	PE	11'	10	1
TOTALS			*347	9

*NOT A TOTAL QUANTITY

MISCELLANEOUS REMOVAL SCHEDULE

LOCATION	HMA SURF REM BUTT JT (SQ YD)	PAVT REMOVAL SPL (SQ YD)	REM EXIST STRUCT N1 (EACH)	REM EXIST STRUCT N2 (EACH)	REM EXIST STRUCT N3 (EACH)	SPBGR REM (FOOT)
STA 87+25 TO 88+05	198					
LT STA 90+60 TO STA 96+00		119.1				
LT STA 90+60 TO 111+52		4572.7				
STA 94+40 TO STA 95+00	147					
LT STA 99+45 (BOX CULVERT)				1		
LT STA 110+75 TO LT STA 111+53						152
LT STA 111+67			1			
LT STA 111+83 TO 133+00		4574.4				
LT STA 111+83 TO LT STA 112+59						152
LT STA 124+18.16					1	
LT STA 124+50 TO LT STA 133+00		192.0				
STA 125+00 TO STA 125+60	146					
STA 135+70 TO STA 136+50	221					
TOTALS	712	9458.2	1	1	1	304

SCHEDULE OF QUANTITIES

Date	Designed: RLS	F.A.S. 209 (C.H. 14) OVER KEATING CREEK NEW BOSTON ROAD SECTION 00-00091-00-BR MERCER COUNTY
Revisions	Drawn: RLS	
	Checked: SMK	
	Approved: SMK	
Prepared by:	URS	
345 East Ash Avenue Decatur, IL 62526		URS Job No. 21-00001253.01