F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
6998	99-00209-01-PV	VERMILION	296	22
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT-		

CONTRACT NO.: 91358

SUMMARY OF QUANTITIES

CODE NUMBER	ITEM	UNIT	TOTAL QUANTITY	MINOR ARTERIAL ROADWAY FEDERAL 1000-2A	BRIDGE S.N. 092-6039 GCPF FEDERAL X631-2A
60255500	MANHOLES TO BE ADJUSTED	EACH	5	5	
60257900	MANHOLES TO BE RECONSTRUCTED	EACH	1	1	
60500060	REMOVING INLETS	EACH	3	3	
60600095	CLASS SI CONCRETE (OUTLET)	CU YD	3.4	3.4	
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	6467.5	5872.3	595.2
60607400	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-9.24	FOOT	99.5	42.2	57.3
60618310	CONCRETE MEDIAN SURFACE, 4 INCH (SPECIAL)	SQ FT	216		216
60900515	CONCRETE THRUST BLOCKS	EACH	1		1
63301210	REMOVE AND RE-ERECT STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	300	300	
63301990	REMOVE AND RE-ERECT TRAFFIC BARRIER TERMINAL, TYPE 1	EACH	1	1	
63302700	REMOVE AND RE-ERECT TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	1	1	
67100100	MOBILIZATION	L SUM	1	0.5	0.5
70101700	TRAFFIC CONTROL AND PROTECTION	L SUM	1	0.9	0.1
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	37548	37548	
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	76	76	
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	8154	8154	
*78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS & SYMBOLS	SQ FT	281	281	
*78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	15003	14351	652
*78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	840	840.0	
*78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	624	624	
*78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	145	145	
*78008310	POLYUREA PAVEMENT MARKING TYPE II - LINE 4"	FOOT	334	334.0	
78200405	GUARDRAIL MARKERS	EACH	5	5	
78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	1	1	
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	37	37	

CODE NUMBER	ITEM	UNIT	TOTAL QUANTITY	MINOR ARTERIAL ROADWAY FEDERAL 1000-2A	BRIDGE S.N. 092-6039 GCPF FEDERAL X631-2A
*80500105	SERVICE INSTALLATION, TYPE A (MODIFIED)	EACH	1	1	
*81012500	CONDUIT IN TRENCH, 1 1/2" DIA., PVC	FOOT	33	33	
*81012600	CONDUIT IN TRENCH, 2" DIA., PVC	FOOT	85	85	
*81012700	CONDUIT IN TRENCH, 2 1/2" DIA., PVC	FOOT	20	20	
*81013100	CONDUIT IN TRENCH, 5" DIA., PVC	FOOT	4	4	
*81021570	CONDUIT, AUGERED 3" DIA., PVC	FOOT	184	184	
*81021590	CONDUIT, AUGERED 4" DIA., PVC	FOOT	96	96	
*81400100	HANDHOLE	EACH	3	3	
*81400300	DOUBLE HANDHOLE	EACH	1	1	
*81702110	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 10	FOOT	1317	1317	
*81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	142	142	
*82103250	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, PHOTO-CELL CONTROL, 250 WATT	EACH	4	4	
*85700200	FULL-ACTUATED CONTROLLER AND TYPE IV CABINET	EACH	1	1	
*87301225	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C	FOOT	766	766	
*87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	489	489	
*87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C	FOOT	1727	1727	
*87301805	ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 6 2C	FOOT	36	36	
*87502680	TRAFFIC SIGNAL POST, ALUMINUM 14 FT	EACH	4	4	
*87702910	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 36 FT.	EACH	1	1	
*87702920	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 38 FT.	EACH	2	2	
*87702970	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 48 FT.	EACH	1	1	
*87800100	CONCRETE FOUNDATION, TYPE A	FOOT	12	12	
*87800200	CONCRETE FOUNDATION, TYPE D	FOOT	3	3	
*87800415	CONCRETE FOUNDATION, TYPE E 36-INCH DIAMETER	FOOT	46	46	
*88030020	SIGNAL HEAD, LED, 1-FACE, 3-SECTION, MAST-ARM MOUNTED	EACH	6	6	

*SPECIALTY ITEMS

PLAN	SURVEYED	BY	DATE
	SOILS		
	ALIGNMENT CHECKED		
	PLAN PROFILE PROOFED		
NOTE BOOK NO.	CADD FILE NAME		

REVISIONS NAME	DATE

CITY OF DANVILLE, ILLINOIS

WINTER AVENUE RECONSTRUCTION

SUMMARY OF QUANTITIES

SCALE: DATE: 12/21/06

DRAWN BY: MBF CHECKED BY: SMK