F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
6998	99-00209-01-PV	VERMILION	296	23
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT-		

CONTRACT NO.: 91358

SUMMARY OF QUANTITIES

CODE NUMBER	ITEM	UNIT	TOTAL QUANTITY	MINOR ARTERIAL ROADWAY FEDERAL I000-2A	BRIDGE S.N. 092-6039 GCPF FEDERAL X631-2A
*88030050	SIGNAL HEAD, LED, 1-FACE, 3-SECTION, BRACKET MOUNTED	EACH	2	2	
*88030100	SIGNAL HEAD, LED, 1-FACE, 5-SECTION, BRACKET MOUNTED	EACH	4	4	
*88030110	SIGNAL HEAD, LED, 1-FACE, 5-SECTION, MAST-ARM MOUNTED	EACH	4	4	
*88200100	TRAFFIC SIGNAL BACKPLATE	EACH	10	10	
X0301232	SURVEY MARKER VAULT	EACH	1	1	
*X0301576	COAXIAL CABLE IN CONDUIT	FOOT	766	766	
*X0320872	VIDEO VEHICLE DETECTION SYSTEM	EACH	1	1	
X0322054	REMOVAL OF PRECAST FLARED END SECTION	EACH	2	2	
X0323381	STORM SEWERS, (WATER MAIN REQUIREMENTS), TYPE 1 12"	FOOT	154	154	
X0323988	TEMPORARY SOIL RETENTION SYSTEM	SQ FT	1637		1637
X0325348	TEMPORARY BALLAST RETAINER (INSTALLED AND REMOVED)	FOOT	142		142
X0696000	BRIDGE DRAINAGE SYSTEM	L SUM	1		1
X4021000	TEMPORARY ACCESS (PRIVATE ENTRANCE)	EACH	11	10	1
X4022000	TEMPORARY ACCESS (COMMERCIAL ENTRANCE)	EACH	7	7	
*X8730027	ELECTRIC CABLE IN CONDUIT, GROUNDING, NO. 6 1C	FOOT	548	548	
XX003437	REMOVE AND REINSTALL EXISTING PRECAST REINFORCED CONCRETE FLARED END SECTIONS	EACH	1	1	
XX004096	REMOVE AND RE-INSTALL CONCRETE FLARED END SECTIONS	EACH	1	1	
XX004782	TEMPORARY BITUMINOUS PAVEMENT	SQ YD	2771	2771	
XX005630	TEMPORARY AGGREGATE SHOULDER	TON	115	115	
Z0002300	BALLAST	CU YD	95		95
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	0.9	0.1
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1		1
Z0069700	SUB-BALLAST	CU YD	34		34
XX006904	PIPE CULVERTS, TYPE 1, REINFORCED CONCRETE - ELLIPTICAL, EQUIVALENT ROUND-SIZE 24" (TEMPORARY)	FOOT	4	4	

CODE NUMBER	ITEM	UNIT	TOTAL QUANTITY	MINOR ARTERIAL ROADWAY FEDERAL I000-2A	BRIDGE S.N. 092-6039 GCPF FEDERAL X631-2A
XX006965	STONE RIPRAP, CLASS A2 (SPECIAL)	SQ YD	267	267	
52100530	ANCHOR BOLTS, 1 1/4"	EACH	156		156

*SPECIALTY ITEMS

PLAN	BY	DATE
SURVEYED / SCALE / ALIGNMENT CHECKED / PLOT CHECKED / CADD FILE NAME / NOTE BOOK NO.		

REVISIONS NAME	DATE

CITY OF DANVILLE, ILLINOIS

WINTER AVENUE RECONSTRUCTION

SUMMARY OF QUANTITIES

SCALE: DATE: 02/07/07

DRAWN BY: MBF CHECKED BY: SMK