

REMOVAL LEGEND

	PAVEMENT REMOVAL		CURB & GUTTER REMOVAL
	DRIVEWAY PAVEMENT REMOVAL		GUARDRAIL REMOVAL
	SIDEWALK REMOVAL		BITUMINOUS TAPER (FOR BUTT JOINTS)
	BUILDING REMOVAL		TREE REMOVAL (AC)

⊗ TREE REMOVAL ⊙ TREE TRUNK PROTECTION

DRIVEWAY PAVEMENT REMOVAL SCHEDULE

TYPE	STATION	LT/RT	PAVEMENT TYPE	DRIVEWAY PAVEMENT REM (SY) 44000200
WINTER AVENUE				
C.E.	150+91.21	RT	BIT.	57.4
BOWMAN AVENUE				
P.E.	60+35.78	LT	BIT.	27.5
C.E.	60+40.29	RT	CONC.	81.9
SHEET TOTAL				

SW 1/4 SEC. 27 T20N-R11W 2nd P.M.

F.A.U. RTE. 6998	SECTION 99-00209-01-PV	COUNTY VERMILION	TOTAL SHEETS 296	SHEET NO. 40
STA. 145+00		TO STA. 151+00		
FED. ROAD DIST. NO. ILLINOIS		FED. AID PROJECT- CONTRACT NO.: 91358		

TREE REMOVAL SCHEDULE (6" TO 15")

STATION	O/S	LT/RT	SIZE (IN)	TREE REMOV 6-15 (UNIT) 20100110
147+33.42	36.88'	RT	6	6
148+60.78	41.12'	RT	7	7
149+25.06	31.30'	LT	12	60
150+59.43	34.00'	RT	6	6
SHEET TOTAL				

TREE REMOVAL SCHEDULE (OVER 15")

STATION	O/S	LT/RT	SIZE (IN)	TREE REMOV OVER 15 (UNIT) 20100210
146+03.82	46.96'	RT	20	20
146+37.16	67.66'	RT	20	20
SHEET TOTAL				

SE 1/4 SEC. 28 T20N-R11W 2nd P.M.

MATCHLINE 145+00 (WINTER AVENUE)

MATCHLINE 245+00 (BICYCLE PATH)

MATCHLINE 63+50 (BOWMAN AVENUE)

MATCHLINE 151+00 (WINTER AVENUE)

COMBINATION CURB AND GUTTER REMOVAL SCHEDULE

FROM STATION	TO STATION	LT/RT	C C & G REM (FOOT) 44000500
147+24.57	147+62.58	RT	45.8
147+32.17	147+64.79	LT	48.1
148+20.88	148+55.00	LT	46.5
148+21.60	148+57.77	RT	47.8
SHEET TOTAL			

NE 1/4 SEC. 33 T20N-R11W 2nd P.M.

PAVEMENT REMOVAL SCHEDULE

FROM STATION	TO STATION	PAVEMENT REM (SY) 44000100
WINTER AVENUE		
145+00.00	147+50.00	663.8
148+50.00	151+00.00	680.3
BOWMAN AVENUE		
60+00.00	63+50.00	1805.8
SHEET TOTAL		

TREE REMOVAL SCHEDULE (ACRES)

FROM STATION	TO STATION	LT/RT	TREE REMOV (ACRES) 20100500
145+00	146+83	LT	0.047
SHEET TOTAL			

CULVERT REMOVAL SCHEDULE

TYPE	FROM STATION	O/S	LT/RT	TO STATION	O/S	LT/RT	SIZE (IN)	PIPE CULVERT REMOV (FOOT) 50105220
WINTER AVENUE								
CMP	146+69.84	8.99'	RT	146+85.78	16.83'	LT	12	30.4
CMP	148+57.71	24.89'	LT	148+95.96	23.50'	LT	15	38.3
CPP	150+14.09	19.31'	LT	150+15.12	16.71'	RT	12	36.0
CMP	150+68.05	25.93'	RT	151+04.64	15.66'	RT	12	38.0
BOWMAN AVENUE								
CMP	60+21.23	27.76'	LT	60+49.63	27.13'	LT	15	28.4
RCCP	62+49.56	28.90'	RT	62+50.57	29.69'	LT	30x19	58.6
SHEET TOTAL								

TREE TRUNK PROTECTION SCHEDULE

STATION	O/S	LT/RT	TREE TRUNK PROTECTION (EACH) 20101100
WINTER AVE.			
150+34.21	34.34'	RT	1
BOWMAN AVE.			
60+78.24	40.12'	RT	1
SHEET TOTAL			

REVISIONS	
NAME	DATE

CITY OF DANVILLE, ILLINOIS
WINTER AVENUE RECONSTRUCTION EXISTING REMOVAL PLAN
 WINTER AVENUE/BOWMAN AVENUE
 STA. 145+00 TO STA. 151+00
 STA. 60+00 TO STA. 63+50
 SCALE: 1" = 20'
 DRAWN BY: NIL
 DATE: 12/21/06
 CHECKED BY: MBF

PLAN SURVEYED, PLOTTED, CHECKED, DATE, BY, NOTE BOOK NO., FILE NAME

