

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	URBAN - FAYETTE COUNTY				
				FEDERAL 80% CITY 20% TEA-21 J000-2A	FEDERAL 80% CITY 20% STU Y007	FEDERAL 80% CITY 100% I000-2A	07AU) STATE 50% CITY 50% I000-2A	07A(2) STATE 100% I000-2A
Z0012450	CONCRETE STEPS	CU. YD.	5	5				
Z0050900	REMOVE CONCRETE FOUNDATION	EACH	2			2		
Z0067500	STEEL CASINGS 16"	FOOT	84			84		
XX000739	CURB STOP & BOX 1 INCH	EACH	83			83		
XX000868	SELECT GRANULAR BACKFILL	CU. YD.	5487			5487		
XX000959	TRASH RECEPTACLES	EACH	36			36		
+ XX001051	WATER SERVICE LINE RECONNECTION	EACH	83			83		
XX001386	SANITARY SEWERS, PVC, 8"	FOOT	419			419		
X0322024	TRENCH DRAIN	EACH	1			1		
XX004101	ORNAMENTAL METAL FENCE	FOOT	78	78				
XX004242	ORNAMENTAL HANDRAIL	FOOT	52	52				
XX004602	BENCH WITH BACK	EACH	36			36		
XX004735	RESTRICTED DEPTH INLET TYPE B, TYPE 1 FRAME, CLOSED LID	EACH	1			1		
+ XX004887	ORNAMENTAL LIGHT UNIT, COMPLETE	EACH	40	40				
XX004998	PVC WATER MAIN 6"	FOOT	671			671		
+ XX004999	PVC WATER MAIN 8"	FOOT	3249			3249		
XX005884	GROUT ABANDONED SEWERS	FOOT	1749			1749		
XX005790	RECONNECT SANITARY SERVICE LATERAL 6"	EACH	50			50		
XX006179	SANITARY MANHOLE REMOVAL AND REPLACEMENT	EACH	4			4		
X0300558	SANITARY SEWER REMOVAL AND REPLACEMENT 8"	FOOT	1599			1599		
Y0000140	SANITARY SEWER REMOVAL AND REPLACEMENT 10"	FOOT	28			28		
XX006887	CAP AND BLOCK 1"	EACH	1			1		
XX006888	CAP AND BLOCK 2"	EACH	1			1		
XX006889	CAP AND BLOCK 3"	EACH	3			3		
X0301708	CAP AND BLOCK 6"	EACH	4			4		
X0301709	CAP AND BLOCK 8"	EACH	1			1		
X0321556	SANITARY MANHOLES TO BE ADJUSTED	EACH	3			3		
X0322719	TEMPORARY DRAINAGE CONNECTION	EACH	20			20		
X6020074	INLETS, TYPE A, TYPE 3V FRAME AND GRATE	EACH	29	20		9		
X6020075	INLETS, TYPE B, TYPE 3V FRAME AND GRATE	EACH	10	5		5		
X6020125	RESTRICTED DEPTH INLET TYPE B, TYPE 3 FRAME AND GRATE	EACH	7	1		6		
X6020127	RESTRICTED DEPTH INLET TYPE B, TYPE 3V FRAME AND GRATE	EACH	12	8		4		
XX006890	CIPP LINER FOR SANITARY SEWER MAIN 6"	FOOT	187			187		
XX006891	CIPP LINER FOR SANITARY SEWER MAIN 8"	FOOT	1162			1162		
XX006892	CIPP LINER FOR SANITARY SEWER MAIN 10"	FOOT	280			280		
XX006893	CIPP LINER FOR SANITARY SEWER MAIN 12"	FOOT	391			391		
XX006894	CIPP LINER FOR SANITARY SEWER MAIN 15"	FOOT	265			265		
XX006895	RESTRICTED DEPTH MANHOLE, 4'-DIAMETER, WITH SALVAGE FRAME AND GRATE	EACH	1			1		
+ XX006896	STEEL CASING BORED AND JACKED 42"	FOOT	110			110		
+ XX005488B	STEEL CASING BORED AND JACKED 48"	FOOT	119			119		
XX006897	5' BRICK CIRCULAR PATTERN	EACH	36	36				
XX006898	STAMPED COLORED PORTLAND CEMENT CONCRETE	SQ. FT.	856	712		144		
XX006899	SERIES A OUTDOOR INTERPRETIVES SIGN TYPE A3	EACH	7	5		2		
XX006900	SERIES A OUTDOOR INTERPRETIVES SIGN TYPE A4	EACH	3	3				
+ XX006901	TREE GRATE ASSEMBLY, COMPLETE	EACH	36	36				
XX006902	HANDICAP RAMP AND HANDRAIL, COMPLETE	EACH	1	1				
XX006903	ORNAMENTAL STREET SIGN POST, COMPLETE	EACH	49	49				
Z0048665	Railroad Protective Liability Insurance	LSUM	1	1				

* SPECIAL PROVISIONS

+ SPECIALTY ITEMS

1 REVISED (4-13-07)

REVISIONS	
NAME	DATE
LWJ	4-13-07

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: VERT. HORIZ. DATE DRAWN BY KOJ CHECKED BY BWC

CADD FILE: /4812/4812-4812.dgn
PLOTTED: 4/16/2007

H.M. & G. NO. 4812