F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
8419	99-00048-01-PV	FAYETTE	142	15
STA.	TO STA.			
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

CONTRACT NO. 95500

STORM SEWER SCHEDULE

LOCATION	TRENCH BACKFILL, SPECIAL	CLASS C PATCHES									STORM SEWER REMOVAL							REMOVING MANHOLES	REMOVING CATCH BASINS	REMOVING INLETS	STORM SEWER CLASS A											
																					TYPE 1					TYPE 2						
																									RUBBER GASKET						RUBBER GASKET
		TYPE I 8 INCH	TYPE II 8 INCH	TYPE III 8 INCH	TYPE IV 8 INCH	TYPE II 10 INCH	TYPE III 10 INCH	TYPE IV 10 INCH	TYPE III 15 INCH	TYPE IV 15 INCH	6"	8"	10"	12"	15"	18"	24"				12"	24"	30"	36"	12"	12"	15"	18"	24"	30"	36"	42"	12"	24"
	CU. YD.	SQ. YD	SQ. YD	SQ. YD	SQ. YD	SQ. YD	SQ. YD	SQ. YD	SQ. YD	SQ. YD	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	EACH	EACH	EACH	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT
RT. STA. 11+02, 27.83'																																
RT. STA. 11+02 TO RT. STA. 11+17	3.4																															
RT. STA. 11+02 TO RT. STA. 12+45	19.0																									13						
LT. STA. 11+17, 27.83'	0.4																				2											
RT. STA. 11+17, 27.83'																																
LT. STA. 11+98.6	1.1																															
LT. STA. 12+69 TO LT. STA. 12+76	1.2																															
RT. STA. 12+69 TO RT. STA. 12+76	1.2																															
LT. STA. 12+76, 23.75'																																
LT. STA. 12+76 TO RT. STA. 12+76	13.4									25.0																						49	
LT. STA. 12+76 TO LT. STA. 14+92	89.3							132.0																		206						
LT. STA. 12+76 TO LT. STA. 14+11	18.3																															
LT. STA. 12+76, 27.83'																																
RT. STA. 12+76 TO RT. STA. 12+91	2.1																				13											
RT. STA. 12+76 TO RT. STA. 14+11	17.9																															
LT. STA. 12+82, 27.83'	0.5																				2											
RT. STA. 12+91, 27.83'																																
RT. STA. 12+92 TO RT. STA. 15+95	13.8																															
LT. STA. 13+42.57, 28.78'	4.5												8						1													
RT. STA. 14+80.71, 22.92'	9.1												16						1													
LT. STA. 14+89.14, 29.97	9.1												16						1													
LT. STA. 14+92, 23.75'																																
LT. STA. 14+92 TO RT. STA. 14+92	17.4									25.0																						49	
LT. STA. 14+92 TO LT. STA. 18+19.95	267.2							200.0																		324						
RT. STA. 14+92, 27.83'																																
RT. STA. 14+92 TO RT. STA. 15+07	2.1																				13											
LT. STA. 15+03, 27.83'	0.8																									2						
LT. STA. 15+03 TO LT. STA. 16+30	16.9																															
RT. STA. 15+07, 27.83'																																
LT. STA. 15+18, 27.83'	0.8																									2						
LT. STA. 16+00, 23. 75'																																
LT. STA. 16+00 TO RT. STA. 16+00	17.4									26.0																						51	
RT. STA. 16+00, 27.83'																																
RT. STA. 16+00 TO RT. STA. 18+10	27.8																															
LT. STA. 16+35, 27.83'	1.5																									2						
LT. STA. 16+35 TO LT. STA. 18+10	23.2																															
LT. STA. 18+19.78, 44.26'																																
LT. STA. 18+19.95, 23.75'																																
LT. STA. 18+19.95, 30.72'																																
LT. STA. 18+20 TO LT. STA. 18+25.38	0.8																				5											
LT. STA. 18+20	29.1														32					1						28						
LT. STA. 18+25, 44.27'																																
SIXTH STREET																																
LT. STA. 600+98, 20.14'	22.2												30				8	1														

FOR MORE ITEMS, SEE NEXT SHEET

REVISIONS NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: VERT.
HORIZ.
DATE

DRAWN BY KOJ
CHECKED BY BWC

H.M. & G. NO. 4812

CADD FILE: 14812/sch_4812.dgn
PLOTTED: 01/23/2007

HENRY, MEISENHEIMER & GENDE, INC. 1075 LAKE ROAD CARLYLE, ILLINOIS 62231 (618) 594-3711 WWW.HMGENGINEERS.COM