

F.A.L. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
8419	99-00048-01-PV	FAYETTE	142	23
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		
CONTRACT NO. 95500				

PAVEMENT MARKINGS

LOCATION	TYPE	THERMOPLASTIC PAVEMENT MARKING				
		YELLOW		WHITE		LETTERS AND SYMBOLS SQ. FT.
		LINE 4"	LINE 6"	LINE 6"	LINE 24"	
		FOOT	FOOT	FOOT	FOOT	
GALLATIN STREET						
STA. 98+96 TO STA. 102+15	YELLOW - CENTERLINE - SKIP DASH	80.0				
	YELLOW - NO PARKING		300.0			
	WHITE - PARKING STALLS			180.0		
	WHITE - STOP BAR				20.0	
STA. 2+55 (STA 703+70 SEVENTH STREET) TO STA. 3+90	YELLOW - CENTERLINE - NO PASSING	366.0				
STA. 3+90 TO STA. 6+29	YELLOW - CENTERLINE - SKIP DASH	60.0				
	WHITE - PARKING STALLS			28.0		
	WHITE - CROSSWALK			118.0		
STA. 6+92.5 TO STA. 10+23.5	YELLOW - CENTERLINE - NO PASSING	614.0				
	WHITE - PARKING STALLS			176.0		
	WHITE - TURN LANE			100.0		
	WHITE - LARGE LEFT TURN ARROW				31.2	
	WHITE - STOP BAR				33.0	
	WHITE - CROSSWALK			230.0		
STA. 10+90.5 TO STA. 14+22	YELLOW - CENTERLINE - NO PASSING	616.0				
	WHITE - PARKING STALLS			160.0		
	WHITE - TURN LANE			127.5		
	WHITE - LEFT TURN ARROW				62.4	
	WHITE - STOP BAR				33.0	
	WHITE - CROSSWALK			230.0		
STA. 14+83 TO STA. 18+02.5	YELLOW - CENTERLINE - NO PASSING	620.0				
	WHITE - PARKING STALLS			176.0		
	YELLOW - NO PARKING		450.0			
	WHITE - TURN LANE			127.0		
	WHITE - LEFT TURN ARROW				62.4	
	WHITE - STOP BAR				33.0	
	WHITE - CROSSWALK			233.0		
SIXTH STREET						
STA. 603+15 TO STA. 604+10	YELLOW - CENTERLINE - NO PASSING	162.0				
	WHITE - PARKING STALLS			28.0		
	WHITE - STOP BAR				21.0	
	WHITE - CROSSWALK			102.0		
STA. 604+71 TO STA. 605+32	YELLOW - CENTERLINE - NO PASSING	94.0				
	WHITE - PARKING STALLS			28.0		
	WHITE - TURN LANE			47.0		
	WHITE - LEFT TURN ARROW				15.6	
	WHITE - STOP BAR				35.0	
	WHITE - CROSSWALK			129.0		
FIFTH STREET						
STA. 503+72 TO STA. 504+09	YELLOW - CENTERLINE - NO PASSING	46.0				
	WHITE - PARKING STALLS			12.0		
	WHITE - TURN LANE			23.0		
	WHITE - LEFT TURN ARROW				15.6	
	WHITE - STOP BAR				33.0	
	WHITE - CROSSWALK			120.0		
STA. 504+72 TO STA. 504+98	YELLOW - CENTERLINE - NO PASSING	24.0				
	WHITE - PARKING STALLS			12.0		
	WHITE - TURN LANE			12.0		
	WHITE - STOP BAR				34.0	
	WHITE - CROSSWALK			122.0		
FOURTH STREET						
STA. 403+84.5 TO STA. 404+08	YELLOW - CENTERLINE - NO PASSING	19.0				
	WHITE - STOP BAR				23.0	
	WHITE - CROSSWALK			103.0		
STA. 404+71.5 TO STA. 404+98	YELLOW - CENTERLINE - NO PASSING	25.0				
	WHITE - STOP BAR				29.0	
	WHITE - CROSSWALK			129.0		
TOTALS		2726	750	2753	294	188
			3503			

SIGN LOCATIONS

LOCATION	ORNAMENTAL STREET SIGN POST, COMPLETE	
	STREET SIGN EACH	STOP SIGN EACH
GALLATIN STREET		
RT STA 98+76.36, 38.84'		1
LT STA 98+75.17, 43.50'	1	
LT STA 98+80.62, 41.28'	1	
RT STA 99+18.67, 44.10'	1	
LT STA 99+30.66, 23.34'	1	
RT STA 99+63.31, 46.02'	1	
LT STA 99+76.05, 23.04'	1	
RT STA 101+89.01, 24.57'	1	
LT STA 101+92.62, 21.96'	1	
LT STA 101+93.14, 22.34'	1	
RT STA 2+15.07, 23.49'		1
LT STA 2+29.91, 22.56'	1	
LT STA 2+33.10, 22.61'	1	
LT STA 2+40.70, 40.24'		1
LT STA 2+74.90, 25.16'	1	
RT STA 5+10.49, 29.70'	1	
LT STA 6+00.73, 36.74'		1
LT STA 6+35.79, 46.61'		1
RT STA 6+77.52, 100.40'		1
LT STA 6+88.38, 78.40'	1	
LT STA 6+92.32, 27.31'	1	
LT STA 7+14.88, 30.45'	1	
LT STA 8+28.01, 31.18'	1	
RT STA 8+37.49, 30.14'	1	
RT STA 10+00.49, 30.64'	1	
LT STA 10+09.00, 31.41'	1	
RT STA 10+13.20, 22.51'		1
RT STA 10+26.60, 42.60'	1	
LT STA 10+34.93, 41.83'		1
RT STA 10+78.91, 42.29'		1
RT STA 10+86.96, 67.80'	1	
LT STA 10+87.70, 58.10'	1	
LT STA 10+88.02, 79.64'	1	
LT STA 10+97.92, 31.17'	1	
LT STA 11+02.56, 23.49'		1
RT STA 11+13.10, 30.40'	1	
LT STA 11+22.67, 31.22'	1	
RT STA 11+32.54, 31.22'	1	
LT STA 13+99.65, 31.83'	1	
RT STA 14+01.20, 32.39'	1	
RT STA 14+24.35, 64.76'	1	
LT STA 14+32.07, 42.35'		1
RT STA 14+76.35, 49.80'		1
RT STA 14+77.42, 62.66'	1	
LT STA 14+87.38, 59.20'	1	
LT STA 14+89.31, 41.98'	1	
LT STA 17+98.42, 30.18'	1	
LT STA 18+13.94, 41.73'	1	
LT STA 18+17.47, 42.88'	1	
TOTAL	37	12
	49	

TREE REMOVAL

LOCATION	TREE REMOVAL (6 TO 15 UNITS DIAMETER) UNIT
GALLATIN STREET	
LT. STA. 100+97.9, 22.4'	6
LT. STA. 100+97.9, 22.4'	6
LT. STA. 100+97.9, 22.4'	8
LT. STA. 100+97.9, 22.4'	12
LT. STA. 100+97.9, 22.4'	10
LT. STA. 101+26.6, 22.9'	6
LT. STA. 101+26.6, 22.9'	6
LT. STA. 101+56.1, 22.8'	7
LT. STA. 101+86.3, 22.3'	10
LT. STA. 101+86.3, 22.3'	9
LT. STA. 101+86.3, 22.3'	8
RT. STA. 2+82.45, 61.0'	13
FOURTH STREET	
RT. STA. 407+81.5, 40.0'	12
TOTAL	113

CADD FILE: /4812/scr_4812.dgn
PLOTTED: 01/23/2007

H.M. & G. INC. 4812

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
SCALE: VERT. _____		DRAWN BY KOJ
DATE _____		