

F/P ROUTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO
	05-00018-02-RP	MADISON	42	9
STA.		TO STA.		
CONTRACT NO.: 97290				

REMOVAL ITEMS

STATION TO STATION	COMBINATION CURB AND GUTTER REMOVAL FOOT 44000500	SIDEWALK REMOVAL SQ FT 44000600	PAVED DITCH REMOVAL FOOT 44004000	CONCRETE REMOVAL CU YD 50102400	CONCRETE RETAINING WALL REMOVAL CU YD *50104605
WEST CORBIN					
10+14.25 TO 10+16.55 RT					1
12+18.11 LT		111	32		
14+49.28 RT		6			
15+16.22 LT				1	
WEST CORBIN SUB-TOTAL		117	32	1	1
MILES DRIVE					
200+28.05 TO 200+58.90 RT	33				
200+31.80 TO 200+58.82 LT	28				
MILES DR SUB-TOTAL	61				
SCHOOL DRIVEWAY					
500+05.71 TO 501+07.86 LT		539			
SCHOOL DRIVEWAY DR SUB-TOTAL					
GRAND TOTAL	61	656	32	1	1

EARTH EXCAVATION SCHEDULE

LOCATION*	EARTH EXCAVATION (CUT)*	EARTH EXCAVATION ADJUSTED FOR SHRINKAGE**	EMBANKMENT (FILL)*	EARTHWORK BALANCE WASTE OR (SHORTAGE)***
STA.	CU.YD.	CU.YD.	CU.YD.	CU.YD.
10+50, LT TO 23+27, LT	1,267	950	91	859
9+44, RT TO 23+27, RT	606	454	194	260
MILES DRIVE	33	25	0	25
WEST DRIVE	33	25	0	25
SCHOOL DRIVEWAY	1,378	1,033	463	570
GRAND TOTAL	3,317	2,487	749	1,739

*TAKEN FROM CROSS SECTIONS
 **QUANTITY OF EARTH EXCAVATION ADJUSTED FOR SHRINKAGE (25% ASSUMED)
 ***EARTHWORK REQUIRED: (-) = QUANTITY OF FILL OR EMBANKMENT NEEDED
 (+) = QUANTITY TO BE WASTED

STRUCTURE SCHEDULE

STATION TO STATION	MANHOLE FRAMES TO BE ADJUSTED EACH *60300350
WEST CORBIN	
11+78.41 RT	1
13+16.23 RT	1
16+43.66 RT	1
18+57.74 RT	1
WEST CORBIN SUB-TOTAL	4
GRAND TOTAL	4

RETAINING WALL SCHEDULE

STATION TO STATION	PIPE HANDRAIL, SPECIAL FOOT *50901765	RETAINING WALL, SPECIAL SQ FT *XX001607
WEST CORBIN		
10+17.15 RT		18
RT 11+25.40 TO 11+54.54	29	
LT 11+25.40 TO 11+53.11	28	
LT 13+97.84 TO 14+05.34		
WEST CORBIN SUB-TOTAL	57	
GRAND TOTAL	57	18

PIPE CULVERT REMOVAL

WEST CORBIN STREET			
STATION	O/S	SIZE/TYPE	LENGTH
11+36.62	X	24" CMP	32'
11+38.34	X	18" CMP	31'
12+31.89	LT	10" CMP	25'
16+89.81	LT	12" CMP	60'
17+73.12	RT	10" CMP	21'
17+84.30	LT	10" CMP	29'
18+42.05	LT	10" CMP	34'
18+77.20	RT	10" CMP	20'
21+24.36	LT	10" CMP	41'
21+65.02	RT	10" CMP	41'
22+43.86	LT	10" CMP	25'
GRAND TOTAL			359'

FENCE SCHEDULE

STATION TO STATION	FENCE TO BE REMOVE AND RE-ERECTED FOOT *XX000714
WEST CORBIN	
10+31.60 TO 10+80.80 LT	65
15+29.25 TO 20+66.70 LT	190
WEST CORBIN SUB-TOTAL	255
GRAND TOTAL	255

PAVEMENT MARKING

STATION TO STATION	PAINT PAVEMENT MARKING - LINE 4" FOOT 78001110	PAINT PAVEMENT MARKING - LINE 12" FOOT 78001150	PAINT PAVEMENT MARKING - LINE 24" FOOT 78001180
WEST CORBIN			
10+59.39 TO 11+51.22 X	184		
12+27.75 TO 17+31.07 X	940		
17+31.07 TO 23+10.97 X	145		
11+62.40 TO 12+12.90 RT		87	
16+29.90 TO 16+59.54 RT		51	
16+17.54 TO 16+94.19 LT		135	
23+31.32 RT			16
WEST CORBIN SUB-TOTAL	1,269	273	16
MILES DRIVE			
200+26.04 TO 200+58.86 X	65		
200+26.04 RT			17
MILES DRIVE SUB-TOTAL	65		17
WEST DRIVE			
400+25.02 TO 400+48.71 X	47		
400+25.02 RT			11
MILES DRIVE SUB-TOTAL	47		11
SCHOOL DRIVEWAY			
500+31.36 TO 500+71.36 X	80		
500+31.36 LT			22
MILES DRIVE SUB-TOTAL	80		22
GRAND TOTAL	1,461	273	66

SIGN SCHEDULE

STATION	O/S	TYPE	DESCRIPTION	SQ. FT.
WEST CORBIN				
10+46.70	18.70 LT	R1	STOP SIGN	6.25
11+01.82	16.86 RT	R7-1	NO PARKING SIGN	1.5
11+99.60	16.60 LT	R2-1/R7-1	SPEED LIMIT (25 M.P.H.) & NO PARKING SIGN	6.5
15+28.44	16.87 RT	R7-1	NO PARKING SIGN	1.5
17+20.29	16.98 LT	R2-1	SPEED LIMIT (25 M.P.H.)	5.0
18+58.77	17.24 RT	R2-1/R7-1	SPEED LIMIT (25 M.P.H.) & NO PARKING SIGN	6.5
20+90.03	17.00 RT	R7-1	NO PARKING SIGN	1.5
19+74.13	16.63 LT	R2-1	SPEED LIMIT (25 M.P.H.)	5.0
WEST CORBIN SUB-TOTAL				33.75
SCHOOL DRIVEWAY				
500+31.13	26.63 RT	R1	STOP SIGN	6.25
SCHOOL DRIVEWAY SUB-TOTAL				6.25
MILES DRIVE				
200+28.03	22.01 LT	D3	STREET SIGN	4.75
200+28.03	22.01 LT	R1	STOP SIGN	6.25
MILES DRIVE SUB-TOTAL				11.00
WEST DRIVE				
400+19.02	12.02 LT	D3	STREET SIGN	4.75
400+19.02	12.02 LT	R1	STOP SIGN	6.25
WEST DRIVE SUB-TOTAL				11.00
GRAND TOTAL				62

TREE REMOVAL SCHEDULES

STATION	O/S	TREE REMOVAL	
		TREE REMOVAL (6 TO 15 UNITS DIAMETER)	TREE REMOVAL (OVER 15 UNITS DIAMETER)
WEST CORBIN			
10+79.45	20' LT		24
11+39.90	33' RT		18
12+51.07	19' RT	6	
13+43.00	33' RT		18
17+25.06	29' LT	15	
17+41.02	23' LT	12	
17+59.00'	29' LT	15	
18+07.14	10' LT	12	
18+09.22	26' LT	15	
18+12.65	17' LT	15	
18+27.42	45' LT		30
GRAND TOTAL		90	90

EROSION CONTROL

STATION TO STATION	TEMPORARY DITCH CHECKS EACH 28000300	INLET AND PIPE PROTECTION EACH 28000500	FENCE (EROSION CONTROL) FEET 28000900	INLET PROTECTION, SPECIAL EACH *X2800500
WEST CORBIN				
10+85.10, 41.78' LT		1		
11+36.76, 22.50' LT		1		
11+36.76, 22.50' RT		1		
11+40.90, 22.50' LT		1		
11+40.90, 22.50' RT		1		
11+43.43, 22.50' LT		1		
11+43.43, 22.50' RT		1		
11+48.16, 14.83' LT		1		
11+48.16, 14.83' RT		1		
15+10.22 TO 16+21.19 LT			116	
17+49.44, 14.83' LT		1		
17+49.44, 14.83' RT		1		
20+14.44, 14.83' LT		1		
20+14.44, 14.83' RT		1		
21+53.13 TO 22+40.53 LT			92	
22+49.97 TO 23+15.86 LT			66	
23+00.98, 14.10' LT		1		
23+00.98, 14.10' RT		1		
WEST CORBIN SUB-TOTAL		14	274	
MILES DRIVE				
200+41.14, 19.08' LT				1
200+41.14, 19.08' RT				1
200+54.22 RT	1			
MILES DRIVE SUB-TOTAL	1			2
SCHOOL DRIVEWAY				
501+04.46 LT	1			
500+28.69 TO 502+15.94 LT			197	
502+09.43 LT	1			
SCHOOL DRIVEWAY SUB-TOTAL	2		197	
GRAND TOTAL	3	14	471	2