F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
9089	04-00180-02-PV	MADISON	92	3
FED. ROAD DIST. NO. _	ILLINOIS	FED. AID PROJECT		

CONTRACT NO. 97299

SUMMARY OF QUANTITIES

SUMMARY OF QUANTITIES

CODE NO.	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY
20200100	EARTH EXCAVATION	CU YD	4252
20800150	TRENCH BACKFILL	CU YD	1686
25000100	SEEDING, CLASS 1	ACRE	0.5
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	45
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	45
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	45
25100120	MULCH, METHOD 2	TON	1
28000500	INLET AND PIPE PROTECTION	EACH	82
30200650	PROCESSING MODIFIED SOIL 12"	SQ YD	19834
30201500	LIME	TON	485
31100300	SUB-BASE GRANULAR MATERIAL, TYPE A 4"	SQ YD	19351
31100500	SUB-BASE GRANULAR MATERIAL, TYPE A 6"	SQ YD	483
35101400	AGGREGATE BASE COURSE, TYPE B	TON	76
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	50
40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	250
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	537
42000501	PORTLAND CEMENT CONCRETE PAVEMENT 10" (JOINTED)	SQ YD	17022
42001200	PAVEMENT FABRIC	SQ YD	17022
42001300	PROTECTIVE COAT	SQ YD	23918
42200100	PORTLAND CEMENT CONCRETE RAILROAD CROSSING	SQ YD	62
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD	604
42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	SQ FT	35068
42400800	DETECTABLE WARNINGS	SQ FT	492
44000100	PAVEMENT REMOVAL	SQ YD	17621
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	1029
44000300	CURB REMOVAL	FOOT	5822
44000600	SIDEWALK REMOVAL	SQ FT	21800
44003100	MEDIAN REMOVAL	SQ FT	14378
550B0050	STORM SEWERS, CLASS B, TYPE 1 12"	FOOT	488

SUMMARY OF QUANTITIES

CODE NO.	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY
550B0070	STORM SEWERS, CLASS B, TYPE 1 15"	FOOT	243
550B0340	STORM SEWERS, CLASS B, TYPE 2 12"	FOOT	444
55019500	STORM SEWERS, TYPE 1, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS IV 12"	FOOT	338
55019600	STORM SEWERS, TYPE 1, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS IV 15"	FOOT	220
55019700	STORM SEWERS, TYPE 1, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS IV 18"	FOOT	275
55019900	STORM SEWERS, TYPE 1, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS IV 24"	FOOT	63
55020000	STORM SEWERS, TYPE 1, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS IV 27"	FOOT	148
55021600	STORM SEWERS, TYPE 2, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS III 12"	FOOT	505
55021700	STORM SEWERS, TYPE 2, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS III 15"	FOOT	96
55021800	STORM SEWERS, TYPE 2, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS III 18"	FOOT	160
55022200	STORM SEWERS, TYPE 2, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS III 30"	FOOT	360
55022400	STORM SEWERS, TYPE 2, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS III 36"	FOOT	567
60218400	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	5
60219300	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 11 FRAME AND GRATE	EACH	10
60220400	MANHOLES, TYPE A, SPECIAL, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1
60222000	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 11 FRAME AND GRATE	EACH	7
60223800	MANHOLES, TYPE A, 6'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1
60224020	MANHOLES, TYPE A, 6'-DIAMETER, TYPE 11 FRAME AND GRATE	EACH	8

SUMMARY OF QUANTITIES

CODE NO.	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY
60224038	MANHOLES, TYPE A, 6'-DIAMETER, TYPE 23 FRAME AND GRATE	EACH	1
60236200	INLETS, TYPE A, TYPE 8 GRATE	EACH	11
60236800	INLETS, TYPE A, TYPE 11 FRAME AND GRATE	EACH	6
60237460	INLETS, TYPE A, TYPE 23 FRAME AND GRATE	EACH	1
60240310	INLETS, TYPE B, TYPE 11 FRAME AND GRATE	EACH	37
60255500	MANHOLES TO BE ADJUSTED	EACH	16
60260100	INLETS TO BE ADJUSTED	EACH	1
60500060	REMOVING INLETS	EACH	8
60603500	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.06	FOOT	20
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	6491
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	55
60605900	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-9.12	FOOT	217
60618300	CONCRETE MEDIAN SURFACE, 4 INCH	SQ FT	3229
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	18
67100100	MOBILIZATION	L SUM	1
70101700	TRAFFIC CONTROL AND PROTECTION	L SUM	1
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	9999
70300210	TEMPORARY PAVEMENT MARKING-LETTERS AND SYMBOLS	SQ FT	339
70300220	TEMPORARY PAVEMENT MARKING-LINE 4"	FOOT	14273
70300240	TEMPORARY PAVEMENT MARKING-LINE 6"	FOOT	982
70300250	TEMPORARY PAVEMENT MARKING-LINE 8"	FOOT	53
70300260	TEMPORARY PAVEMENT MARKING-LINE 12"	FOOT	322
70300280	TEMPORARY PAVEMENT MARKING-LINE 24"	FOOT	130
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	6205
* 78008200	POLYUREA PAVEMENT MARKING TYPE I-LETTERS & SYMBOLS	SQ FT	339
* 78008210	POLYUREA PAVEMENT MARKING TYPE I-LINE 4"	FOOT	14273
* 78008230	POLYUREA PAVEMENT MARKING TYPE I-LINE 6"	FOOT	982

* SPECIALTY ITEMS

FINAL SURVEY — BY — DATE — SURVEYED — PLOTTED — NOTE BOOK — TEMPLATE AREAS — AREAS CHECKED — NO.

ORIGINAL SURVEY — BY — DATE — SURVEYED — PLOTTED — NOTE BOOK — TEMPLATE AREAS — AREAS CHECKED — NO.

Juneau Associates, Inc. P.C.
CONSULTING ENGINEERS AND LAND SURVEYORS
2100 State Street • P.O. Box 1325
Granite City, Illinois 62040
Phone:(618)877-4400/(618)452-9536
Fax:(618)452-9541
100 North Bassemth Drive
Edwardsville, Illinois 62025
Phone: (618)659-0800/(618) 659-0800
Fax: (618)659-0941

REVISIONS			
NO.	DATE	BY	REMARKS

DWG. NO.

SUMMARY OF QUANTITIES
F.A.U. ROUTE 9089
20TH STREET (PHASES II, III & IV)
GRANITE CITY, ILLINOIS
SECTION No. 04-00180-02-PV

N.T.S.

DSN. BY:	BFK	DATE:	12/26/06	SHEET
DWN. BY:	DAN	DATE:	12/26/06	3
CHK'D:	BFK	DATE:	12/26/06	
JOB NO.	030204	DGN. NAME:	SUMQTY	OF 92 SHTS