F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
9089	04-00180-02-PV	MADISON	92	14
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

CONTRACT NO. 97299

FINAL SURVEY — NOTE BOOK — NO. — DATE — BY — SURVEYED — PLOTTED — TEMPLATE — AREAS — AREAS CHECKED

STRIPING SCHEDULE

LOCATION	TYPE	POLYUREA								RAISED REFL. PAVT. MKRS		PRISMATIC CURB REFLECTOR (EACH)	PAINT PAVEMENT MARKING RAISED MEDIAN (SQ FT)	PAINT PAVEMENT MARKING CURB (FOOT)
		4" YELLOW (FOOT)	4" WHITE (FOOT)	6" WHITE (FOOT)	8" WHITE (FOOT)	12" YELLOW (FOOT)	12" WHITE (FOOT)	24" WHITE (FOOT)	LETTERS & SYMBOLS (SQ FT)	ONE-WAY AMBER (EACH)	ONE-WAY CRYSTAL (EACH)			
STA. 110+34.87 TO STA. 122+83.02														
	EDGE LINE		2322											
	STOP BARS						39							
	SKIP-DASH 10'-30'		625											
	DOUBLE CENTER LINE	2410												
	CROSSWALKS			268										
STA. 122+83.02 TO STA. 143+69.73										18	24	6	144	450
	EDGE LINE	378	3668		53									
	STOP BARS						116	130						
	SKIP-DASH 10'-30'		940											
	DOUBLE CENTER LINE	3620												
	CROSSWALKS			714										
	LANE LINE		310											
	DIAGNOLS					84	83							
	ARROWS								94					
	RAILROAD XING								245					
TOTAL		6408	7865	982	53	84	238	130	339	18	24	6	144	450

HEAVY HAUL ROAD PAVING SCHEDULE

LOCATION	PROCESS MOD SOIL 12 IN (SQ YD)	LIME (TON)	PC CONC PAVEMENT 24 IN (CU YD)	SUB BASE GRANULAR TY A 6 IN (SQ YD)	PROT COAT (SQ YD)
STA. 132+65.93 TO STA. 132+95.93	233	2.9	156	233	233
STA. 133+20.83 TO STA. 133+50.83	250	3.1	167	250	250
TOTAL	483	6.0	323	483	483

PROTECTIVE COAT SCHEDULE

LOCATION	AREA (SQ YD)
PC CONCRETE PAVEMENT	17022
PC CONCRETE HEAVY HAUL PAVEMENT	483
PC CONCRETE RAILROAD CROSSING	62
COMBINATION CURB AND GUTTER	1511
DRIVEWAY PAVEMENT	585
4" PCC SIDEWALK	3896
4" CONCRETE MEDIAN	359
TOTAL	23918

DOWNSPOUT OUTLET FLUME

LOCATION	DOWNSPOUT OUTLET FLUME (EACH)
STA. 112+09.17 RT	1
STA. 112+49.37 RT	1
STA. 112+91.71 RT	1
STA. 113+37.50 RT	1
STA. 114+25.07 RT	1
STA. 115+08.80 RT	1
STA. 115+93.58 RT	1
STA. 116+77.00 RT	1
STA. 117+62.97 RT	1
STA. 118+33.60 RT	1
STA. 118+75.54 RT	1
STA. 119+17.63 RT	1
STA. 120+06.14 RT	1
STA. 120+36.76 RT	1
STA. 121+28.93 RT	1
STA. 121+83.11 RT	1
TOTAL	16

EARTHWORK SCHEDULE

LOCATION	EARTH EXCAVATION (CU YD)	EARTH EXCAVATION ADJUSTED FOR SHRINKAGE (CU YD)	EMBANKMENT (CU YD)	EARTHWORK BALANCE WASTE(+) OR SHORTAGE(-) (CU YD)
STA. 110+34.87 TO STA. 126+10.50	4252	3189	72	3117
TOTAL	4252	3189	72	3117

P.C.C. RAILROAD CROSSING

LOCATION	PCC RAILROAD CROSSING (SQ YD)	PROT COAT (SQ YD)
STA. 126+02.94 TO STA. 126+11.43	61.9	61.9
TOTAL	62	62

ORIGINAL SURVEY — NOTE BOOK — NO. — DATE — BY — SURVEYED — PLOTTED — TEMPLATE — AREAS — AREAS CHECKED

PAVING SCHEDULE

LOCATION	PROCESS MOD SOIL 12 IN (SQ YD)	LIME (TON)	PC CONC PAVEMENT 10 IN (SQ YD)	SUB BASE GRANULAR TY A 4 IN (SQ YD)	PAVEMENT FABRIC (SQ YD)	PROT COAT (SQ YD)	STAGE CONSTRN INCIDTL HMA SURF (TON)
STA. 110+34.87 TO STA. 126+03.90	8756	217	7872	8756	7872	7872	
STA. 126+10.50 TO STA. 132+65.93	3851	95	3484	3851	3484	3484	
STA. 132+95.93 TO STA. 133+20.83	149	4	131	149	131	131	
STA. 133+50.83 TO STA. 143+69.73	6595	163	5535	6595	5535	5535	
TOTAL	19351	479	17022	19351	17022	17022	500

Juneau Associates, Inc. P.C.
CONSULTING ENGINEERS AND LAND SURVEYORS
2100 State Street, P.O. Box 1325, Granite City, Illinois 62040, Phone: (618) 877-1400/(618) 452-9536, Fax: (618) 452-6941
100 North Kenrick Drive, Edwardsville, Illinois 62025, Phone: (618) 659-0900/(618) 655-0400, Fax: (618) 659-0941

REVISIONS			
NO.	DATE	BY	REMARKS

DWG. NO.

QUANTITY SCHEDULES
F.A.U. ROUTE 9089
20TH STREET (PHASES II, III & IV)
GRANITE CITY, ILLINOIS
SECTION No. 04-00180-02-PV

SCALE: N.T.S.

DSN. BY:	BFK	DATE:	12/26/06	SHEET
DWN. BY:	JJB	DATE:	12/26/06	14
CHK'D:	BFK	DATE:	12/26/06	
JOB NO.	030204	DGN. NAME:	COMSCH	OF 92 SHTS