


F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
9089	04-00180-02-PV	MADISON	92	21
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		
CONTRACT NO. 97289				

**CURB REMOVAL**

LOCATION	CURB TYPE B (FOOT)
STA. 110+34.87-24.22' RT TO STA. 111+37.39-23.70' RT	103
STA. 110+34.87-24.12' LT TO STA. 111+21.77-30.03' LT	91
STA. 111+41.89-29.95' LT TO STA. 111+60.82-30.37' LT	26
STA. 111+74.27-29.83' LT TO STA. 113+16.24-38.00' LT	150
STA. 111+82.54-23.96' RT TO STA. 122+43.00-24.72' RT	1060
STA. 113+44.35-38.00' LT TO STA. 115+25.71-29.92' LT	191
STA. 115+60.48-30.17' LT TO STA. 116+37.01-38.00' LT	89
STA. 116+73.26-38.00' LT TO STA. 120+45.81-30.16' LT	384
STA. 120+66.80-30.21' LT TO STA. 122+02.79-25.89' LT	140
STA. 122+17.51-25.89' LT TO STA. 122+51.02-25.36' LT	34
STA. 122+70.52-25.96' LT TO STA. 122+86.64-35.58' LT	21
STA. 123+49.04-25.45' LT TO STA. 126+02.44-25.42' LT	253
STA. 123+75.79-24.30' RT TO STA. 126+03.00-24.56' RT	227
STA. 126+42.79-39.33' RT TO STA. 129+37.01-38.66' RT	312
STA. 126+44.07-40.00' LT TO STA. 129+37.20-38.88' LT	309
STA. 129+73.04-38.01' RT TO STA. 132+39.04'-24.81' RT	76
STA. 129+73.34-41.00' LT TO STA. 132+63.92-31.18' LT	304
STA. 130+77.59-30.22' RT TO STA. 131+28.31-29.68' RT	58
STA. 131+66.45-24.70' RT TO STA. 131+95.36-24.72' RT	29
STA. 132+13.50-24.65' RT TO STA. 132+65.87-37.30' RT	60
STA. 132+97.55-31.03' LT TO STA. 133+20.42-23.98' LT	26
STA. 132+96.94-30.06' RT TO STA. 133+16.10-24.10' RT	21
STA. 133+52.46-24.08' LT TO STA. 135+87.77-29.58' LT	237
STA. 133+93.96-24.59' RT TO STA. 135+89.20-32.89' RT	199
STA. 136+19.80-35.47' RT TO STA. 139+13.42-30.20' RT	301
STA. 136+22.84-29.58' LT TO STA. 139+15.22-38.46' LT	303
STA. 139+44.24-38.47' LT TO STA. 141+56.06-27.43' LT	221
STA. 139+47.23-30.28' RT TO STA. 139+60.88-24.65' RT	16
STA. 139+96.26-24.18' RT TO STA. 140+73.81-25.82' RT	77
STA. 141+08.00-27.00' RT TO STA. 141+47.95-28.73' RT	40
STA. 141+84.09-30.59' RT TO STA. 142+19.02-32.53' RT	35
STA. 142+02.88-28.94' LT TO STA. 142+56.23-33.55' LT	54
STA. 142+43.09-34.61' RT TO STA. 142+56.31-126.52' RT	172
STA. 143+06.06-40.78' LT TO STA. 143+69.99-108.48' LT	110
STA. 143+61.66-45.77' LT TO STA. 143+71.96-40.86' LT	12
STA. 143+71.96-40.86' LT TO STA. 143+73.31-57.39' LT	17
STA. 143+61.66-45.77' LT TO STA. 143+73.31-57.39' LT	17
STA. 143+51.44-25.79' RT TO STA. 143+65.47-19.59' RT	15
STA. 143+51.44-25.79' RT TO STA. 143+63.80-35.90' RT	16
STA. 143+63.80-35.90' RT TO STA. 143+65.47-19.59' RT	16
<b>TOTAL</b>	<b>5822</b>

FINAL SURVEY	SURVEYED	BY	DATE
NOTE BOOK	PLOTTED		
NO.	TEMPLATE		
	AREAS		
	CHECKED		

ORIGINAL SURVEY	SURVEYED	BY	DATE
NOTE BOOK	PLOTTED		
NO.	TEMPLATE		
	AREAS		
	CHECKED		

 <b>Juneau Associates, Inc. P.C.</b> CONSULTING ENGINEERS AND LAND SURVEYORS <small>2102 State Street, P.O. Box 1335 Granite City, Illinois 62040 Phone: (618) 877-4000/(618) 877-0235 Fax: (618) 877-0241</small>		<b>QUANTITY SCHEDULES</b> F.A.U. ROUTE 9089 20TH STREET (PHASES II, III & IV) GRANITE CITY, ILLINOIS SECTION No. 04-00180-02-PV									
REVISIONS <table border="1"> <tr> <th>NO.</th> <th>DATE</th> <th>BY</th> <th>REMARKS</th> </tr> <tr> <td> </td> <td> </td> <td> </td> <td> </td> </tr> </table>		NO.	DATE	BY	REMARKS					SCALE: N.T.S.	
NO.	DATE	BY	REMARKS								
DSN. BY: BFK DWN. BY: JJB CHKD: BFK		DATE: 12/26/06 DATE: 12/26/06 DATE: 12/26/06									
DWG. NO.		JOB NO. 030204 DGN. NAME: COMSCH OF 92 SHTS									

21