

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	WILLIAMSON	917	7
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

\* FAI 57 & FAU 9629 (OLD IL 13)  
 \*\* (X1-6-2)WB-2, (X1-6)HBK-2

# SUMMARY OF QUANTITIES

		WILLIAMSON URBAN											
		F. A. I. 57						FAU 9629 (OLD IL 13)					
		90% FEDERAL/ 10% STATE-ACIM						90% FED 10% STATE	100% STATE	90% FED 10% STATE	90% FED 10% CITY		
CODE NUMBER	ITEM DESCRIPTION	UNIT	QUANTITY	ROADWAY	BRIDGE	BRIDGE	BRIDGE	BRIDGE	LIGHTING	SIGNALS	SIGNALS	ROADWAY	ROADWAY
				STA 1500+00 TO STA 1556+85	100-0084 TO 100-0085	100-0086 TO 100-0087	100-0008 TO 100-0009	100-0005		SB I57 RAMP ACIM	VA & NB I57 RAMP	STA. 753+20 TO STA. 784+40 ACIM	STA. 753+20 TO STA. 784+40 ACIM
				1000-2A	X271-2A	X171-5B	SFTY-2A	SFTY-2A	Y030-1E	Y031-1F	Y031-1F	1000-2A	1000-2A
													8.0
X0300203	CLEAN AND FILL EXPANSION JOINTS	EACH	8.0										
X0300471	RUBBLIZING PORTLAND CEMENT CONCRETE PAVEMENT	SQ YD	17,159.0	17,159.0						1.0	1.0		
X0300737	RADIO TRANSCEIVER	EACH	2.0										
X0322066	PROTECTIVE SHIELD (PERMANENT)	SQ YD	878.0				878.0						
X0322662	TEMPORARY SIGNING	EACH	3.0				3.0						
X0322729	MATERIAL TRANSFER DEVICE	TON	2,362.0	2,362.0									
X0322879	GRADING AND SHAPING FORESLOPES	SQ YD	431.0	431.0									
X0323991	SURFACE MOUNT LANE SEPARATOR	FOOT	792.0										792.0
51202305	DRIVING PILES	FOOT	8,079.0		2,739.0	5,340.0							34.0
X6060500	CORRUGATED MEDIAN REMOVAL	SQ FT	34.0										
X6370940	CONCRETE BARRIER, DOUBLE FACE, 42 INCH HEIGHT	FOOT	3,116.0	3,116.0									
X7050169	TEMPORARY TRAFFIC BARRIER TERMINAL, TYPE 1 SPECIAL (FLARED)	EACH	1.0	1.0									4.0
X7240205	REMOVE SIGN COMPLETE	EACH	21.0	17.0									
X7330105	OVERHEAD SIGN STRUCTURE WALKWAY, TYPE A	FOOT	57.0	57.0									
X7330110	OVERHEAD SIGN STRUCTURE WALKWAY, CANTILEVER, TYPE A	FOOT	14.0	14.0									6.6
X7340100	CONCRETE FOUNDATIONS, GROUND MOUNT	CU YD	24.4	17.8									
X8420220	REMOVE EXISTING HIGH MAST LIGHT TOWER	EACH	10.0						10.0				
X8420300	LIGHTING FOUNDATION REMOVAL, LIGHT TOWER	EACH	6.0						6.0				
XX003813	ELECTRIC CABLE IN CONDUIT, NO. 10 3/C	FOOT	1,529.0							497.0	1,032.0		
XX006661	UNINTERRUPTIBLE POWER SUPPLY	EACH	2.0							1.0	1.0		
<del>Z0006600</del>	<del>BRIDGE DECK CONCRETE OVERLAY</del>	<del>SQ YD</del>	<del>2,007.0</del>										
<del>Z0006601</del>	<del>BRIDGE DECK HYDRO GRANIT FORTION 1/2"</del>	<del>SQ YD</del>	<del>1,953.0</del>										
Z0016001	DECK SLAB RPAIR (FULL DEPTH, TYPE I)	SQ YD	115.1				84.0						
Z0016002	DECK SLAB REPAIR (FULL DEPTH, TYPE II)	SQ YD	300.0				200.0						
Z0016200	DECK SLAB REPAIR (PARTIAL)	SQ YD											1,768.0
Z0017202	DOWEL BARS 1 1/2"	EACH	1,768.0										
X0325744	STATE FURNISHED BORROW (SELECT)	CU YD	33,200	33,200									
X0325745	STATE FURNISHED BORROW (RESTRICTED)	CU YD	44,700	44,700									

\*\* HSIP FUNDING  
 90% FED. / 10% STATE  
 \* SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

## SUMMARY OF QUANTITIES 1 OF 12

SCALE: VERT.  
 DATE: HORIZ.

DRAWN BY JCK  
 CHECKED BY

Rev. 4-16-07  
 Rev. 4-10-07

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	WILLIAMSON	917	8
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

\* FAI 57 & FAU 9629 (OLD IL 13)  
 \*\* IX1-6-2IVB-2, IX1-6IHBK-2

# SUMMARY OF QUANTITIES

		WILLIAMSON URBAN											
		F. A. I. 57					FAU 9629 (OLD IL 13)						
		90% FEDERAL/ 10% STATE - ACIM					90% FED 10% STATE SIGNALS	100% STATE SIGNALS	90% FED 10% STATE ROADWAY	90% FED 10% CITY ROADWAY			
CODE NUMBER	ITEM DESCRIPTION	UNIT	QUANTITY	ROADWAY	BRIDGE	BRIDGE	BRIDGE	BRIDGE	LIGHTING	90% FED 10% STATE SIGNALS	100% STATE SIGNALS	90% FED 10% STATE ROADWAY	90% FED 10% CITY ROADWAY
				I000-2A	X271-2A	X171-5B	SFTY-2A	SFTY-2A	Y030-1E	Y031-1F	Y031-1F	I000-2A	I000-2A
Z0030130	IMPACT ATTENUATORS (PARTIALLY REDIRECTIVE), TEST LEVEL 3	EACH	1.0										
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	8										
Z0030260	IMPACT ATTENUATORS, TEMPORARY (FULLY REDIRECTIVE, NARROW), TEST LEVEL 3	EACH	8										
Z0030330	IMPACT ATTENUATORS, RELOCATE (FULLY REDIRECTIVE), TEST LEVEL 3	EACH	7.0										
Z0030350	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3	EACH	4.0					2.0					
Z0040400	PIPE CULVERT (EROSION CONTROL)	FOOT	1,712.0										
Z0040530	PIPE UNDERDRAIN REMOVAL	FOOT	19,949.0										
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1.0										
Z0073500	TEMPORARY SUPPORT SYSTEM	L SUM	1.0			1.0							
Z0076600	TRAINEES	HOURL	2000		2000								
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	1,915.0										
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	1,259.0										
20100500	TREE REMOVAL, ACRES	ACRE	13.2										
20200100	EARTH EXCAVATION	CU YD	60,910		54,321							5,689.0	
20400100	BORROW EXCAVATION	CU YD	24,641		24,641								
20700400	POROUS GRANULAR EMBANKMENT, SPECIAL	CU YD	838.0			440.0	398.0						
20800150	TRENCH BACKFILL	CU YD	3507		1654							1,853.0	
21101665	TOPSOIL FURNISH AND PLACE, 18"	SQ YD	392.0									392.0	
25000115	SEEDING, CLASS 1B	ACRE	23.8		21.7								2.1
25000350	SEEDING, CLASS 7	ACRE	25.9		23.8								2.1
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	3024		3514								310.0
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	2033.5		2601								232.5
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	2033.5		2601								232.5
25000700	AGRICULTURAL GROUND LIMESTONE	TON	47.5		43.5								4.0
25100115	MULCH, METHOD 2	ACRE	45.5		45.5								
25100630	EROSION CONTROL BLANKET	SQ YD	65,816.0		56,438.0							9,378.0	
25101005	HEAVY DUTY EXCELSIOR BLANKET	SQ YD	2929		2929								
28000200	EARTH EXCAVATION FOR EROSION CONTROL	CU YD	45.0		33.0							12.0	
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	2564		2370							194.0	
28000300	TEMPORARY DITCH CHECKS	EACH	110.0		87.0							23.0	
28000400	PERIMETER EROSION BARRIER	FOOT	16,635		16,635								
28000500	INLET AND PIPE PROTECTION	EACH	31.0		14.0							17.0	
28001000	AGGREGATE (EROSION CONTROL)	TON	168.2		167.0							1.2	

△ SFTY-3N  
 © Y080

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

## SUMMARY OF QUANTITIES

2 OF 12

SCALE: VERT.  
 HORIZ.  
 DATE

DRAWN BY JCK  
 CHECKED BY

B. Rev. 4-16-07