

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	WILLIAMSON	917	8
STA.			TO STA.	
FED. ROAD DIST. NO.			ILLINOIS FED. AID PROJECT	

- * FAI 57 & FAU 9629 (OLD IL 13)
- ** (X1-6-2)VB-2, (X1-6)HBK-2

SUMMARY OF QUANTITIES

		WILLIAMSON										
		URBAN										
		F. A. I. 57					FAU 9629 (OLD IL 13)					
		90% FEDERAL/ 10% STATE - ACIM					90% FED 10% STATE	100% STATE	90% FED 10% STATE	90% FED 10% CITY		
		ROADWAY	BRIDGE	BRIDGE	BRIDGE	BRIDGE	LIGHTING	SIGNALS	SIGNALS	ROADWAY	ROADWAY	
		STA 1500+00 TO STA 1556+85	100-0084 TO 100-0085	100-0086 TO 100-0087	100-0008 TO 100-0009	100-0005		SB I57 RAMP ACIM	VA & NB I57 RAMP	STA. 753+20 TO STA. 784+40 ACIM	STA. 753+20 TO STA. 784+40 ACIM	
		CONSTRUCTION TYPE CODE	I000-2A	X271-2A	X171-5B	SFTY-2A	SFTY-2A	Y030-1E	Y031-1F	Y031-1F	I000-2A	I000-2A
CODE NUMBER	ITEM DESCRIPTION	UNIT	QUANTITY									
Z0030130	IMPACT ATTENUATORS (PARTIALLY REDIRECTIVE), TEST LEVEL 3	EACH	1.0	1.0								
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	9	8								
Z0030260	IMPACT ATTENUATORS, TEMPORARY (FULLY REDIRECTIVE, NARROW), TEST LEVEL 3	EACH	8	8								
Z0030330	IMPACT ATTENUATORS, RELOCATE (FULLY REDIRECTIVE), TEST LEVEL 3	EACH	7.0	7.0								
Z0030350	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3	EACH	4.0	2.0								
Z0040400	PIPE CULVERT (EROSION CONTROL)	FOOT	1,712.0	1,712.0								
Z0040530	PIPE UNDERDRAIN REMOVAL	FOOT	19,949.0	19,949.0								
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1.0	1.0								
Z0073500	TEMPORARY SUPPORT SYSTEM	L SUM	1.0									
Z0076600	TRAINEES	hour	2000	2000								
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	1,915.0	1,915.0								
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	1,259.0	1,259.0								
20100500	TREE REMOVAL, ACRES	ACRE	13.2	13.2								
20200100	EARTH EXCAVATION	CU YD	60,010	54,321								
20400100	BORROW EXCAVATION	CU YD	102,241	102,241								
20700400	POROUS GRANULAR EMBANKMENT, SPECIAL	CU YD	838.0		440.0	398.0						
20800150	TRENCH BACKFILL	CU YD	3507	1654								
21101665	TOPSOIL FURNISH AND PLACE, 18"	SO YD	392.0									
25000115	SEEDING, CLASS 1B	ACRE	23.8	21.7								
25000350	SEEDING, CLASS 1	ACRE	26.7	23.8								
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	3824	3514								
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	2835.5	2601								
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	2835.5	2601								
25000700	AGRICULTURAL GROUND LIMESTONE	TON	47.5	43.5								
25100115	MULCH, METHOD 2	ACRE	45.5	45.5								
25100630	EROSION CONTROL BLANKET	SO YD	65,816.0	56,438.0								
25101005	HEAVY DUTY EXCELSIOR BLANKET	SO YD	2929	2929								
28000200	EARTH EXCAVATION FOR EROSION CONTROL	CU YD	45.0	33.0								
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	2564	2370								
28000300	TEMPORARY DITCH CHECKS	EACH	110.0	87.0								
28000400	PERIMETER EROSION BARRIER	FOOT	16,635	16,635								
28000500	INLET AND PIPE PROTECTION	EACH	31.0	14.0								
28001000	AGGREGATE (EROSION CONTROL)	TON	168.2	167.0								

ASPT-3N
© 1090

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES
 2 OF 12
 SCALE: VERT. DATE
 HORIZ. DATE
 DRAWN BY JCK
 CHECKED BY