

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	WILLIAMSON	917	14
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

• FAI 57 & FAU 9629 (OLD IL 13)  
 \*\* (X1-6-2)VB-2, (X1-6)HBK-2

# SUMMARY OF QUANTITIES

CODE NUMBER	ITEM DESCRIPTION	UNIT	QUANTITY	WILLIAMSON										
				URBAN										
				F. A. I. 57 90% FEDERAL/ 10% STATE - ACIM						FAU 9629 (OLD IL 13)				
WORK TYPE	ROADWAY	BRIDGE	BRIDGE	BRIDGE	BRIDGE	LIGHTING	90% FED 10% STATE SIGNALS	100% STATE SIGNALS	90% FED 10% STATE ROADWAY	90% FED 10% CITY ROADWAY				
	STA 1500+00 TO STA 1556+85	100-0084 100-0085	100-0086 100-0087	100-0008 100-0009	100-0005		SB 157 RAMP ACIM	VA & NB 157 RAMP	STA. 753+20 TO STA. 784+40 ACIM	STA. 753+20 TO STA. 784+40 ACIM				
CONSTRUCTION TYPE CODE	I000-2A	X271-2A	X171-5B	SFTY-2A	SFTY-2A	Y030-1E	Y031-1F	Y031-1F	I000-2A	I000-2A				
60218400	MANHOLES, TYPE A, 4' -DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1.0								1.0			
60218900	MANHOLES, TYPE A, 4' -DIAMETER, TYPE 6 FRAME AND GRATE	EACH	2.0	2.0										
60221000	MANHOLES, TYPE A, 5' -DIAMETER, TYPE 1 FRAME, OPEN LID	EACH	1.0								1.0			
60223700	MANHOLES, TYPE A, 6' -DIAMETER, TYPE 1 FRAME, OPEN LID	EACH	1.0								1.0			
60224030	MANHOLES, TYPE A, 6' -DIAMETER, TYPE 15 FRAME AND LID	EACH	1.0								1.0			
60236200	INLETS, TYPE A, TYPE 8 GRATE	EACH	2.0	1.0							1.0			
60237420	INLETS, TYPE A, TYPE 20 FRAME AND GRATE	EACH	3.0	3.0										
60238900	INLETS, TYPE A, SPECIAL, TYPE 1 FRAME, OPEN LID	EACH	2.0								2.0			
60240215	INLETS, TYPE B, TYPE 1 FRAME, CLOSED LID	EACH	1.0								1.0			
60240240	INLETS, TYPE B, TYPE 6 FRAME AND GRATE	EACH	4.0	4.0										
60240301	INLETS, TYPE B, TYPE 8 GRATE	EACH	1.0								1.0			
60243300	INLETS, SPECIAL, TYPE 3, 5'	EACH	12.0								12.0			
60243500	INLETS, SPECIAL, TYPE 3, 6'	EACH	6.0								6.0			
60247200	JUNCTION BOX	EACH	1.0								1.0			
60260100	INLETS TO BE ADJUSTED	EACH	3.0								3.0			
60270050	DRAINAGE STRUCTURES, TYPE 4 WITH TWO TYPE 20 FRAMES AND GRATES	EACH	20.0	20.0										
60406100	FRAMES AND LIDS, TYPE 1, CLOSED LID	EACH	1.0								1.0			
60500060	REMOVING INLETS	EACH	20.0	7.0							13.0			
60500105	FILLING MANHOLES	EACH	3.0								3.0			
60603500	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.06	FOOT	556.0	311.0							245.0			
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	4,253.0	1,060.0							3,193.0			
60618300	CONCRETE MEDIAN SURFACE, 4 INCH	SQ FT	8,217.0	4,118.0							4,099.0			
60623714	CONCRETE MEDIAN (SPECIAL)	SQ FT	733.0								733.0			
60624600	CORRUGATED MEDIAN	SQ FT	34.0								34.0			
60900515	CONCRETE THRUST BLOCKS	EACH	1.0	1.0										
* 63000000	STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	4,157.0	4,157.0										

\*SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

**SUMMARY OF QUANTITIES**

**8 OF 12**

SCALE: VERT. \_\_\_\_\_  
 HORIZ. \_\_\_\_\_

DATE \_\_\_\_\_

DRAWN BY JCK  
 CHECKED BY \_\_\_\_\_

PLOT DATE = 12/14/2005  
 FILE NAME = S:\projects\9822882\old\13\old\13\sh-m32  
 PLOT SCALE = 50.0000' / IN.  
 USER NAME = krenzlp