CONTRACT NO. 98950

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	WILLIAMSON	917	22
STA.	TO STA.			
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

* FAI 57 & FAU 9629 (OLD IL 13)
** (X1-6-2)VB-2, (X1-6)HBK-2

CONCRETE PAVEMENT

LOCATION STA TO STA	PCC PAVEMENT 8" (JOINTED) SQ YD	PCC PAVEMENT 10" (JOINTED) SQ YD	BRIDGE APPROACH PAVEMENT (SPECIAL) SQ YD	PCC DRIVEWAY PAVEMENT 6" SQ YD	PCC DRIVEWAY PAVEMENT 7" SQ YD	PROTECTIVE COAT SQ YD	BRIDGE DECK GROOVING SQ YD	SUB-BASE GRANULAR MATERIAL, TYPE A 6" SQ YD	SUB-BASE GRANULAR MATERIAL, TYPE A 4" SQ YD
FAI 57									
STAGE 4	0.0	0.0	906.0	0.0	0.0	906.0	873.0	0.0	0.0
STAGE 5	0.0	1,913.0	0.0	0.0	0.0	1,915.0	0.0	0.0	0.0
STAGE 6	0.0	2,476.0	0.0	0.0	0.0	2,477.0	0.0	0.0	0.0
STAGE 7	0.0	0.0	1,167.0	0.0	0.0	1,127.0	1,100.0	0.0	0.0
FAI 57 PROJECT TOTALS	0.0	4,389.0	2,073.0	0.0	0.0	6,425.0	1,973.0	0.0	0.0
FAU 9629 (OLD IL 13)									
STA. 761+33 TO STA. 762+36.2		60.0				60.0		60.0	
RT. STA. 762+09 CRISP DR.				176.0		176.0			
STA. 771+98 TO STA. 774+66		404.0				404.0		403.0	
RT. STA. 777+48					110.0	110.0			
RT. STA. 781+83					62.0	62.0			
STA. 0+30 TO STA. 0+80 NEW ST.	661.0					661.0			762.0
FAU 9629 (OLD IL 13) PROJECT TOTALS	661.0	464.0	0.0	176.0	172.0	1,473.0	0.0	463.0	762.0
SCHEDULE PROJECT SUB-TOTALS	661.0	4,853.0	2,073.0	176.0	172.0	7,898.0	1,973.0	463.0	762.0
FROM CONCRETE CURB & GUTTER SCHEDULE						2,415.0		51.0	
FROM CONCRETE BARRIER SCHEDULE						3,803.0			
FROM SIDEWALK SCHEDULE						1,188.0			
FROM BRIDGE PLANS							7,001.0		
PROJECT TOTALS	661.0	4,853.0	2,073.0	176.0	172.0	15,304.0	8,974.0	514.0	762.0

REVISIONS NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE

SCALE: VERT.
HORIZ.
DATE

DRAWN BY JCK
CHECKED BY

PLOT DATE = 1/18/2007
FILE NAME = c:\projects\d9829282\old13sch.m32
PLOT SCALE = 50.0000 / IN.
USER NAME = krenz_jc