CONTRACT NO. 98950

| F.A. RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
|---|---|---|---|---|
| * | ** | WILLIAMSON | 917 | 26 |
| STA. | | TO STA. | | |
| FED. ROAD DIST. NO. | ILLINOIS | FED. AID PROJECT | | |

* FAI 57 & FAU 9629 (OLD IL 13)
** (X1-6-2)VB-2, (X1-6)HBK-2

# STORM SEWERS

| LOCATION | STORM SEWERS, CLASS A, TYPE 1 | | | | | | | | STORM SEWERS, CLASS A, TYPE 2 | | | PRC FLARED END SECTIONS | | | | TRENCH BACKFILL | CONCRETE COLLAR | REINFORCED CONCRETE PIPE ELBOW 24" | REINFORCED CONCRETE PIPE TEE 12" W/12" RISER | CONCRETE THRUST BLOCKS |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | 12" | 15" | 18" | 21" | 24" | 27" | 36" | 42" | 12" | 21" | 24" | 12" | 18" | 21" | 24" | | | | | |
| | FOOT | FOOT | FOOT | FOOT | FOOT | FOOT | FOOT | FOOT | FOOT | FOOT | FOOT | EACH | EACH | EACH | EACH | CU YD | CU YD | EACH | EACH | EACH |
| FAI 57 | | | | | | | | | | | | | | | | | | | | |
| STAGE 4 | 0 | 0 | 0 | 0 | 36 | 0 | 0 | 0 | 35 | 0 | 26 | 1 | 0 | 0 | 1 | 70 | 1.12 | 2 | 0 | 1 |
| STAGE 5 | 429 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 206 | 0 | 0 | 1 | 0 |
| STAGE 6 | 469 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 169 | 0 | 0 | 0 | 0 |
| STAGE 7 | 366 | 391 | 513 | 258 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 907 | 0 | 0 | 0 | 0 |
| STAGE 7C | 172 | 172 | 244 | 22 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 302 | 0.5 | 0 | 0 | 0 |
| FAI 57 PROJECT TOTALS | 1436 | 563 | 757 | 280 | 36 | 0 | 0 | 0 | 35 | 0 | 26 | 1 | 0 | 0 | 1 | 1,654.0 | 1.6 | 2 | 1 | 1 |
| FAU 9629 (OLD IL 13) | | | | | | | | | | | | | | | | | | | | |
| RT STA 761+53 TO STA 761+85 | | | | | | 31 | | | | | | | | | | | | | | |
| RT STA 762+10 | | | | | | | | | | | | | | 2 | | | | | | |
| RT STA 764+61 | | | | | | | | | | | | | 1 | | | | | | | |
| RT STA 764+61 TO STA 764+90 | | | 24 | | | | | | | | | | | | | | | | | |
| RT STA 764+90 TO STA 765+35 | | | 42 | | | | | | | | | | | | | 9.2 | | | | |
| RT STA 765+35 TO STA 765+50 | 24 | | | | | | | | | | | | | | | 4.0 | | | | |
| RT STA 765+50 | | | | | | | | | | | | 1 | | | | | | | | |
| RT STA 765+35 TO STA 766+02 | 64 | | | | | | | | | | | | | | | 18.3 | | | | |
| RT STA 767+68 TO STA 768+21 | 53 | | | | | | | | | | | | | | | 12.7 | | | | |
| RT STA 768+21 TO STA 768+77 | 50 | | | | | | | | | | | | | | | | | | | |
| RT STA 768+77 | | | | | | | | | | | | 1 | | | | | | | | |
| RT STA 771+65 | | | | | | | | | | | | 1 | | | | | | | | |
| RT STA 771+65 TO STA 771+72 | 5 | | | | | | | | | | | | | | | | | | | |
| LT STA 773+75 TO STA 773+85.5 | 5 | | | | | | | | | | | | | | | | | | | |
| RT STA 773+75 TO STA 774+10. | | | | | | 29 | | 29 | | | | | | | | 21.8 | | | | |
| RT STA 773+77.5 | 11 | | | | | | | | | | | | | | | 10.3 | | | | |
| LT STA 773+85.5 | | | | | | | | | | | | | | | | 4.0 | | | | |
| RT STA 774+10 TO STA 774+48. | | | | | | 33 | | 33 | | | | | | | | 22.9 | | | | |
| RT STA 774+48 TO STA 774+53 | | | 17 | | | | | | | | | | | | | 6.6 | | | | |
| RT STA 774+48 TO STA 775+10 | 58 | | | | | | | | | | | | | | | 22.6 | | | | |
| RT STA 774+48 TO STA 775+60 | | | | | | | 108 | | | | | | | | | 79.6 | | | | |



| REVISIONS | |
|---|---|
| NAME | DATE |

ILLINOIS DEPARTMENT OF TRANSPORTATION

**SCHEDULE**

SCALE: VERT. HORIZ.
DATE
DRAWN BY JCK
CHECKED BY

PLOT DATE = 1/18/2007
FILE NAME = c:\projects\d902802\cldi3\cldi3sch.m32
PLOT SCALE = 50.0000 ' / IN.
USER NAME = kranzjo