CONTRACT NO. 98950

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	WILLIAMSON	917	34
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

* FAI 57 & FAU 9629 (OLD IL 13)
** (X1-6-2)VB-2, (X1-6)HBK-2

DRAINAGE REMOVAL

LOCATION STATION	PAVED DITCH REMOVAL	CONCRETE HEADWALL REMOVAL		PIPE CULVERT REMOVAL			REMOVING INLETS	FILLING MANHOLES	STORM SEWER REMOVAL						TRENCH BACKFILL	CONCRETE REMOVAL	CLASS B PATCHES, TYPE IV, 10 INCH
		INFO. ONLY		INFORMATION ONLY					12"	15"	18"	24"	30"	48"			
	FOOT	REMOVAL (CU YDS)	EACH	CULVERT SIZE (INCH)	CULVERT TYPE	FOOT	EACH	EACH	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	CU YD	CU YD	SQ YD
FAU 9629 (OLD IL 13)																	
LT. STA. 755+15 TO STA. 755+31				18	RCCP	16											
RT. STA. 758+80	4																
RT. STA. 762+68 TO STA. 763+09				15	CPP	41									5.0		
RT. STA. 771+00 TO STA. 771+63	63																
STA. 771+47															113.0	7.0	54.0
RT. STA. 771+63		2.6	1														
RT. STA. 771+63 TO STA. 772+97														134	272.0		
LT. STA. 772+80							1										
LT. STA. 772+80 TO STA. 772+95									20						19.0		
STA. 773+00				60	RCCP	80									200.0		69.0
LT. STA. 773+00		5.4	1														
RT. STA. 773+00								1									
LT. STA. 773+07		0.8	1														
LT. STA. 773+09 TO STA. 773+51				18	RCCP	24									8.0		
LT. STA. 773+51		0.7	1														
RT. STA. 773+61 TO STA. 774+48													110		67.0		
LT. STA. 774+17		0.3	1				1		13								
RT. STA. 774+48							1										
RT. STA. 775+05								1									
RT. STA. 775+14								1									
RT. STA. 775+22							1										
RT. STA. 775+22 TO STA. 775+61													39		18.0		
RT. STA. 775+26 TO STA. 775+62												45			11.0		
RT. STA. 775+61							2			12					2.0		
RT. STA. 775+61 TO STA. 775+94												35			13.0		
RT. STA. 775+61 TO STA. 777+26													165		115.0		
RT. STA. 777+69							1										
RT. STA. 777+69 TO STA. 777+97												28			20.0		
RT. STA. 777+85 TO STA. 778+00												15			12.0		
RT. STA. 778+00							2					9			16.0		
RT. STA. 778+00 TO STA. 779+98												198			98.0		
RT. STA. 779+98							1										
RT. STA. 779+98 TO STA. 781+54												156			70.0		
RT. STA. 781+54							1										
RT. STA. 782+25							1										
RT. STA. 782+25 TO STA. 783+96											171				53.0		
RT. STA. 783+96							1										
FAU 9629 (OLD IL 13) PROJECT TOTALS	67		5			161	13	3	33	12	171	486	314	134	1112	7	123
SCHEDULE PROJECT SUB-TOTALS	139		17			447	20	3	33	12	171	538	314	134	1,112	10	123
FROM STORM SEWER SCHEDULE															2,088		
FROM BOX CULVERT SCHEDULE															163		
FROM PIPE CULVERT SCHEDULE															144		
PROJECT TOTALS	139		17			447	20	3	33	12	171	538	314	134	3,507	10	123

2 OF 2

REVISIONS NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE

SCALE: VERT. HORIZ.
DATE
DRAWN BY JCK
CHECKED BY

PLOT DATE = 1/10/2007
FILE NAME = c:\projects\d902802\old3\old3sch.dgn
PLOT SCALE = 50.0000 ' / IN.
USER NAME = krenzje