F.A. RTE.	SECTION	1 C	OUNT	Y	TOTAL SHEETS	SHEET NO.		
	**	W	ILLIAN	MSON	917	36		
STA.		TO	TO STA.					
FED. ROA	D DIST. NO.	ILLINOIS	FED.	AID	PROJECT	Γ		

- * FAI 57 & FAU 9629 (OLD IL 13)
- ** (X1-6-2)VB-2, (X1-6)HBK-2

PIPE UNDERDRAINS

LOCATION STATION TO STATION	PIPE UNDERDRAINS 4" FOOT	PIPE UNDERDRAINS 4" (SPECIAL) FOOT	CONCRETE HEADWALL FOR PIPE DRAINS EACH	SHOULDER REMOVAL & REPLACEMENT 8" FOOT	PIPE UNDERDRAIN REMOVAL FOOT	COMMENTS
FAI 57						
STAGE 1	3,612	167	5	0	3, 691	
STAGE 1A	6, 949	752	2	0	7,012	
STAGE 2	759	0	0	0	413	
STAGE 3	3, 630	341	0	0	3, 943	
STAGE 4	4,376	412	7.	90	4, 713	
STAGE 5	3, 114	80	5	0	118	
STAGE 6	3, 920	120	2	0	0	
STAGE 8	0	10	1	0	59	
FAI 57 PROJECT TOTALS	26, 360	1,882	22	90	19, 949	
FAU 9629 (OLD IL 13) PROJECT TOTALS	0	0	0	0	0	
PROJECT TOTALS	26, 360	1,882	22	90	19, 949	

NOTE: 1.) EXISTING CONCRETE HEADWALLS DETERMINED BY THE ENGINEER TO BE IN GOOD CONDITION SHALL BE CLEANED AND REUSED ACCORDING TO THE SCHEDULE.

NEW RODENT SHIELDS SHALL BE INSTALLED. THE COST SHALL BE INCLUDED IN THE PROPOSED PIPE UNERDRAINS 4" (SPECIAL)

2.) THE REMOVAL OF THE EXISTING PIPE UNDERDRAINS 4" (SPECIAL) SHALL BE PAID FOR AS PIPE UNDERDRAIN REMOVAL.

3.) THE CONTRACTOR MUST PROTECT THE ENDS OF THE PIPE UNDERDRAINS BETWEEN STAGES OF CONSTRUCTION, NO EXTRA COMPENSATION WILL BE GIVEN.

4.) AT SAG LOCATIONS, BOTH PIPE UNDERAINS 4" (SPECIAL) SHALL BE MEASURED FOR PAYMENT.

5.) THE PIPE UNDERDRAINS 4" SHALL BE CONNECTED TO THE EXISTING UNDERDRAINS AT THE ENDS OF THE JOB DETERMINED BY THE ENGINEER.

REVISIONS		THINOTS	DEDADTMENT OF	TRANSPORTATION			
NAME	DATE	ILLINOI3	DEL ARTMENT OF	TRANSFORTATION			
-							
		SCHEDULE					
			OUILE	/ L-L			

		VERT.					
		SCALE: HORIZ.		DRAWN BY JCK			
***************************************		DATE		CHECKED BY			