CONTRACT NO. 98950

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	WILLIAMSON	917	47
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

* FAI 57 & FAU 9629 (OLD IL 13)
** (X1-6-2)VB-2, (X1-6)HBK-2

SEEDING

LOCATION STATION TO STATION	TEMPORARY EROSION CONTROL SEEDING	SEEDING, CLASS 1B	SEEDING, CLASS 7	NITROGEN FERTILIZER NUTRIENT	PHOSPHORUS FERTILIZER NUTRIENT	POTASSIUM FERTILIZER NUTRIENT	AGRICULTURAL GROUND LIMESTONE	MULCH, METHOD 2
	POUND	ACRE	ACRE	POUND	POUND	POUND	TON	ACRE
FAI 57								
STAGE 1	130.0	1.29	1.30	208.0	155.0	155.0	2.6	2.59
STAGE 1A	105.0	1.05	1.05	169.0	126.0	126.0	2.1	2.10
STAGE 2	2.0	0.00	0.08	3.4	0.0	0.0	0.0	0.08
STAGE 3	495.0	3.94	4.95	670.0	473.0	473.0	7.9	8.89
STAGE 4	520.0	3.75	5.20	657.0	450.0	450.0	7.5	8.95
STAGE 5	289.0	2.81	2.89	459.0	338.0	338.0	5.7	5.70
STAGE 6	544.0	4.83	5.44	846.0	580.0	580.0	9.7	10.27
STAGE 7C	5.0	0.05	0.05	8.0	6.0	6.0	0.1	0.10
STAGE 8	280.0	3.94	2.80	493.0	473.0	473.0	7.9	6.74
FAI 57 PROJECT TOTALS	2,370.0	21.66	23.76	3,513.4	2,601.0	2,601.0	43.5	45.42
FAU 9629 (OLD IL 13)								
LT STA 755+18 TO STA 761+35	32.8	0.3	0.3	52.6	39.4	39.4	0.7	
LT STA 763+00 TO STA 766+05	13.3	0.1	0.1	21.3	16.0	16.0	0.3	
RT STA 757+25 TO STA 761+97	41.4	0.4	0.4	66.3	49.7	49.7	0.8	
RT STA 762+23 TO STA 766+08	25.1	0.3	0.3	40.1	30.1	30.1	0.5	
RT STA 767+63 TO STA 771+95	26.1	0.3	0.3	41.7	31.3	31.3	0.5	
RT STA 771+65 TO STA 772+80	4.3	0.1	0.1	6.9	5.2	5.2	0.1	
RT STA 772+70 TO STA 774+67	9.6	0.1	0.1	15.3	11.5	11.5	0.2	
RT STA 775+07 TO STA 777+27	5.7	0.1	0.1	9.1	6.8	6.8	0.1	
RT STA 777+66 TO STA 781+80	13.2	0.1	0.1	21.1	15.8	15.8	0.3	
RT STA 782+05 TO STA 784+05	4.6	0.1	0.1	7.3	5.5	5.5	0.1	
CRISP DRIVE								
STA 10+80 TO STA 13+00	17.7	0.2	0.2	28.3	21.2	21.2	0.4	
FAU 9629 (OLD IL 13) PROJECT TOTALS	193.8	2.10	2.10	310.0	232.5	232.5	4.0	0.00
PROJECT TOTALS	2,563.8	23.76	25.86	3,823.4	2,833.5	2,833.5	47.5	45.42

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE

SCALE: VERT. HORIZ.
DATE

DRAWN BY JCK
CHECKED BY

PLOT DATE = 1/17/2007
FILE NAME = c:\projects\d902802\old13\old13sch.m32
PLOT SCALE = 50.0000 ' / IN.
USER NAME = kranzjo