

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	WILLIAMSON	917	50

STA. TO STA.
 FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT

- * FAI 57 & FAU 9629 (OLD IL 13)
- ** (X1-6-2)VB-2, (X1-6)HBK-2

PERMANENT PAVEMENT MARKINGS

LOCATION STATION TO STATION	THERMOPLASTIC PAVEMENT MARKING								PREFORMED PLASTIC PAVEMENT MARKING											
	SOLID WHITE FOOT	LINE 4" SKIP-DASH YELLOW FOOT	SOLID YELLOW FOOT	LINE 6" SOLID WHITE FOOT	LINE 8" SOLID WHITE FOOT	LINE 12"		LINE 24" SOLID WHITE FOOT	LETTERS AND SYMBOLS SQ FT	TYPE B - LINE 4"			TY B - LINE 8" WHITE FOOT	TY B - LINE 12" WHITE FOOT						
						SOLID WHITE FOOT	SOLID YELLOW FOOT			WHITE FOOT	YELLOW FOOT	WHT. SKIP-DASH FOOT								
FAI 57 NORTHBOUND																				
STA. 1506+90 TO STA. 1512+12														283						
STA. 1506+90 TO STA. 1509+63										78	273		70							
STA. 1509+63 TO STA. 1510+48.26 BK										171	85		20							
STA. 1510+49.48 AH TO STA. 1511+69										242	120		30							
STA. 1511+69 TO STA. 1516+69										85	500		130							
STA. 1512+55 TO STA. 1516+62													100							
STA. 1516+69 TO STA. 1528+26										2078	1157		290							
STA. 1528+26 TO STA. 1534+86											660		170							
STA. 1534+86 TO STA. 1543+00										814	814		200	360						
FAI 57 SOUTHBOUND																				
STA. 1500+00 TO STA. 1503+05																				
STA. 1503+05 TO STA. 1508+10 ENTERING FROM RAMP C										305	305		80							
STA. 1508+10 TO STA. 1509+43.50 BK											505		130	505						
STA. 1509+15.58 AH TO STA. 1519+39										624	1,023		60							
STA. 1513+09 TO STA. 1519+39 EXITING RAMP F													360	630						
STA. 1515+57 TO STA. 1523+50																				
STA. 1519+39 TO STA. 1529+50										1182	1011		250	277						
STA. 1529+50 TO STA. 1555+97											2647		660							
RAMP E																				
STA. 3+48 TO STA. 13+27										979			979							
STA. 13+27 TO STA. 15+66																				
STA. 15+60 TO STA. 20+18														239						
RAMP EE																				
STA. 0+00 TO STA. 6+60																				
STA. 3+00 TO STA. 6+60																				
STA. 6+60 TO STA. 16+70										1,010			1,010	360						
RAMP F																				
STA. 0+00 TO STA. 4+54																				
STA. 4+54 TO STA. 12+62										808			808							
STA. 0+71 TO STA. 4+55														384						
RAMP FF																				
STA. 3+37.79 TO STA. 8+36										498			498							
STA. 8+36 TO STA. 10+65																				
STA. 8+36 TO STA. 37+16.72																				
STA. 10+65 TO STA. 26+50										2,881			400	229						
RAMP C (SB I-57 STATIONING)																				
STA. 1502+10 TO STA. 1505+27										326										
STA. 1502+80 TO STA. 1503+05													25							
STA. 1505+27 TO STA. 1507+08										181										
STA. 1503+05 TO STA. 1504+90														185						
RAMP B																				
STA. 0+00 TO STA. 2+73														468						
FAI 57 PROJECT SUB-TOTALS										3,802	0	3,320	0	0	0	10,733	9,234	2,950		
FAI 57 PROJECT TOTALS											7,122	0	0	424	0	0	0	22,917	2,707	560

1 OF 3

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION	
NAME	DATE	SCHEDULE	
		SCALE: VERT. DRAWN BY JCK	
		HORIZ. CHECKED BY	
		DATE	