CONTRACT NO. 98950

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	WILLIAMSON	917	130
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

* I-57, & OLD IL 13 (FAU 9629)
** (X1-6-2)VB-2,(X1-6)HBK-2

STORM SEWER, CLASS A, TY. 1 18"
DSFL ELEV. = 459.85

STA. 1540+78
DRAINAGE STRUCTURES, TY. 4 WITH TWO TY. 20 FRAMES AND GRATES, 1 EACH
TOP OF GRATE ELEV. = 466.25 (RT. NB)
TOP OF GRATE ELEV. = 466.01 (LT. SB)
INVERT ELEV. = 460.35

PROJECT ENDS
STA. 1542+33 NB I-57

STORM SEWER, CLASS A, TY. 1 12"
DSFL ELEV. = 461.85

STA. 1542+25
DRAINAGE STRUCTURES, TY. 4 WITH TWO TY. 20 FRAMES AND GRATES, 1 EACH
TOP OF GRATE ELEV. = 465.74 (RT. NB)
TOP OF GRATE ELEV. = 465.56 (LT. SB)
INVERT ELEV. = 461.10

EXIST. ROW LINE

℄ I-57 NB

IMPROVEMENT ENDS
STA. 1551+75 NB I-57

RAMP "FF"

STA. 1541+75
DRAINAGE STRUCTURES, TY. 4 WITH TWO TY. 20 FRAMES AND GRATES, 1 EACH
TOP OF GRATE ELEV. = 465.91 (RT. NB)
TOP OF GRATE ELEV. = 465.71 (LT. SB)
INVERT ELEV. = 460.85

EXIST. ROW LINE

POT Sta 21+92.87

POT Sta 31+66.61

℄ I-57 SB

CONSTRUCTION LIMITS
(TYP.)

STORM SEWER, CLASS A, TY. 1 15"
DSFL ELEV. = 460.35

1540+00 1545+00 1550+00 1555+00
25+00 30+00 35+00
1543+00
12' 12' 12' 12' 16' 12' 12' 12' 12' 8'

N

50' 0 25' 50'

459.97
18" 15" 12"
+75 INVERT ELEV. 460.35
+75 INVERT ELEV. 460.85
+25 INVERT ELEV. 461.10

480 475 470 465 460 455 450 445 440

1540+00 1541+00 1542+00 1543+00 1544+00 1545+00 1546+00 1547+00 1548+00 1549+00 1550+00 1551+00 1552+00 1553+00 1554+00 1555+00

PLAN
SURVEYED
PLOTTED
ALIGNMENT CHECKED
CADD FILE NAME
NOTE BOOK
NO.
DATE

PROFILE
SURVEYED
PLOTTED
GRADES CHECKED
CADD FILE NAME
NOTE BOOK
NO.
STRUCTURE NO'ATANS CHKD
BY
DATE

PLOT DATE = 12/7/2005
FILE NAME = c:\projects\98288\2\sht03\sht03p1.dgn
PLOT SCALE = 50.0000 ' / IN.
USER NAME = hendon

I-57 MEDIAN STORM SEWER – STA. 1540+00 TO STA. 1555+00