CONTRACT NO. 98950

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	WILLIAMSON	917	149
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

* FAI 57 & FAU 9629 (OLD IL 13)
** (X1-6-2)VB-2, (X1-6)HBK-2

EARTHWORK - FAI 57 STAGE 1

LOCATION STA TO STA	EARTH EXCAVATION	FOR INFORMATION ONLY					BORROW EXCAVATION	REMARKS
		AVERAGE SHRINKAGE FACTOR	EARTH EXCAVATION (ADJUSTED)	EMBANKMENT	EARTHWORK BALANCE WASTE (+) SHORTAGE (-)	BORROW SWELL FACTOR		
	CU YD	%	CU YD	CU YD	CU YD	%	CU YD	
FAI 57								
STA 1542+33 TO STA 1556+90 MEDIAN	572	36.8%	361	45	316			
RT STA 1499+70 TO STA 1510+00	494	17.2%	410	5,937	-5,527			
FAI 57 STAGE 1 PROJECT TOTAL	**1,066**	27.0%	771	5,982	-5,211	25.0%	**6,514**	

REVISIONS NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE

SCALE: VERT. HORIZ.
DATE
DRAWN BY JCK
CHECKED BY

PLOT DATE = 1/16/2007
FILE NAME = c:\projects\d9802802\old13\old13sch_n32
PLOT SCALE = 50.0000 ' / IN.
USER NAME = kvenajo