CONTRACT NO. 98950

			~~				
F.A RTE.	SECTION		COUNTY			TOTAL	SHEE NO.
*	**		₩	ILLIAN	/SON	917	15
STA.			ТО	STA.			
FED. ROA	D DIST. NO.	ILLIN	OIS	FED.	AID	PROJECT	

- * FAI 57 & FAU 9629 (OLD IL 13) ** (X1-6-2)VB-2, (X1-6)HBK-2

GUARD RAIL - FAI 57 STAGE 1

LOCATION STATION TO STATION	CORING FOR GUARDRAIL INSTALLATION FOOT	TEMPORARY TRAFFIC BARRIER TERMINAL, TYPE 1, (FLARED) EACH		TERMINAL,			TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (FLARED) EACH	REMOVAL	TEMPORARY STEEL PLATE BEAM GUARDRAIL, TYPE A FOOT	TRAFFIC BARRIER TERMINAL,	TEMPORARY TRAFFIC BARRIER TERMINAL, TYPE 6	TEMPORARY TRAFFIC BARRIER TERMINAL, TYPE 10 EACH	REMARKS
FAI 57 SOUTHBOUND													
RT (OUTSIDE SHOULDER)										N. C			
STA. 1501+89 TO STA. 1510+00							1	843.0	805.0				NOTE 1
FAI 57 STAGE 1 PROJECT TOTALS	0.0	0	0.0	0	0	0	1	843.0	805.0	0	0	0	

NOTE: 1.) THE FACE OF THE TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (FLARED) SHALL BE PLACED NEXT TO THE SHOULDER IN THE 2 FT BITUMINOUS SHOULDER. THE FACE OF THE TEMPORARY STEEL PLATE BEAM GUARDRAIL, TYPE A SHALL BE PLACED NEXT TO THE 2 FT BITUMINOUS SHOULDER WITH A TAPER BETWEEN THEM SHOWN ON THE PLANS. SEE TYPICAL FOR MORE CLARIFICATION. THE TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (FLARED) SHALL USE A FLARE RATE OF 15:1.

ILLINOIS DEPARTMENT OF TRANSPORTATION **SCHEDULE** SCALE: VERT. CHECKED BY