CONTRACT NO. 98950

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
•	••	WILLIAMSON	917	172
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

• FAI 57 & FAU 9629 (OLD IL 13)
•• (X1-6-2)VB-2, (X1-6)HBK-2

RAISED PAVEMENT MARKERS - FAI 57 STAGE 1A

LOCATION STATION TO STATION	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	RAISED REFLECTIVE PAVEMENT MARKER		
		ONE-WAY AMBER	TWO-WAY AMBER	ONE-WAY CRYSTAL
	EACH	EACH	EACH	EACH
FAI 57				
NORTHBOUND				
STA. 1505+56 TO STA. 1515+56	13			
STA. 1505+56 TO STA. 1515+56				26
STA. 1517+63 TO STA. 1528+73	14			
STA. 1517+63 TO STA. 1528+73				28
STA. 1531+15 TO STA. 1543+18	15			
STA. 1531+15 TO STA. 1543+18				31
SOUTHBOUND				
STA. 1499+15 TO STA. 1515+53	21			
STA. 1499+15 TO STA. 1515+53				41
STA. 1517+61 TO STA. 1528+70	14			
STA. 1517+61 TO STA. 1528+70				28
STA. 1531+19 TO STA. 1543+18	15			
STA. 1531+19 TO STA. 1543+18				30
FAI 57 STAGE 1A PROJECT SUBTOTALS		0	0	184
FAI 57 STAGE 1A PROJECT TOTALS	92	184		

REVISIONS NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE

SCALE: VERT. HORIZ.
DATE
DRAWN BY JCK
CHECKED BY

PLOT DATE = 1/16/2007
FILE NAME = c:\projects\x\x9823082\sht03\sht03sch.sh32
PLOT SCALE = 50.0000 ' / IN.
USER NAME = kranz.jo