

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	WILLIAMSON	917	189

STA. TO STA.

FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT

• FAI 57 & FAI 9629 (OLD IL 13)

\*\* (X1-6-2)VB-2, (X1-6)HBK-2

### BITUMINOUS PAVEMENT - FAI 57 STAGE 2

LOCATION STATION TO STATION	POLYMERIZED BITUMINOUS CONCRETE SURFACE COURSE SUPERPAVE MIX D, N105 TON	POLYMERIZED BITUMINOUS CONCRETE SURFACE COURSE SUPERPAVE MIX E, N105 TON	POLYMERIZED BITUMINOUS CONCRETE BINDER COURSE SUPERPAVE IL-19.0, N105 TON	BITUMINOUS CONCRETE BINDER COURSE SUPERPAVE IL-19.0, N90		BITUMINOUS CONCRETE PAVEMENT (FULL DEPTH) SUPERPAVE, 14 1/4"			STABILIZED SUB-BASE 4" SQ YD	STABILIZED SUB-BASE (VARIABLE DEPTH) TON	SUB-BASE GRANULAR MATERIAL, 6" SQ YD	SUB-BASE GRANULAR MATERIAL, 10" SQ YD	SUB-BASE GRANULAR MATERIAL, TYPE C TON	BITUMINOUS MATERIAL (PRIME COAT) GALLON	AGGREGATE (PRIME COAT) TON	MATERIAL TRANSFER DEVICE TON
				INFO. ONLY		FOR INFORMATION ONLY										
				THICKNESS (IN.)	TON	POLY BIT SURFACE MIX D, N105 1 1/2" TON	POLY BIT BINDER IL-19.0, N105 2 1/4" TON	BIT BINDER IL-19.0, N90 10 1/2" TON								
<b>FAI 57</b>																
<b>NORTHBOUND</b>																
STA 1512+10 TO STA 1513+25			23.0	12.75	130.0									58		
STA 1512+10 TO STA 1515+56										557.0						
STA 1513+25 TO STA 1515+56			47.0	12.75	268.0									120		
STA 1523+45 TO STA 1525+86			168.0	9.75	731.0					1,332.0				430		
<b>SOUTHBOUND</b>																
STA 1520+43 TO STA 1522+15			82.0	9.75	358.0					651.0				211		
<b>FAI 57 STAGE 2 PROJECT TOTALS</b>	<b>0</b>	<b>0</b>	<b>320</b>		<b>1,487</b>			<b>0</b>	<b>0</b>	<b>0</b>	<b>2,540</b>	<b>0</b>	<b>0</b>	<b>819</b>	<b>0</b>	<b>0</b>

PLOT DATE = 10/26/2006  
 FILE NAME = c:\prow\msh\c992092\old\13\old13sh.m32  
 PLOT SCALE = 50.0000' / IN.  
 USER NAME = kranzj

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE

SCALE: VERT. \_\_\_\_\_  
 HORIZ. \_\_\_\_\_

DATE \_\_\_\_\_

DRAWN BY JCK  
 CHECKED BY \_\_\_\_\_