CONTRACT NO. 98950

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	WILLIAMSON	917	193
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

* FAI 57 & FAU 9629 (OLD IL 13)
** (X1-6-2)VB-2, (X1-6)HBK-2

EARTHWORK - FAI 57 STAGE 2

LOCATION STA TO STA	EARTH EXCAVATION	FOR INFORMATION ONLY AVERAGE SHRINKAGE FACTOR	EARTH EXCAVATION (ADJUSTED)	EMBANKMENT	EARTHWORK BALANCE WASTE (+) SHORTAGE (-)	BORROW SWELL FACTOR	BORROW EXCAVATION	REMARKS
	CU YD	%	CU YD	CU YD	CU YD	%	CU YD	
FAI 57								
LT STA 1512+10 TO STA 1515+56	117	0.0%	117	0	117			
LT STA 1523+20 TO STA 1525+86	220	19.6%	177	451	-274			
RT STA 1520+43 TO STA 1522+30	134	30.9%	93	32	61			
FAI 57 STAGE 2 PROJECT TOTAL	471	16.8%	387	483	-96	25.0%	120	

REVISIONS NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE

SCALE: VERT. HORIZ.
DATE

DRAWN BY JCK
CHECKED BY

PLOT DATE = 1/16/2007
FILE NAME = c:\projects\d902802\old13\old13sch.m32
PLOT SCALE = 50.0000 ' / IN.
USER NAME = kranzjc