

PAVEMENT MARKING REMOVAL - FAI 57 STAGE 2

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	**	WILLIAMSON	917	196
STA. TO STA.				
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

- FAI 57 & FAU 9629 (OLD IL 13)
- (X1-6-2)VB-2, (X1-6)HBK-2

LOCATION STATION TO STATION	PAVEMENT MARKING REMOVAL		WORK ZONE PAVEMENT MARKING REMOVAL SQ FT	REMARKS
	DASH LINE SQ FT	SOLID LINE SQ FT		
	FAI 57 NORTHBOUND			
STA. 1506+05 TO STA. 1506+90	0	57		
STA. 1506+90 TO STA. 1507+81	8	30		
STA. 1507+81 TO STA. 1510+48.26 BK	22	179		
STA. 1510+49.47 AH TO STA. 1510+95	4	31		
STA. 1510+95 TO STA. 1518+78	65	261		
STA. 1517+30 TO STA. 1518+78	12	0		LEFT DASH LINE ON RAMP E
STA. 1518+78 TO STA. 1526+85	67	538		
STA. 1526+85 TO STA. 1530+71	32	129		
STA. 1530+71 TO STA. 1542+33	97	775		
STA. 1542+33 TO STA. 1543+18	0	85		
FAI 57 SOUTHBOUND				
STA. 1499+15 TO STA. 1500+00	0	85		
STA. 1500+00 TO STA. 1504+00	33	267		
STA. 1503+10 TO STA. 1504+00	0	90		RIGHT AND LEFT EDGE LINES ON RAMP C
STA. 1504+00 TO STA. 1505+10.50	18	70		
STA. 1504+00 TO STA. 1505+10.50	18	70		RIGHT EDGE LINE AND LEFT DASH LINE ON RAMP C
STA. 1505+10.50 TO STA. 1509+43.50 BK	28	222		
STA. 1509+15.58 AH TO STA. 1517+34	68	546		
STA. 1517+34 TO STA. 1519+37	17	68		
STA. 1519+37 TO STA. 1526+25	57	459		
STA. 1526+25 TO STA. 1527+90	14	0		LEFT DASH LINE ON RAMP FF
STA. 1526+25 TO STA. 1535+56	78	310		
STA. 1535+56 TO STA. 1542+33	57	451		
STA. 1542+33 TO STA. 1543+18	0	85		
FAI STAGE 2 PROJECT SUBTOTAL	695	4,808	0	
FAI 57 STAGE 2 PROJECT TOTAL				
	5,503		0	

RAISED PAVEMENT MARKERS - FAI STAGE 2

LOCATION STATION TO STATION	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL EACH	RAISED REFLECTIVE PAVEMENT MARKER		
		ONE-WAY AMBER EACH	TWO-WAY AMBER EACH	ONE-WAY CRYSTAL EACH
		FAI 57 NORTHBOUND		
STA. 1505+56 TO STA. 1515+56	26			26
STA. 1517+63 TO STA. 1528+73	28			28
STA. 1531+15 TO STA. 1543+18	31			31
STA. 1543+18 TO STA. 1550+85	10			20
FAI 57 SOUTHBOUND				
STA. 1499+15 TO STA. 1515+53	41			41
STA. 1517+61 TO STA. 1528+70	28			28
STA. 1531+19 TO STA. 1543+18	30			30
STA. 1543+18 TO STA. 1556+85	17			35
STA. 1543+18 TO STA. 1556+85				35
FAI 57 STAGE 2 PROJECT SUBTOTALS		0	0	239
FAI 57 STAGE 2 PROJECT TOTALS		211		239

REVISIONS	NAME	DATE	ILLINOIS DEPARTMENT OF TRANSPORTATION
			SCHEDULE
			SCALE: VERT. DRAWN BY JCK
			DATE: CHECKED BY