CONTRACT NO. 98950

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	WILLIAMSON	917	217
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

* FAI 57 & FAU 9629 (OLD IL 13)
** (X1-6-2)VB-2, (X1-6)HBK-2

BITUMINOUS PAVEMENT - FAI 57 STAGE 3

LOCATION STATION TO STATION	POLYMERIZED BITUMINOUS CONCRETE SURFACE COURSE SUPERPAVE MIX D, N105	POLYMERIZED BITUMINOUS CONCRETE SURFACE COURSE SUPERPAVE MIX E, N105	POLYMERIZED BITUMINOUS CONCRETE BINDER COURSE SUPERPAVE IL-19.0, N105	BITUMINOUS CONCRETE BINDER COURSE SUPERPAVE IL-19.0, N90 INFO. ONLY		BITUMINOUS CONCRETE PAVEMENT (FULL DEPTH) SUPERPAVE, 14 1/4" FOR INFORMATION ONLY				STABILIZED SUB-BASE 4"	STABILIZED SUB-BASE (VARIABLE DEPTH)	SUB-BASE GRANULAR MATERIAL, 6"	SUB-BASE GRANULAR MATERIAL, 10"	SUB-BASE GRANULAR MATERIAL, TYPE C	BITUMINOUS MATERIAL (PRIME COAT)	AGGREGATE (PRIME COAT)	MATERIAL TRANSFER DEVICE
						POLY BIT SURFACE MIX D, N105 1 1/2"	POLY BIT BINDER IL-19.0, N105 2 1/4"	BIT BINDER IL-19.0, N90 10 1/2"									
	TON	TON	TON	THICKNESS (IN.)	TON	TON	TON	TON	SQ YD	SQ YD	TON	SQ YD	SQ YD	TON	GALLON	TON	TON
FAI 57																	
NORTHBOUND																	
STA 1506+90 TO STA 1509+35			65.0	11.00	328.0								54	229			
STA 1506+90 TO STA 1508+87			6.0	12.75	33.0									15			
STA 1509+35 TO STA 1510+48.26 BK			38.0	11.00	191.0							390.0	8	101			
STA 1510+49.47 AH TO STA 1511+62			32.0	11.00	158.0							337.0	8	84			
STA 1510+50 TO STA 1512+10			27.0	12.75	154.0							109.0		69			
STA 1511+62 TO STA 1513+00			26.0	9.75	117.0							308.0	7	70			
STA 1538+90 TO STA 1541+00			81.0	9.75	358.0							782.0	10	213			
STA 1541+00 TO STA 1542+33			51.0	9.75	227.0							495.0	6	135			
STA 1542+33 TO STA 1550+00			177.0	9.75	789.0							1,907.0	36	474			
SOUTHBOUND																	
STA 1536+00 TO STA 1536+85			6.0	15.00	24.0									9			
STA 1536+00 TO STA 1536+85			30.0	11.00	152.0							298.0	5	80			
STA 1536+85 TO STA 1537+00			6.0	11.00	29.0							53.0	1	15			
STA 1537+00 TO STA 1541+00			155.0	11.00	771.0							1,405.0	24	407			
STA 1541+00 TO STA 1542+33			51.0	11.00	256.0							467.0	8	135			
STA 1542+33 TO STA 1544+96		56.0	85.0	11.00	423.0							715.0	21	224			
STA 1544+96 TO STA 1547+22.5 SEE NOTE 1		38.0	58.0	11.00	291.0							496.0	4	155			
STA 1547+22.5 TO STA 1550+46.5		55.0	83.0	11.00	416.0							710.0		222			
STA 1550+46.5 TO STA 1553+46.75		42.0	64.0	11.00	324.0							558.0		173			
STA 1553+46.75 TO STA 1556+00		29.0	43.0	11.00	221.0							386.0		119			
FAI 57 STAGE 3 PROJECT TOTALS	0	220	1,084		5,262				0	0	0	9,416	0	192	2,929	0	0

NOTE: 1.) SUB-BASE GRANULAR MATERIAL, TYPE C ENDS AT STA 1545+51.

REVISIONS NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE

SCALE: VERT. HORIZ.
DATE
DRAWN BY JCK
CHECKED BY

PLOT DATE = 1/16/2007
FILE NAME = c:\pr_objects\d902802\old13ach.m32
PLOT SCALE = 50.0000 ' / IN.
USER NAME = kramzjo