CONTRACT NO. 98950

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	WILLIAMSON	917	218
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

* FAI 57 & FAU 9629 (OLD IL 13)
** (X1-6-2)VB-2, (X1-6)HBK-2

SHOULDERS - FAI 57 STAGE 3

LOCATION STATION TO STATION	PAVED SHOULDER REMOVAL	BITUMINOUS SHOULDERS, SUPERPAVE	BITUMINOUS SHOULDERS SUPERPAVE 6 1/2"	BITUMINOUS SHOULDERS SUPERPAVE 8"	BITUMINOUS SHOULDERS SUPERPAVE 8 1/2"	BITUMINOUS SHOULDERS SUPERPAVE 9 1/2"	AGGREGATE SHOULDERS, TYPE A 8"	AGGREGATE SHOULDERS, TYPE B	BITUMINOUS MATERIALS (PRIME COAT)	SHOULDER RUMBLE STRIP	REMARKS
	SQ YD	TON	SQ YD	SQ YD	SQ YD	SQ YD	SQ YD	TON	GALLON	FOOT	
FAI 57											
NORTHBOUND											
LT (OUTSIDE SHOULDER)											
STA. 1506+90 TO STA. 1509+35	205			176.1							
STA. 1509+35 TO STA. 1510+48.26 BK	106			31.5							
STA. 1510+49.47 AH TO STA. 1511+62	91			31.3							
STA. 1511+62 TO STA. 1512+31	55			19.2							
STA. 1512+31 TO STA. 1513+00	57			15.3							
STA. 1538+90 TO STA. 1541+00	233			46.7							AREA AROUND EXISTING DELINEATOR
STA. 1541+17	4										
STA. 1541+00 TO STA. 1542+33	148			29.6							AREA AROUND EXISTING DELINEATOR
STA. 1542+33 TO STA. 1550+00	852			170.3							AREA AROUND EXISTING DELINEATOR
STA. 1546+16 TO STA. 1556+00											
STA. 1545+00	2										
STA. 1549+15	2										
SOUTHBOUND											
RT (OUTSIDE SHOULDER)											
STA. 1536+00 TO STA. 1536+85				19.0							
STA. 1536+85 TO STA. 1542+33				122.0							
STA. 1536+00 TO STA. 1541+00	556										
STA. 1539+93	3										AREA AROUND EXISTING DELINEATOR
STA. 1541+00 TO STA. 1550+25	1,028										
STA. 1542+33 TO STA. 1545+51				71.0							
STA. 1543+95	3										AREA AROUND EXISTING DELINEATOR
STA. 1545+51. TO STA. 1556+00							234				
STA. 1547+95	3										AREA AROUND EXISTING DELINEATOR
STA. 1550+25 TO STA. 1556+00	639										
STA. 1551+95	3										AREA AROUND EXISTING DELINEATOR
FAI 57 STAGE 3 PROJECT TOTALS	3,990	0.0	0.0	732.0	0.0	0.0	234.0	0.0	0.0	0.0	

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE

SCALE: VERT. HORIZ.
DATE

DRAWN BY JCK
CHECKED BY

PLOT DATE = 1/16/2007
FILE NAME = c:\projects\d902802\oldi3\oldi3sch.m32
PLOT SCALE = 50.0000 ' / IN.
USER NAME = kranzjo