

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
•	**	WILLIAMSON	917	223
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

- FAI 57 & FAU 9629 (OLD IL 13)
- ** (X1-6-21VB-2, (X1-6)HBK-2

LIME MODIFIED SOILS - FAI 57 STAGE 3

LOCATION STA TO STA	PROCESSING MODIFIED SOILS 12"	LIME	FOR INFO. ONLY WATER
	SQ YD	TON	UNIT
FAI 57 NORTHBOUND			
LT. STA. 1506+90 TO STA. 1509+35	847.0	25.0	13.0
FAI 57 STAGE 3 PROJECT TOTALS	847.0	25.0	13.0

EARTHWORK - FAI 57 STAGE 3

LOCATION STA TO STA	EARTH EXCAVATION CU YD	FOR INFORMATION ONLY					BORROW SWELL FACTOR %	BORROW EXCAVATION CU YD	REMARKS
		AVERAGE SHRINKAGE FACTOR %	EARTH EXCAVATION (ADJUSTED) CU YD	EMBANKMENT CU YD	EARTHWORK BALANCE WASTE (+) SHORTAGE (-) CU YD				
FAI 57									
LT STA 1506+00 TO STA 1513+00	279	15.8%	235	8,784	-8,549				
LT STA 1538+90 TO STA 1550+50	3,531	24.5%	2,665	1,665	1,000				
RT STA 1530+67 TO STA 1556+20	8,610	23.0%	6,630	3,436	3,194				
STOCKPILE					4,270			SOIL FROM FAI 57 STAGE 1A - SEE SPECIAL PROVISIONS	
FAI 57 STAGE 3 PROJECT TOTAL	12,420	21.1%	9,530	13,885	-85	25.0%	106		

PLOT DATE = 1/16/2007
 FILE NAME = s:\p\o\m\sta\9829\2\ad13\ad13shu32
 PLOT NAME = 20.0000 / IN.
 USER NAME = jprajup

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE

SCALE: VERT. DATE DRAWN BY JCK
 HORIZ. DATE CHECKED BY