CONTRACT NO. 98950

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	WILLIAMSON	917	225
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

* FAI 57 & FAU 9629 (OLD IL 13)
** (X1-6-2)VB-2, (X1-6)HBK-2

EROSION CONTROL - FAI 57 STAGE 3

LOCATION STATION TO STATION	PIPE CULVERT (EROSION CONTROL) FOOT	EROSION CONTROL BLANKET SQ YD	HEAVY DUTY EXCELSIOR BLANKET SQ YD	PERIMETER EROSION BARRIER FOOT	EARTH EXCAVATION FOR EROSION CONTROL CU YD	AGGREGATE (EROSION CONTROL) TON	TEMPORARY DITCH CHECKS EACH	INLET & PIPE PROTECTION EACH	END SECTIONS 8" EACH	REMARKS
FAI 57										
NORTHBOUND										
LT STA 1506+10	10.0					2.0			1.0	
LT STA 1506+26	28.0					2.0			1.0	
LT STA 1505+95 TO STA 1513+00		4,671.0		742.0						APPROXIMATE OFFSET =100'
LT STA 1506+18 TO STA 1513+00				704.0						APPROXIMATE OFFSET =80'
LT STA 1508+85	29.0					2.0			1.0	
LT STA 1508+88	9.0					2.0			1.0	
LT STA 1510+85	13.0					2.0			1.0	
LT STA 1510+88	36.0					2.0			1.0	
LT STA 1512+87	14.0					2.0			1.0	
LT STA 1512+90	34.0					2.0			1.0	
LT STA 1538+90 TO STA 1550+00		4,578.0								
LT STA 1539+50							1.0			
LT STA 1542+35							1.0			
LT STA 1542+50					11.0	1.0				
LT STA 1545+20							1.0			
LT STA 1546+15							1.0			
LT STA 1547+15							1.0			
LT STA 1548+15							1.0			
LT STA 1549+15							1.0			
SOUTHBOUND										
RT STA 1536+00 TO STA 1555+97		4,381.0								
RT STA 1530+90								1.0		
RT STA 1530+24					11.0	1.0				
RT STA 1532+00							1.0			
RT STA 1535+00							1.0			
RT STA 1537+00							1.0			
RT STA 1538+90							1.0			
RT STA 1539+62								1.0		
RT STA 1541+00							1.0			
RT STA 1542+00							1.0			
RT STA 1544+00							1.0			
RT STA 1545+00							1.0			
RT STA 1546+00							1.0			
RT STA 1546+76								1.0		
RT STA 1549+05							1.0			
RT STA 1551+35							1.0			
RT STA 1553+65							1.0			
FAI 57 STAGE 3 PROJECT TOTAL	**173.0**	**13,630.0**	**0.0**	**1,446.0**	**22.0**	**18.0**	**19.0**	**3.0**	**8.0**	

REVISIONS NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE

SCALE: VERT. HORIZ.
DATE
DRAWN BY JCK
CHECKED BY

PLOT DATE = 12/14/2006
FILE NAME = c:\pw_acts\d9928282\old13\old13sch.m32
PLOT SCALE = 50.0000 ' / IN.
USER NAME = krenzjo