

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	WILLIAMSON	917	323
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

BARRIER DELINEATION - FAI 57 STAGE 4

LOCATION STA TO STA	GUARDRAIL MARKERS, TYPE B	BARRIER WALL MARKERS, TYPE B	TERMINAL MARKERS DIRECT APPLIED
	EACH	EACH	EACH
FAI 57			
NORTHBOUND			
LT STA 1513+00 TO STA 1514+95	3		
LT STA 1513+00 TO STA 1523+50		8	
LT STA 1514+95 TO STA 1515+93	2		
LT STA 1526+86 TO STA 1540+74		9	
LT STA 1528+80 TO STA 1529+12	1		
LT STA 1530+84 TO STA 1537+02	7		1
SOUTHBOUND			
RT STA 1508+18 TO STA 1519+25		8	
RT STA 1510+00 TO STA 1515+91	7		
RT STA 1521+65 TO STA 1536+03		9	
LT STA 1509+28 TO STA 1511+28		4	
LT STA 1520+70 TO STA 1527+10		7	
RAMP FF			
RT STA 12+01 TO STA 12+70	2		
RT STA 14+37 TO STA 16+00	3		
FAI 57 STAGE 4 PROJECT TOTALS	25	45	1

- FAI 57 & FAU 9629 (OLD IL 13)
- (X1-6-2)VB-2, (X1-6)HBK-2

ATTENUATORS - FAI 57 STAGE 4

LOCATION STATION TO STATION	IMPACT ATTENUATORS, (PARTIALLY REDIRECTIVE), TEST LEVEL 3	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	IMPACT ATTENUATORS, TEMPORARY (FULLY REDIRECTIVE, NARROW), TEST LEVEL 3	IMPACT ATTENUATORS, RELOCATE (FULLY REDIRECTIVE), TEST LEVEL 3	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3	REMARKS
	EACH	EACH	EACH	EACH	EACH	
FAI 57						
NORTHBOUND						
RT (OUTSIDE SHOULDER)						
STA 1540+09.5				1		FROM RT STA 1550+85 (NBL)
LT (OUTSIDE SHOULDER)						
STA 1523+45			1			
STA 1540+65					1	FROM LT STA 1551+41 (NBL)
SOUTHBOUND						
RT (OUTSIDE SHOULDER)						
STA 1521+65			1			
STA 1508+18					1	FROM RT STA 1510+00 (SBL)
LT (INSIDE SHOULDER)						
STA 1509+31				1		FROM LT STA 1511+28 (SBL)
STA 1520+70				1		FROM LT STA 1527+20 (SBL)
FAI 57 STAGE 4 PROJECT TOTALS	0	0	2	3	2	

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE

SCALE: VERT. DATE
HORIZ. DATE

DRAWN BY JCK
CHECKED BY

PLOT DATE = 12/16/2008
FILE NAME = c:\projects\98950\old3\old3.dwg
PLOT SCALE = 1/8" = 1'-0"
USER NAME = krentzjp