CONTRACT NO. 98950

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	WILLIAMSON	917	369
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

* FAI 57 & FAU 9629 (OLD IL 13)
** (X1-6-2)VB-2, (X1-6)HBK-2

SURFACE REMOVAL - FAI 57 STAGE 5

LOCATION STA TO STA	BITUMINOUS SURFACE REMOVAL - BUTT JOINT	BITUMINOUS SURFACE REMOVAL 5"	BITUMINOUS SURFACE REMOVAL (VARIABLE DEPTH)	TEMPORARY RAMP	REMARKS
	SQ YD	SQ YD	SQ YD	SQ YD	
FAI 57					
RAMP F					
STA 4+70	88.0				
FAI 57 STAGE 5 PROJECT TOTAL	88.0	0.0	0.0	0.0	

REMOVAL - FAI 57 STAGE 5

LOCATION STATION TO STATION	RUBBLIZING PORTLAND CEMENT CONCRETE PAVEMENT	CORRUGATED MEDIAN REMOVAL	PAVEMENT REMOVAL	DRIVEWAY PAVEMENT REMOVAL	COMBINATION CURB AND GUTTER REMOVAL	MEDIAN SURFACE REMOVAL	REMOVAL OF EXISTING STRUCTURES NO. 5	REMOVAL OF EXISTING STRUCTURES NO. 6	REMARKS
	SQ YD	SQ FT	SQ YD	SQ YD	FOOT	SQ FT	EACH	EACH	
FAI 57									
SOUTHBOUND									
STA 1519+25 TO STA 1520+00			177.0						
STA 1520+00 TO STA 1520+50			108.0						
STA 1521+00 TO STA 1521+50			17.0						
STA 1521+50 TO STA 1522+15			118.0						
RAMP F									
STA 4+40 TO STA 9+70.88			944.0						
STA 9+70.88 TO STA 10+78.46			1,033.0						
LT STA 14+37.08 TO STA 15+81.2					250				
LT STA 15+51.42 TO STA 15+80.22					120				
LT STA 14+73.54 TO STA 15+76.42					241				
LT STA 14+68.67 TO STA 15+81.21					173				
RAMP FF									
STA 0+00 TO STA 1+00			601.0						
STA 0+34 TO STA 0+65						642			EXIST RAISED ISLAND
STA 0+34 TO STA 7+50			1,503.0						
STA 1+00 TO STA 7+87.55			1,222.0						
RT STA 0+34 TO STA 1+48									RT OF EXIST RAMP
RT STA 0+34 TO STA 1+45									LT OF EXIST RAMP
LT STA 0+34 TO STA 1+80									LT OF EXIST RAISED ISLAND
FAI 57 STAGE 5 PROJECT TOTALS	0.0	0.0	5,723.0	0.0	784.0	642.0	0.0	0.0	

REVISIONS NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE

SCALE: VERT. HORIZ.
DATE

DRAWN BY JCK
CHECKED BY

PLOT DATE = 1/16/2007
FILE NAME = c:\projects\d902802\old13\old13sch.m32
PLOT SCALE = 50.0000 ' / IN.
USER NAME = kranzjo