CONTRACT NO. 98950

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	WILLIAMSON	917	418
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

* FAI 57 & FAU 9629 (OLD IL 13)
** (X1-6-2)VB-2, (X1-6)HBK-2

BITUMINOUS PAVEMENT - FAI 57 STAGE 6

LOCATION STATION TO STATION	POLYMERIZED BITUMINOUS CONCRETE SURFACE COURSE SUPERPAVE MIX D, N105	POLYMERIZED BITUMINOUS CONCRETE SURFACE COURSE SUPERPAVE MIX E, N105	POLYMERIZED BITUMINOUS CONCRETE BINDER COURSE SUPERPAVE IL-19.0, N105	BITUMINOUS CONCRETE BINDER COURSE SUPERPAVE IL-19.0, N90		BITUMINOUS CONCRETE PAVEMENT (FULL DEPTH) SUPERPAVE, 14 1/4" FOR INFORMATION ONLY				STABILIZED SUB-BASE 4"	STABILIZED SUB-BASE (VARIABLE DEPTH)	SUB-BASE GRANULAR MATERIAL, 6"	SUB-BASE GRANULAR MATERIAL, 10"	SUB-BASE GRANULAR MATERIAL, TYPE C	BITUMINOUS MATERIAL (PRIME COAT)	AGGREGATE (PRIME COAT)	MATERIAL TRANSFER DEVICE
				INFO. ONLY		POLY BIT SURFACE MIX D, N105 1 1/2"	POLY BIT BINDER IL-19.0, N105 2 1/4"	BIT BINDER IL-19.0, N90 10 1/2"									
	TON	TON	TON	THICKNESS (IN.)	TON	TON	TON	TON	SQ YD	SQ YD	TON	SQ YD	SQ YD	TON	GALLON	TON	TON
FAI 57																	
NORTHBOUND																	
LT STA 1523+45 TO STA 1524+00			22.0	VAR	74.0								19.0				
LT STA 1523+45 TO STA 1524+00				5"	5.0												
LT STA 1524+00 TO STA 1524+50			20.0	VAR	77.0												
LT STA 1524+00 TO STA 1525+00				5"	9.0								34.0				
LT STA 1524+50 TO STA 1525+00			20.0	VAR	86.0												
LT STA 1525+00 TO STA 1525+86			33.0	VAR	150.0												
LT STA 1525+00 TO STA 1525+86				5"	8.0								29.0				
LT STA 1525+50 TO STA 1525+86												44.0					
LT STA 1525+00 TO STA 1526+86															6		
RAMP E																	
STA 0+32 TO STA 2+00										636.0							
STA 2+00 TO STA 3+48										263.0							
STA 3+48 TO STA 5+00						23.0	34.0	175.0	271.0						87		
STA 5+00 TO STA 6+38						21.0	31.0	159.0	245.0						79		
STA 6+38 TO STA 9+00						39.0	59.0	302.0	466.0						149		
STA 9+00 TO STA 12+59						54.0	81.0	423.0	638.0						204		
STA 16+70 TO STA 19+91										1,577.0							
R STA 0+32 TO STA 1+00														33	26		
R STA 1+00 TO STA 2+00														47	20		
R STA 2+00 TO STA 4+26														58	48		
R STA 4+26 TO STA 7+30														78	65		
R STA 7+30 TO STA 9+43														54	45		
R STA 9+43 TO STA 10+25														21	18		
R STA 10+25 TO STA 12+58														83	75		
LT STA 6+38 TO STA 7+31														16	13		
LT STA 7+31 TO STA 9+43														38	30		
LT STA 9+43 TO STA 12+58														59	47		
RAMP EE																	
STA 8+67 TO STA 12+00						50.0	75.0	383.0	592.0						189		
STA 12+00 TO STA 14+25						34.0	51.0	255.0	400.0						128		
STA 14+25 TO STA 15+38						17.0	26.0	130.0	201.0						64		
STA 15+38 TO STA 16+70						12.0	30.0	152.0	235.0						75		
R STA 8+97 TO STA 9+62														17	14		
R STA 9+62 TO STA 12+64														78	65		
R STA 12+64 TO STA 16+00														86	72		
R STA 16+00 TO STA 19+82															94		
R STA 12+64 TO STA 16+00																	
LT STA 8+97 TO STA 14+25														95	75		
LT STA 8+97 TO STA 9+63															9		
LT STA 9+63 TO STA 12+64															42		
FAI 57 STAGE 6 PROJECT TOTALS	**0**	**0**	**95**		**409**				**3,048**	**2,476**	**0**	**44**	**82**	**772**	**1,739**	**0**	**0**

REVISIONS NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE

SCALE: VERT.
HORIZ.
DATE

DRAWN BY JCK
CHECKED BY

PLOT DATE = 1/15/2007
FILE NAME = N:\Projects\d98028\x\d98028x01d03sch.dgn
PLOT SCALE = 50.0000 ' / IN.
USER NAME = kranz.jo