CONTRACT NO. 98950

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	WILLIAMSON	917	420
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

* FAI 57 & FAU 9629 (OLD IL 13)
** (X1-6-2)VB-2, (X1-6)HBK-2

SHOULDERS - FAI 57 STAGE 6

LOCATION STATION TO STATION	PAVED SHOULDER REMOVAL SQ YD	BITUMINOUS SHOULDERS, SUPERPAVE TON	BITUMINOUS SHOULDERS SUPERPAVE 6 1/2" SQ YD	BITUMINOUS SHOULDERS SUPERPAVE 8" SQ YD	BITUMINOUS SHOULDERS SUPERPAVE 8 1/2" SQ YD	BITUMINOUS SHOULDERS SUPERPAVE 9 1/2" SQ YD	AGGREGATE SHOULDERS, TYPE A 8" SQ YD	AGGREGATE SHOULDERS, TYPE B TON	BITUMINOUS MATERIALS (PRIME COAT) GALLON	SHOULDER RUMBLE STRIP FOOT	REMARKS
FAI 57											
NORTHBOUND											
LT (OUTSIDE SHOULDER)											
STA. 1523+45 TO STA. 1524+00	13	9									
STA. 1524+00 TO STA. 1524+50		10									
STA. 1524+00 TO STA. 1525+00	23										
STA. 1524+50 TO STA. 1525+00		11									
STA. 1525+00 TO STA. 1525+86	20			19							
RAMP E											
PAVED AREA FOR DELINIATORS	163										25 LOCATIONS - PAVED SHOULDER REMOVAL = 6.5 SQ YDS EACH
RT											
STA. 0+00 TO STA. 1+00				82							
STA. 0+33.95 TO STA. 6+38.17							134.0				
STA. 1+00 TO STA. 2+00				63							
STA. 1+36.42 TO STA. 4+00	234										
STA. 2+00 TO STA. 4+25.67				149							
STA. 4+25.67 TO STA. 7+30.38				203							
STA. 6+38.17 TO STA. 12+73.68							141.5				
STA. 7+30.38 TO STA. 9+42.77				139							
STA. 4+00 TO STA. 10+00	533										
STA. 9+42.77 TO STA. 10+25				55							
STA. 10+00 TO STA. 12+21.27	197										
STA. 10+25 TO STA. 12+58				234							
LT											
STA. 1+32.15 TO STA. 4+00	119										
STA. 4+00 TO STA. 10+00	267										
STA. 6+38.17 TO STA. 12+73.68							141.5				
STA. 6+38.21 TO STA. 7+30.83				39							
STA. 7+30.83 TO STA. 9+42.77				94							
STA. 9+42.77 TO STA. 12+73.61				147							
STA. 10+00 TO STA. 12+23.99	100										
RAMP EE											
PAVED AREA FOR DELINIATORS	156										29 LOCATIONS - PAVED SHOULDER REMOVAL = 5.4 SQ YDS EACH
RT											
STA. 0+00 TO STA. 4+00	178										
STA. 4+00 TO STA. 10+40.58	285										
STA. 8+96.5 TO STA. 9+62.12				44							
STA. 8+96.74 TO STA. 14+28.85							118.5				
STA. 9+62.12 TO STA. 12+64.4				202							
STA. 12+64.4 TO STA. 15+99.77				224							
STA. 15+99.77 TO STA. 19+81.44				295							
STA. 14+28.85 TO STA. 19+91.44							125.0				
LT											
STA. 0+00 TO STA. 4+00	356										
STA. 4+00 TO STA. 10+22.81	554										
STA. 8+96.5 TO STA. 14+24.88				235							
STA. 8+96.74 TO STA. 9+62.12				29							
STA. 8+96.74 TO STA. 14+28.85							118.5				
STA. 9+62.12 TO STA. 12+64.4				130							
FAI 57 STAGE 6 PROJECT TOTALS	**3,198.0**	**30.0**	**0.0**	**2,383.0**	**0.0**	**0.0**	**779.0**	**0.0**	**0.0**	**0.0**	

REVISIONS NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE

SCALE: VERT.
HORIZ.
DATE

DRAWN BY JCK
CHECKED BY

PLOT DATE = 1/15/2007
FILE NAME = c:\projects\d982882\old13\old13sch.m32
PLOT SCALE = 50.0000 ' / IN.
USER NAME = krenzjo