CONTRACT NO. 98950

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	WILLIAMSON	917	490
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

* FAI 57 & FAU 9629 (OLD IL 13)
** (XI-6-2)VB-2, (XI-6)HBK-2

SURFACE REMOVAL - FAI 57 STAGE 7

LOCATION STA TO STA	BITUMINOUS SURFACE REMOVAL - BUTT JOINT SQ YD	BITUMINOUS SURFACE REMOVAL 5" SQ YD	BITUMINOUS SURFACE REMOVAL (VARIABLE DEPTH) SQ YD	TEMPORARY RAMP SQ YD	REMARKS
FAI 57					
NORTHBOUND					
STA 1513+00 TO STA 1513+65		188.0			
STA 1513+65 TO STA 1515+56		467.0			
STA 1517+63 TO STA 1528+73		2,714.0			
STA 1528+73 TO STA 1529+04		83.0			
STA 1530+90 TO STA 1531+19		78.0			
STA 1531+19 TO STA 1538+90		1,885.0			
STA 1538+90 TO STA 1541+33		648.0			
FAI 57					
SOUTHBOUND					
STA 1511+00 TO STA 1515+53		1,108.0			
STA 1517+61 TO STA 1528+70		2,711.0			
STA 1528+70 TO STA 1529+02		86.0			
STA 1530+88 TO STA 1531+19		83.0			
STA 1531+19 TO STA 1536+00		1,176.0			
STA 1536+00 TO STA 1536+85		217.0			
STA 1536+85 TO STA 1542+33		1,462.0			
STA 1542+78	122.0				
FAI 57 STAGE 7 PROJECT TOTAL	122.0	12,906.0	0.0	0.0	

REVISIONS NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE

SCALE: VERT. HORIZ.
DATE
DRAWN BY JCK
CHECKED BY

PLOT DATE = 10/26/2006
FILE NAME = c:\projects\d902802\old13\old13sch.m32
PLOT SCALE = 50.0000 ' / IN.
USER NAME = kranzjo