CONTRACT NO. 98950

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	WILLIAMSON	917	510
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

* FAI 57 & FAU 9629 (OLD IL 13)
** (X1-6-2)VB-2, (X1-6)HBK-2

EARTHWORK - FAI 57 STAGE 7A

LOCATION STA TO STA	EARTH EXCAVATION	FOR INFORMATION ONLY					BORROW EXCAVATION	REMARKS
		AVERAGE SHRINKAGE FACTOR	EARTH EXCAVATION (ADJUSTED)	EMBANKMENT	EARTHWORK BALANCE WASTE (+) SHORTAGE (-)	BORROW SWELL FACTOR		
	CU YD	%	CU YD	CU YD	CU YD	%	CU YD	
FAI 57								
LT STA 1506+70 TO STA 1513+10	0	36.8%	0	80	-80			
FAI 57 STAGE 7 PROJECT TOTAL	0	36.8%	0	80	-80	25.0%	100	

REVISIONS NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE

SCALE: VERT. HORIZ.

DATE

DRAWN BY JCK

CHECKED BY

PLOT DATE = 1/16/2007
FILE NAME = c:\pro_docs\c98950\sld13\sld13schu.dgn
PLOT SCALE = 50.0000 ' / IN.
USER NAME = kevanjp